



COUNTY OF SANTA CRUZ

PLANNING DEPARTMENT

701 OCEAN STREET, 4TH FLOOR, SANTA CRUZ, CA 95060
(831) 454-2580 FAX: (831) 454-2131 TDD: (831) 454-2123
TOM BURNS, PLANNING DIRECTOR

NOTICE OF ENVIRONMENTAL REVIEW PERIOD

SANTA CRUZ COUNTY

APPLICANT: Steve Wiesner of SC County Department of Public Works

APPLICATION NO.: 08-0099

APN: N. Rodeo Gulch (Post Mile Marker 4.35)

The Environmental Coordinator has reviewed the Initial Study for your application and made the following preliminary determination:

XX Negative Declaration
(Your project will not have a significant impact on the environment.)

XX Mitigations will be attached to the Negative Declaration.

 No mitigations will be attached.

 Environmental Impact Report
(Your project may have a significant effect on the environment. An EIR must be prepared to address the potential impacts.)

As part of the environmental review process required by the California Environmental Quality Act (CEQA), this is your opportunity to respond to the preliminary determination before it is finalized. Please contact Matt Johnston, Environmental Coordinator at (831) 454-3201, if you wish to comment on the preliminary determination. Written comments will be received until 5:00 p.m. on the last day of the review period.

Review Period Ends: **May 28, 2008**

Bob Loveland
Staff Planner

Phone: 454-3163

Date: April 22, 2008

NAME : N. Rodeo Gulch 4.35
APPLICATION: 08-0099
A.P.N: County Right of Way

NEGATIVE DECLARATION MITIGATIONS

- A. In order to ensure that mitigation measures B through D are communicated to the crew members responsible for constructing the project and are properly implemented, the Department of Public Works (DPW) shall organize a pre-construction meeting on the site to review the mitigation measures. The following parties shall attend: DPW project engineer, project crew supervisor, project biologists and Environmental Planning staff. The disturbance envelope will be verified, silt fence will be inspected, erosion control plan verified, dewatering and fish removal plan reviewed, and the results of pre-construction wildlife surveys will be collected at that time.
- B. In order to prevent adverse impacts to California red legged frogs (*Rana aurora draytonii*) (CLRF) and foothill yellow-legged frogs (*Rana boylei*), a qualified wildlife biologist shall perform pre-construction surveys and conduct an educational session with all work crewmembers prior to disturbance. If either species of frog are present, all vegetation removal and disturbance shall only occur in the presence of a qualified biological resource monitor. If CLRF are identified in the work area during the project the monitor shall halt activity and contact the U.S. Fish and Wildlife Service for direction and recommendations to avoid take of the species.
- C. In order to prevent erosion and sedimentation of the creek, prior to disturbance DPW shall implement the erosion control plan reviewed and approved by Environmental Planning staff. At the pre-construction meeting, Environmental Planning staff shall confirm that access to the work area is from the top of the bank and construction will be accomplished per the erosion control plan, confirm that the spoils storage area is away from the creek bank and protected from erosion, and confirm the silt fencing and other erosion control features are properly installed.
- D. To minimize noise impacts on surrounding properties to a less than significant level during construction, construction shall be limited to the time between 8:00 A.M. and 5:00 P.M. weekdays.



Environmental Review Initial Study

Application Number: **08-0099**

Date: April 3, 2008
Staff Planner: Bob Loveland

I. OVERVIEW AND ENVIRONMENTAL DETERMINATION

APPLICANT: County of Santa Cruz
(DPW)

APN: N. Rodeo Gulch (Post Mile Marker
4.35)

CONTACT: Steve Wiesner
(831) 454-2160

SUPERVISORAL DISTRICT: First (Janet
Beautz)

LOCATION:

The project area is located on N. Rodeo Gulch Road at Post Mile-Marker 4.35.

SUMMARY PROJECT DESCRIPTION:

Winter stormwater flows within Rodeo Gulch Creek (2005 to 2006) eroded the toe of the roadway embankment causing the slope embankment and associated roadway to fail into the stream channel (FEMA DR- CA 1628). In order to restore the road embankment and associated roadway back to pre-disaster configuration, the following activities need to be completed: construct a new retaining wall; place Rock Slope Protection (RSP) at the toe of the slope; revegetate restored roadway embankment; place new asphalt pavement and install a new steel guard rail.

ALL OF THE FOLLOWING POTENTIAL ENVIRONMENTAL IMPACTS ARE EVALUATED IN THIS INITIAL STUDY. CATEGORIES THAT ARE MARKED HAVE BEEN ANALYZED IN GREATER DETAIL BASED ON PROJECT SPECIFIC INFORMATION.

<input type="checkbox"/> Geology/Soils	<input checked="" type="checkbox"/> Noise
<input type="checkbox"/> Hydrology/Water Supply/Water Quality	<input checked="" type="checkbox"/> Air Quality
<input checked="" type="checkbox"/> Biological Resources	<input type="checkbox"/> Public Services & Utilities
<input checked="" type="checkbox"/> Energy & Natural Resources	<input type="checkbox"/> Land Use, Population & Housing
<input type="checkbox"/> Visual Resources & Aesthetics	<input type="checkbox"/> Cumulative Impacts
<input type="checkbox"/> Cultural Resources	<input type="checkbox"/> Growth Inducement
<input type="checkbox"/> Hazards & Hazardous Materials	<input checked="" type="checkbox"/> Mandatory Findings of Significance
<input checked="" type="checkbox"/> Transportation/Traffic	

DISCRETIONARY APPROVAL(S) BEING CONSIDERED

<input type="checkbox"/> General Plan Amendment	<input type="checkbox"/> Grading Permit
<input type="checkbox"/> Land Division	<input checked="" type="checkbox"/> Riparian Exception
<input type="checkbox"/> Rezoning	<input type="checkbox"/> Other:
<input type="checkbox"/> Development Permit	<input type="checkbox"/>
<input type="checkbox"/> Coastal Development Permit	<input type="checkbox"/>

NON-LOCAL APPROVALS

Other agencies that must issue permits or authorizations:

California Department of Fish & Game
National Marine Fisheries Service
U.S. Fish & Wildlife Service
Army Corps of Engineers


ENVIRONMENTAL REVIEW ACTION

On the basis of this Initial Study and supporting documents:

☐ I find that the proposed project COULD NOT have a significant effect on the environment, and a NEGATIVE DECLARATION will be prepared.

☒ I find that although the proposed project could have a significant effect on the environment, there will not be a significant effect in this case because the attached mitigation measures have been added to the project. A MITIGATED NEGATIVE DECLARATION will be prepared.

☐ I find that the proposed project MAY have a significant effect on the environment, and an ENVIRONMENTAL IMPACT REPORT is required.


Matt Johnston

4/24/08
Date

For: Claudia Slater
Environmental Coordinator

II. BACKGROUND INFORMATION

EXISTING SITE CONDITIONS:

Parcel Size: NA

Existing Land Use: County maintained road adjacent to an established riparian corridor.

Vegetation: Slope in area affected by project: ☐ 0 - 30% ☒ 31 - 100%

Nearby Watercourse: Rodeo Creek Gulch

Distance To: Road surface is approximately 45 feet above the creek channel.

ENVIRONMENTAL RESOURCES AND CONSTRAINTS

Groundwater Supply: No

Water Supply Watershed: No

Groundwater Recharge: Yes

Timber or Mineral: No

Agricultural Resource: No

Biologically Sensitive Habitat: Yes

Fire Hazard: No

Floodplain: No

Erosion: No

Landslide: Yes

Liquefaction: No

Fault Zone: No

Scenic Corridor: No

Historic: No

Archaeology: No

Noise Constraint: No

Electric Power Lines: Yes

Solar Access: Yes

Solar Orientation: NA

Hazardous Materials: No

SERVICES

Fire Protection: Central Fire

School District: Soquel Union

Sewage Disposal: NA

Drainage District: Zone 5

Project Access: Post Mile-Marker 4.35

Water Supply: No

PLANNING POLICIES

Zone District: Residential Agriculture

General Plan: Suburban Residential

Urban Services Line: ☐ Inside

Coastal Zone: ☐ Inside

Special Designation: No

☒ Outside

☒ Outside

PROJECT SETTING AND BACKGROUND:

The project area is located within the county right-of-way along N. Rodeo Gulch Road adjacent to Post Mile Marker 4.35 (Attachment 1). The topography of the site includes a low to moderate gradient stream located within a deeply incised channel and flanked by steep vegetated slopes. Although the area damaged by the slope failure has minimal vegetative cover, the surrounding slopes are covered with well established riparian vegetation: white alder (*Alnus rhombifolia*), willow (*Salix sp.*), California bay (*Umbellularia californica*), blackberry (*Rubus sp.*), Poison oak (*Toxicodendron diversilobum*) and five-finger fern (*Adiantum aleuticum*). A biotic assessment has been completed and has identified that the project area provides suitable habitat for two federally listed species: Tidewater Goby (*Eucyclogobius newberryi*) listed as endangered and California Red-legged Frog (*Rana aurora draytonii*) listed as threatened.

During winter flood events of 2005 to 2006, heavy stormwater flows within Rodeo Gulch Creek washed out the toe of the roadway embankment causing total failure of the road embankment and half the road width and shoulder of Rodeo Gulch Road. The County of Santa Cruz requested public assistance to reconstruct the failed roadway through the Federal Emergency Management Agency (FEMA) and was approved (FEMA DR- CA 1628).

DETAILED PROJECT DESCRIPTION:

The repair work involved in reestablishing and stabilizing this section of county maintained roadway includes constructing: a steel soldier pile and timber lagging retaining wall (64 linear feet); toe slope protection between the creek channel and the base of the retaining wall (placement of 426 tons of Rock Slope Protection (RSP); reconstruct roadway and shoulder and construct a metal beam guardrail (Attachment 2 Sheet 2). The construction area is approximately 150 feet long by 50 feet wide. Two construction staging areas will be located along Rodeo Gulch Road (adjacent to the limits of construction). A temporary construction access road will be installed, northwest corner of the construction area, in order to complete the necessary earthwork (620 cubic yards) for the new retaining wall, placement of the RSP and reconstructing the failed roadway and shoulder. The construction access road will be removed upon project completion and appropriate Best Management Practices (BMP's) will be implemented to stabilize areas of bare soil. A limited section of stream channel will need to be diverted and dewatered in order to properly install the RSP (Attachment 2 Sheet 5). The dewatering process will be achieved by utilizing temporary dams, diversion pipe and portable pump(s). The placement of silt fencing, straw wattles and other BMP measures will be employed during construction activities in order to safeguard water quality and federally listed species (Attachment 2 Sheet 7). The implementation of the Erosion control and Revegetation Plans will provide short-term slope stability for areas disturbed during construction activities and long-term slope stability for the roadway embankment below the new retaining wall (Attachment 2 Sheets 6 & 7).

III. ENVIRONMENTAL REVIEW CHECKLIST

A. Geology and Soils

Does the project have the potential to:

1. Expose people or structures to potential adverse effects, including the risk of material loss, injury, or death involving:

- A. Rupture of a known earthquake fault, as delineated on the most recent Alquist-Priolo Earthquake Fault Zoning Map issued by the State Geologist for the area or as identified by other substantial evidence?

_____	_____	_____	<u>X</u>
-------	-------	-------	----------

- B. Seismic ground shaking?

_____	_____	<u>X</u>	_____
-------	-------	----------	-------

The project has been engineered to minimize damage related to seismic shaking. A soils report completed by a licensed civil engineer has been completed for this project (Terra Consultants, dated 2008).

- C. Seismic-related ground failure, including liquefaction?

_____	_____	<u>X</u>	_____
-------	-------	----------	-------

Refer to section "A.1B" above.

- D. Landslides?

_____	_____	<u>X</u>	_____
-------	-------	----------	-------

2. Subject people or improvements to damage from soil instability as a result of on- or off-site landslide, lateral spreading, to subsidence, liquefaction, or structural collapse?

_____	_____	<u>X</u>	_____
-------	-------	----------	-------

Refer to section "A.1B" above.

3. Develop land with a slope exceeding 30%?

_____	_____	_____	<u>X</u>
-------	-------	-------	----------

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

4. Result in soil erosion or the substantial loss of topsoil?

_____	_____	X	_____
-------	-------	---	-------

The streambanks and soils in the project area are prone to erosion. Appropriate soil erosion and sediment control Best Management Practices (BMP's) such as straw wattles, silt fencing, etc. are included in the project and will be used and maintained during construction. Following construction, hydroseeding of native seed, live staking of willows, and placement of biodegradable erosion control fabric will be applied to all disturbed areas including streambanks, access routes and staging areas (Attachment 2 Sheet 6).

5. Be located on expansive soil, as defined in Table 18-1-B of the Uniform Building Code(1994), creating substantial risks to property?

_____	_____	_____	X
-------	-------	-------	---

6. Place sewage disposal systems in areas dependent upon soils incapable of adequately supporting the use of septic tanks, leach fields, or alternative waste water disposal systems?

_____	_____	_____	X
-------	-------	-------	---

7. Result in coastal cliff erosion?

_____	_____	_____	X
-------	-------	-------	---

B. Hydrology, Water Supply and Water Quality

Does the project have the potential to:

1. Place development within a 100-year flood hazard area?

_____	_____	X	_____
-------	-------	---	-------

The project area is not mapped by the Federal Emergency Management Agency (FEMA) as being within a 100-year flood hazard area. The stream bank will be restored to its approximate pre-disturbed location.

2. Place development within the floodway resulting in impedance or redirection of flood flows?

_____	_____	X	_____
-------	-------	---	-------

The Rock Slope Protection (RSP) placed near the toe of the stream channel will be softened with willow staking (Attachment 2 Sheet 6).

	Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
3. Be inundated by a seiche or tsunami?	_____	_____	_____	<u>X</u>
4. Deplete groundwater supplies or interfere substantially with groundwater recharge such that there would be a net deficit, or a significant contribution to an existing net deficit in available supply, or a significant lowering of the local groundwater table?	_____	_____	_____	<u>X</u>
5. Degrade a public or private water supply? (Including the contribution of urban contaminants, nutrient enrichments, or other agricultural chemicals or seawater intrusion).	_____	_____	<u>X</u>	_____
No new contaminants associated with this project.				
6. Degrade septic system functioning?	_____	_____	_____	<u>X</u>
7. Alter the existing drainage pattern of the site or area, including the alteration of the course of a stream or river, in a manner that could result in flooding, erosion, or siltation on or off-site?	_____	_____	<u>X</u>	_____
Two temporary dams and a diversion pipe will be placed in the project area in order to dewater the stream (Attachment 2 Sheet 5) temporarily and allow for the installation of "Rock Slope Protection" (RSP) at the toe of the embankment. Upon completion of the placement of RSP, the dams and diversion pipe will be removed and the water will reoccupy the pre-construction stream alignment.				
8. Create or contribute runoff that would exceed the capacity of existing or planned storm water drainage systems, or create additional source(s) of polluted runoff?	_____	_____	<u>X</u>	_____

No newly collected runoff is proposed as part of this project.

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

9. Contribute to flood levels or erosion in natural watercourses by discharges of newly collected runoff?

		X	
--	--	---	--

Refer to "B. 8" above.

10. Otherwise substantially degrade water supply or quality?

	X		
--	---	--	--

The direct impacts to water quality such as sedimentation and increased turbidity will be minimized by dewatering and diverting the stream during construction. An erosion/ sediment control plan has been approved that utilizes appropriate BMP's (silt fencing, straw wattles). Following construction, native seed, mulch and/or biodegradable erosion control fabric will be applied to all disturbed areas (Attachment 2 Sheet 6).

C. Biological Resources

Does the project have the potential to:

1. Have an adverse effect on any species identified as a candidate, sensitive, or special status species, in local or regional plans, policies, or regulations, or by the California Department of Fish and Game, or U.S. Fish and Wildlife Service?

	X		
--	---	--	--

A biotic assessment was completed by Nationwide Infrastructure Support Technical Assistance Consultants (NISTAC) in May 2007. The report has identified that the project does have the potential to negatively impact two federally listed species: Tidewater Goby (*Eucyclogobius newberryi*), which is listed as endangered and California Red-legged Frog (*Rana aurora draytonii*), which is listed as threatened. According to the assessment, the Tidewater Goby is not presumed to be in the project area, due to lack of suitable habitat, but has been documented further downstream in Corcoran Lagoon. The lagoon is located approximately 3 miles downstream and provides the brackish water environment the species requires. The potential impact to the species is from degradation of water quality (release of excessive amounts of sediments due to construction activities and/or release of petroleum products (fuels, oils). The direct impacts to water quality such as sedimentation and increased turbidity will be minimized by dewatering and diverting the stream during construction. An erosion/ sediment control plan has been developed using appropriate soil erosion and sediment control BMPs to address these concerns. Following construction activities native seed, container stock and biodegradable erosion control fabric will be applied to all disturbed areas.

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

California Red-legged Frogs have not been formally documented within the project area, but have been approximately 4.5 miles west of the area. Since there is suitable habitat present within the project area and documentation of the species within its range has been recorded, presence is assumed. The mitigations contained within "Section Four" (Avoidance & Minimization Measures) of the biotic assessment (Attachment 3) will be implemented in order to provide an acceptable level of protection to each of the two listed species.

2. Have an adverse effect on a sensitive biotic community (riparian corridor), wetland, native grassland, special forests, intertidal zone, etc.)?

X

The project site is within the riparian corridor and sensitive habitat as defined in the Santa Cruz County Code Sections 16.30 and 16.32, respectively; and within the jurisdiction of the California Department of Fish and Game's Stream and Lake Bed Alteration Program (Section 1600). The proposed project will result in a temporary disturbance of riparian and aquatic habitat by heavy equipment accessing and working within the project area. Riparian and sensitive habitat disturbed during construction will be revegetated with locally appropriate native species. The project proposes to remove one eucalyptus tree (non-native). Hydroseeding of native grass species, and installation of biodegradable erosion control fabric will be applied to all disturbed areas (Attachment 2 Sheet 6).

3. Interfere with the movement of any native resident or migratory fish or wildlife species, or with established native resident or migratory wildlife corridors, or impede the use of native or migratory wildlife nursery sites?

X

The proposed project will require the temporary dewatering of the stream. Dewatering is necessary to complete various aspects of construction and to minimize potential impacts from release of sediment and other materials that may be deleterious to the stream environment. The biological assessment completed by Nationwide Infrastructure Support Technical Assistance Consultants (NISTAC), has determined that Tidewater Gobies are not present in this reach of the stream due to lack of adequate habitat. The presence of California Red-legged Frogs has been assumed because of adequate habitat and recorded sitings of the species within the project area. The implementation of the mitigations contained within the biotic assessment will reduce potential impacts to less than significant.

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

4. Produce nighttime lighting that will illuminate animal habitats?

_____	_____	X	_____
-------	-------	---	-------

Construction activities are limited to daytime hours only so nighttime lighting will not be required.

5. Make a significant contribution to the reduction of the number of species of plants or animals?

_____	_____	X	_____
-------	-------	---	-------

The placement of approved Best Management Practices (BMP's) and implementation of identified mitigations will reduce potential impacts to less than significant.

6. Conflict with any local policies or ordinances protecting biological resources (such as the Significant Tree Protection Ordinance, Sensitive Habitat Ordinance, provisions of the Design Review ordinance protecting trees with trunk sizes of 6 inch diameters or greater)?

_____	_____	X	_____
-------	-------	---	-------

The project sites are within the riparian corridor and sensitive habitat as defined in the Santa Cruz County Code Sections 16.30 and 16.32, respectively; and within the jurisdiction of the California Department of Fish and Game's Stream and Lake Bed Alteration Program (Section 1600). The proposed project will result in temporary disturbance of riparian and aquatic habitat by heavy equipment accessing and working in the project area. Riparian and sensitive habitat disturbed during construction will be treated with appropriate Best Management Practices (BMP's) and revegetated with locally appropriate native species (Attachment 2 Sheets 6 & 7).

7. Conflict with the provisions of an adopted Habitat Conservation Plan, Biotic Conservation Easement, or other approved local, regional, or state habitat conservation plan?

_____	_____	_____	X
-------	-------	-------	---

D. Energy and Natural Resources

Does the project have the potential to:

1. Affect or be affected by land designated as "Timber Resources" by the General Plan?

_____	_____	_____	X
-------	-------	-------	---

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

- | | | | | | |
|----|--|-------|-------|-------|-------------|
| 2. | Affect or be affected by lands currently utilized for agriculture, or designated in the General Plan for agricultural use? | _____ | _____ | _____ | _____X_____ |
| 3. | Encourage activities that result in the use of large amounts of fuel, water, or energy, or use of these in a wasteful manner? | _____ | _____ | _____ | _____X_____ |
| 4. | Have a substantial effect on the potential use, extraction, or depletion of a natural resource (i.e., minerals or energy resources)? | _____ | _____ | _____ | _____X_____ |

E. Visual Resources and Aesthetics

Does the project have the potential to:

- | | | | | | |
|----|---|-------|-------|-------|-------------|
| 1. | Have an adverse effect on a scenic resource, including visual obstruction of that resource? | _____ | _____ | _____ | _____X_____ |
|----|---|-------|-------|-------|-------------|

Neither the stream nor the road is designated a scenic resource area.

- | | | | | | |
|----|--|-------|-------|-------|-------------|
| 2. | Substantially damage scenic resources, within a designated scenic corridor or public view shed area including, but not limited to, trees, rock outcroppings, and historic buildings? | _____ | _____ | _____ | _____X_____ |
|----|--|-------|-------|-------|-------------|

Neither the stream nor the road is designated a scenic resource area.

- | | | | | | |
|----|--|-------|-------|-------------|-------|
| 3. | Degrade the existing visual character or quality of the site and its surroundings, including substantial change in topography or ground surface relief features, and/or development on a ridge line? | _____ | _____ | _____X_____ | _____ |
|----|--|-------|-------|-------------|-------|

Heavy equipment will be operating in and around the riparian zone and streambed for approximately 90 days. The effect on aesthetics will be temporary and will be visible from the County right-of-way on North Rodeo Gulch Road. Soils disturbed by equipment access and/or construction will be revegetated with native grass species

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

and container stock. The planting of willows through the rock slope protection and additional revegetation work completed on the reconstructed roadway embankment will assist in masking the presence of artificial surfaces once established (Attachment 2 Sheet 6 & 7).

- | | | | | | |
|----|--|-------|-------|-------|-------------|
| 4. | Create a new source of light or glare which would adversely affect day or nighttime views in the area? | _____ | _____ | _____ | _____X_____ |
| 5. | Destroy, cover, or modify any unique geologic or physical feature? | _____ | _____ | _____ | _____X_____ |

F. Cultural Resources

Does the project have the potential to:

- | | | | | | |
|----|---|-------|-------|-------|-------------|
| 1. | Cause an adverse change in the significance of a historical resource as defined in CEQA Guidelines 15064.5? | _____ | _____ | _____ | _____X_____ |
|----|---|-------|-------|-------|-------------|

Not mapped or expected.

- | | | | | | |
|----|--|-------|-------|-------|-------------|
| 2. | Cause an adverse change in the significance of an archaeological resource pursuant to CEQA Guidelines 15064.5? | _____ | _____ | _____ | _____X_____ |
|----|--|-------|-------|-------|-------------|

Not mapped or expected.

- | | | | | | |
|----|---|-------|-------|-------|-------------|
| 3. | Disturb any human remains, including those interred outside of formal cemeteries? | _____ | _____ | _____ | _____X_____ |
| 4. | Directly or indirectly destroy a unique paleontological resource or site? | _____ | _____ | _____ | _____X_____ |

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

G. Hazards and Hazardous Materials

Does the project have the potential to:

1. Create a significant hazard to the public or the environment as a result of the routine transport, storage, use, or disposal of hazardous materials, not including gasoline or other motor fuels?

_____	_____	_____X_____	_____
-------	-------	-------------	-------

Implementing the project will require use of heavy equipment in the riparian area and equipment will operate in the bed and banks of the stream channel. To reduce the potential of an accidental release of hazardous materials (fuel, hydraulic fluids) a Spill Prevention & Response Plan will be implemented to prepare for the unlikely event of a fuel or oil spill (Attachment 4).

2. Be located on a site which is included on a list of hazardous materials sites compiled pursuant to Government Code Section 65962.5 and, as a result, would it create a significant hazard to the public or the environment?

_____	_____	_____	_____X_____
-------	-------	-------	-------------

3. Create a safety hazard for people residing or working in the project area as a result of dangers from aircraft using a public or private airport located within two miles of the project site?

_____	_____	_____	_____X_____
-------	-------	-------	-------------

4. Expose people to electro-magnetic fields associated with electrical transmission lines?

_____	_____	_____	_____X_____
-------	-------	-------	-------------

5. Create a potential fire hazard?

_____	_____	_____	_____X_____
-------	-------	-------	-------------

6. Release bio-engineered organisms or chemicals into the air outside of project buildings?

_____	_____	_____	_____X_____
-------	-------	-------	-------------

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

H. Transportation/Traffic

Does the project have the potential to:

1. Cause an increase in traffic that is substantial in relation to the existing traffic load and capacity of the street system (i.e., substantial increase in either the number of vehicle trips, the volume to capacity ratio on roads, or congestion at intersections)?

_____	_____	X	_____
-------	-------	---	-------

The results of the project itself will not cause a foreseeable increase in traffic substantial to the existing traffic load and capacity of Rodeo Gulch Road. Temporary additional use by construction workers and haul trucks will occur. This impact is considered less than significant.

2. Cause an increase in parking demand which cannot be accommodated by existing parking facilities?

_____	_____	_____	X
-------	-------	-------	---

3. Increase hazards to motorists, bicyclists, or pedestrians?

_____	_____	X	_____
-------	-------	---	-------

The proposed project will comply with current road requirements to prevent potential hazards to motorists, bicyclists, and/or pedestrians. Temporary traffic control will decrease potential hazards for the duration of the project (Attachment 5).

4. Exceed, either individually (the project alone) or cumulatively (the project combined with other development), a level of service standard established by the county congestion management agency for designated intersections, roads or highways?

_____	_____	X	_____
-------	-------	---	-------

I. Noise

Does the project have the potential to:

1. Generate a permanent increase in ambient noise levels in the project vicinity above levels existing without the project?

_____	_____	X	_____
-------	-------	---	-------

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

2. Expose people to noise levels in excess of standards established in the General Plan, or applicable standards of other agencies?

X

There will be a temporary increase in noise in the project vicinity due to construction activities (e.g., operation of heavy equipment) that may exceed the County General Plan threshold of an hourly average of 50 Leq during the day. This impact will be mitigated by restricting the hours of operation to 8 AM through 5 PM, Monday through Friday when residents are frequently absent. Noise generated during construction will increase the ambient noise levels for adjoining areas. Given the limited duration of construction this impact it is considered to be less than significant.

3. Generate a temporary or periodic increase in ambient noise levels in the project vicinity above levels existing without the project?

X

Refer to I. 2. above.

J. Air Quality

Does the project have the potential to:

1. Violate any air quality standard or contribute substantially to an existing or projected air quality violation?

X

The North Central Coast Air Basin does not meet state standards for ozone and inhalable particulate matter (PM₁₀) (MBUAPCD, 2006). The regional pollutants of concern that would be emitted by the project are ozone precursors (Volatile Organic Compounds [VOCs] and nitrogen oxides [NOx]) and fugitive dust (PM₁₀). Ozone precursors and PM₁₀ would be emitted by onsite construction equipment and haul trucks delivering and removing materials from the project sites. Construction projects using typical construction equipment such as dump trucks, scrapers, bulldozers, compactors and front-end loaders which temporarily emit precursors of ozone [volatile organic compounds (VOC) or oxides of nitrogen (NOx)], are accommodated in the emission inventories of State-and federally-required air plans and would not have a significant impact on the attainment and maintenance of ozone standards. Project construction may result in a short-term, localized decrease in air quality due to generation of small amounts of dust. Standard dust control BMPs (e.g., periodic watering) are incorporated into the project, so air quality impacts associated with construction will be at a less than significant level.

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

2. Conflict with or obstruct implementation of an adopted air quality plan?

_____	_____	X	_____
-------	-------	---	-------

Refer to J. 1. above.

3. Expose sensitive receptors to substantial pollutant concentrations?

_____	_____	X	_____
-------	-------	---	-------

Construction may result in a short-term, localized decrease in air quality due to generation of dust. Standard dust control BMPs are also incorporated into the project, so air quality impacts associated with construction will be at a less than significant level.

4. Create objectionable odors affecting a substantial number of people?

_____	_____	X	_____
-------	-------	---	-------

The project would have less than significant impacts for the construction period, and would not create long-term objectionable odors.

K. Public Services and Utilities

Does the project have the potential to:

1. Result in the need for new or physically altered public facilities, the construction of which could cause significant environmental impacts, in order to maintain acceptable service ratios, response times, or other performance objectives for any of the public services:

a. Fire protection?	_____	_____	_____	X
b. Police protection?	_____	_____	_____	X
c. Schools?	_____	_____	_____	X
d. Parks or other recreational activities?	_____	_____	_____	X

	Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
e. Other public facilities; including the maintenance of roads?	_____	_____	_____	<u>X</u>
2. Result in the need for construction of new storm water drainage facilities or expansion of existing facilities, the construction of which could cause significant environmental effects?	_____	_____	_____	<u>X</u>
3. Result in the need for construction of new water or wastewater treatment facilities or expansion of existing facilities, the construction of which could cause significant environmental effects?	_____	_____	_____	<u>X</u>
4. Cause a violation of wastewater treatment standards of the Regional Water Quality Control Board?	_____	_____	_____	<u>X</u>
5. Create a situation in which water supplies are inadequate to serve the project or provide fire protection?	_____	_____	_____	<u>X</u>
6. Result in inadequate access for fire protection?	_____	_____	_____	<u>X</u>
7. Make a significant contribution to a cumulative reduction of landfill capacity or ability to properly dispose of refuse?	_____	_____	<u>X</u>	_____
The material excavated from the project area will be reused on site so there will be no material removed to the county landfill.				
8. Result in a breach of federal, state, and local statutes and regulations related to solid waste management?	_____	_____	_____	<u>X</u>

Significant Or Potentially Significant Impact	Less than Significant with Mitigation Incorporation	Less than Significant Or No Impact	Not Applicable
---	---	---	-------------------

L. Land Use, Population, and Housing

Does the project have the potential to:

- | | | | | | |
|----|--|--|--|---|---|
| 1. | Conflict with any policy of the County adopted for the purpose of avoiding or mitigating an environmental effect? | | | X | |
| 2. | Conflict with any County Code regulation adopted for the purpose of avoiding or mitigating an environmental effect? | | | X | |
| 3. | Physically divide an established community? | | | | X |
| 4. | Have a potentially significant growth inducing effect, either directly (for example, by proposing new homes and businesses) or indirectly (for example, through extension of roads or other infrastructure)? | | | | X |
| 5. | Displace substantial numbers of people, or amount of existing housing, necessitating the construction of replacement housing elsewhere? | | | | X |

M. Non-Local Approvals

Does the project require approval of federal, state, or regional agencies?

Yes X No

N. Mandatory Findings of Significance

1. Does the project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, substantially reduce the number or restrict the range of a rare or endangered plant, animal, or natural community, or eliminate important examples of the major periods of California history or prehistory?

Yes No X

2. Does the project have the potential to achieve short term, to the disadvantage of long term environmental goals? (A short term impact on the environment is one which occurs in a relatively brief, definitive period of time while long term impacts endure well into the future)

Yes No X

3. Does the project have impacts that are individually limited, but cumulatively considerable ("cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, and the effects of reasonably foreseeable future projects which have entered the Environmental Review stage)?

Yes No X

4. Does the project have environmental effects which will cause substantial adverse effects on human beings, either directly or indirectly?

Yes No X

TECHNICAL REVIEW CHECKLIST

	<u>REQUIRED</u>	<u>COMPLETED*</u>	<u>N/A</u>
Agricultural Policy Advisory Commission (APAC) Review	_____	_____	<u>X</u>
Archaeological Review	_____	_____	<u>X</u>
Biotic Report/Assessment	_____	<u>X</u>	_____
Geologic Hazards Assessment (GHA)	_____	_____	<u>X</u>
Geologic Report	_____	_____	<u>X</u>
Geotechnical (Soils) Report Terra Consultants Inc. (2008)	_____	<u>X</u>	_____
Riparian Pre-Site	_____	_____	<u>X</u>
Septic Lot Check	_____	_____	<u>X</u>
Other:	_____	_____	_____
	_____	_____	_____
	_____	_____	_____

Attachments:

1. Location Map
2. Project Plans (Sheets 1-7)
3. Avoidance and Minimization Measures (Section Four) contained within the biotic assessment.
4. Spill Prevention Control & Countermeasure Plan
5. Traffic Control Requirements

Other technical reports or information sources used in preparation of this Initial Study

1. Biotic Assessment completed by Nationwide Infrastructure Support Technical Assistance Consultants (NISTAC), dated May 2007. The document is on review at the Santa Cruz County Planning Department.
2. Biological Opinion completed by the U.S. Fish & Wildlife Service (USFWS) dated March 10, 2008. The document is on review at the County of Santa Cruz Planning Department.



Environmental Review Initial Study

ATTACHMENT 1 APPLICATION 08-0090 Location Map

Streams


— <all other values>

STREAMTYPE

— PERENNIAL


- - - - - INTERMITTENT


— SWALE




Map Created by
 Santa Cruz County Planning Dept
 April 2008





 DOUBLE CHANNEL STEEL WALER

 TIEBACK

TIEBACK	ELEV.
(A)	151.37
(B)	151.37
(C)	151.37
(D)	151.37
(E)	151.37
(F)	151.37
(G)	151.37

CABLE/ROD DIA.	MIN. UNBONDED LENGTH	*EST. BONDED LENGTH (6" DIA GROUT)	*EST. BONDED LENGTH (6" DIA GROUT)
1 INCH**	30 FT.	25 FT.	20 FT.

* NOTE: THE ABOVE SPECIFIED TIEBACK BONDING LENGTHS HAVE BEEN CALCULATED AND ARE THE ESTIMATED MINIMUM LENGTHS. ACTUAL BONDING LENGTHS MAY BE BASED ON PULL-OUT TEST RESULTS AT THE PROJECT LOCATION. TIEBACK TENSION DESIGN IS 98 KIPS. EACH TIEBACK SHALL BE FIELD TESTED TO 119 KIPS. FINAL CUTOFF TENSION SHALL BE A MINIMUM OF 80 KIPS. MAXIMUM ALLOWABLE VERTICAL AND HORIZONTAL TIEBACK DEFLECTION SHALL BE 5.2% FROM THE DESIGN ALIGNMENT OF TIEBACK TO FACE OF WALL. UNDER A PERFORMANCE TEST, CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR DETERMINING ZONE AND REQUIRED BONDING LENGTHS. THE CO. DESIGN ENGINEER SHALL BE NOTIFIED 24 HRS IN ADVANCE ON SITE DURING TIEBACK PONDING LENGTH TESTING.

AS DETERMINED BY INSTANT ANALYSIS

WORKING STRESS DESIGN

REINF. CONC.	f'_c	=	3,000 PSI
	f_c	=	1,350 PSI
STRUCTURAL STEEL	f_y	=	60,000 PSI
& BAR REINF. STEEL	f_u	=	34,000 PSI
TREATED TIMBER	f_c	=	1,750 PSI



DOUGLAS FIR #1
(MINIMUM)
Environmental Review Initial Study
ATTACHMENT 2 3 of 7
APPLICATION 04-0099

APPLICATION



1. 1/4" MIN. ELEVATIONS ARE TO BOTTOM OF STEEL PLATE. THE CONC. FILL SHALL EXTEND AN ADD'L ONE FOOT BELOW THE END OF PLATE
2. ALL RIGHT ANGLE BENDS IN 6" DIA. REBAR. THE UNDERGROUND PIPE ARE TO BE FABRICATED FROM TWO 6" ANGLE IRON FITTINGS
3. ALL CONCRETE AND BAR REBAR SHALL CONFORM WITH ALL CONCRETE AND BAR REBAR SPECIFICATIONS
4. ALL STEEL CONSTRUCTION SHALL CONFORM TO AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

WALL PROFILE



SHEET NAME	DRAWING NAME
01	01
02	02
03	03
04	04
05	05
06	06
07	07
08	08
09	09
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100



SECTION AT 10+58.07
1" = 10'



SECTION AT 10+82.07
1" = 10'




SECTIONS AND DETAILS


STRUCTURAL STEEL

1. ALL STEEL SHALL BE A36 STEEL, UNLESS OTHERWISE SPECIFIED.
2. ALL STEEL SHALL BE WELDED TO THE STRUCTURE BY THE CONTRACTOR.
3. ALL STEEL SHALL BE WELDED TO THE STRUCTURE BY THE CONTRACTOR.
4. ALL STEEL SHALL BE WELDED TO THE STRUCTURE BY THE CONTRACTOR.
5. ALL STEEL SHALL BE WELDED TO THE STRUCTURE BY THE CONTRACTOR.
6. ALL STEEL SHALL BE WELDED TO THE STRUCTURE BY THE CONTRACTOR.
7. ALL STEEL SHALL BE WELDED TO THE STRUCTURE BY THE CONTRACTOR.
8. ALL STEEL SHALL BE WELDED TO THE STRUCTURE BY THE CONTRACTOR.
9. ALL STEEL SHALL BE WELDED TO THE STRUCTURE BY THE CONTRACTOR.
10. ALL STEEL SHALL BE WELDED TO THE STRUCTURE BY THE CONTRACTOR.

NOTES REGARDING SPECIAL INSULATION

1. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.
2. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.
3. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.
4. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.
5. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.
6. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.
7. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.
8. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.
9. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.
10. SPECIAL INSULATION IS REQUIRED FOR THE STEEL STRUCTURE.






DIVERSION PLAN

Environmental Review Initial Study
ATTACHMENT 2 Set 7
APPLICATION 08-0099

DIVERSION DETAILS

NTS

[illegible]

SITE DEWATERING AND STREAM BYPASS


SHEET NAME: _____ DRAWING NAME: _____

TEMPORARY EROSION CONTROL NOTES

Temporary erosion control shall consist of, but not be limited to, constructing such facilities and taking such measures as are necessary to prevent, control, and abate water, siltation and mud, and erosion damage to public and private property resulting during the construction of this project. Appropriate measures shall be taken as are necessary to prevent siltation. Only clean water runoff will be allowed to enter the waters of Rodeo Creek. Surface runoff resulting from all construction activities shall be controlled and directed away from the work area and away from the waters of Rodeo Creek. Construction activities shall be controlled and directed away from the work area and away from the waters of Rodeo Creek. Construction activities shall be controlled and directed away from the work area and away from the waters of Rodeo Creek.

The requirements in said Section 7 - 1.01G of the California Standard Specifications shall apply during the implementation of temporary and permanent erosion control work. The contractor is responsible for submitting a Storm Water Pollution Prevention Plan for temporary erosion control measures for all phases of the work and shall conform to the provisions in California Standard Specifications in Section 7-1.01G, "Water Pollution". The contractor shall submit plans for temporary erosion control measures 24 hours prior to the preconstruction meeting. Plans for temporary erosion control measures must be approved by the County Resource Planner and Engineer prior to construction.

Planning Dept. approved winter erosion control measures shall be fully implemented and put in place for construction work being undertaken after October 15, for the duration of the contract. Applicable and adequate materials (plastic tarp, car rolls and sand bags) shall be on site and ready for use at all times. The contractor shall be responsible for the maintenance and repair of all erosion control measures. The Planning Dept. authorized inspector shall field review the work site and erosion control work after October 15 and during the course of the all remaining construction work.



ATTACHMENT 2.7 of 7
APPLICATION 03-0001 PLAN

1" = 10'

BLACK PLASTIC

The active work area shall be minimized in terms of exposed soil during winter season (October 15 - April 15) and shall be temporarily covered with black plastic during winter rains or as directed by the engineer. Black plastic sheeting shall have a minimum thickness of 6 mil and shall be keyed in at the top of the slope and firmly held in place with sandbags or other weights placed no more than 10 ft apart. Seams shall be taped or sealed with a minimum overlap of 6 inches. Seams shall be taped or sealed with a minimum overlap of 6 inches. Seams shall be taped or sealed with a minimum overlap of 6 inches.

Contractor shall have plastic sheeting, sand bag weights, rope and pole stakes system stored at the project site at all times to temporarily protect the slope during winter rains (October 15 - April 15). Plastic shall be installed before a storm event or as directed by the engineer. Plastic will concentrate runoff and shall be directed to a drain pipe or to the bottom of the slope to a sediment barrier. The sediment barrier shall include silt fence and straw rolls or equal and installed as specified in the special provisions or as directed by the engineer. Permanent erosion control measures shall be installed as soon as the active construction zone area work is completed.

Exposed soil areas outside the active construction zone shall be hydroseeded, and slopes 3:1 or greater will be covered with erosion control blanket as specified in the special provisions or as directed by the engineer and installed by October 15.

EROSION CONTROL NOTES


- ALL EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE COUNTY ENGINEER BEFORE THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES.
- EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE COUNTY ENGINEER BEFORE THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES.
- EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE COUNTY ENGINEER BEFORE THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES.
- EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE COUNTY ENGINEER BEFORE THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES.
- EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE COUNTY ENGINEER BEFORE THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES.
- EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE COUNTY ENGINEER BEFORE THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES.
- EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE COUNTY ENGINEER BEFORE THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES.
- EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE COUNTY ENGINEER BEFORE THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES.

NOTE: FROM PLANS OF EROSION CONTROL MEASURES MAY BE USED IN THE CONSTRUCTION OF EROSION CONTROL MEASURES. ALL EROSION CONTROL MEASURES SHALL BE INSTALLED BY THE COUNTY ENGINEER BEFORE THE START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE AND REPAIR OF ALL EROSION CONTROL MEASURES.

EROSION CONTROL BLANKET INSTALLATION

- Preparation: The preparation is essential to ensure complete contact of the protection matting with the soil surface. The matting shall be installed in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps.
- Installation: The installation of the erosion control blanket shall be done in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps.
- Maintenance: The erosion control blanket shall be maintained in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps.

The erosion control blanket shall be installed in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps. The matting shall be installed in a continuous manner, with no gaps or overlaps.



EROSION CONTROL DURING CONSTRUCTION

SHEET NAME: DRAWING NAME:

EROSION BLANKETS & TYPED REINFORCEMENT MATS SLOPE INSTALLATION

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

NOT TO SCALE

SECTION FOUR Adverse Effects and Avoidance and Minimization Measures

This section evaluates the potential effects of the proposed action to the tidewater goby and the California red-legged frog and proposes measures to avoid and *minimize* potential adverse effects.

4.1 POTENTIAL ADVERSE EFFECTS TO THE TIDEWATER GOBY

No habitat suitable to support the tidewater goby is present in the immediate action area. The tidewater goby inhabits brackish shallow lagoons with salinity levels from zero to 10 ppt. This habitat type does not occur in the action area. The proposed action is located approximately 2 miles upstream from the northern boundary of proposed critical habitat for the tidewater goby (USFWS 2006c). The proposed action is approximately 3 miles upstream of the Corcoran Lagoon where Rodeo Creek Gulch flows into the Pacific Ocean. Tidewater gobies were observed in 2000 in this lagoon (USFWS 2005b). The area currently proposed as critical habitat for the tidewater goby includes Corcoran Lagoon and up to 1 mile upstream of the lagoon in the Rodeo Creek Gulch drainage (USFWS 2006c). The channel of Rodeo Creek Gulch in the action area is above the elevation influenced by tides. Although direct effects to the tidewater goby would not occur, indirect effects to the tidewater goby are possible, as explained below.

4.1.1 Erosion and Sedimentation

The proposed action consisting of construction of a retaining wall along the riparian corridor of Rodeo Creek Gulch where no structure previously existed may contribute to an increase in stormwater entering Rodeo Creek Gulch. There is potential for increased erosion and sedimentation due to the loss of natural substrate for riparian vegetation. The retaining wall will have an underdrain system including filter fabric to help prevent erosion beneath it. The sediment from Rodeo Creek Gulch during construction could degrade the water quality in the area proposed as critical habitat for the tidewater goby located between 2-3 miles downstream. Therefore, avoidance and minimization measures would be implemented during project construction and implementation as described in Section 4.2.

4.1.2 Hydrology

The proposed action would not substantially change the hydrology of Rodeo Creek Gulch. Storm water runoff from the action area currently discharges into Rodeo Creek Gulch. The new retaining wall would contain an underdrain system with filter fabric to help prevent erosion beneath it, and riprap protection at the base of the retaining wall would act as energy dissipaters reducing the speed of the water into the creek. Therefore, no adverse effects are anticipated on tidewater goby habitat further downstream of the proposed action as a result of hydrologic changes.

4.2 AVOIDANCE AND MINIMIZATION MEASURES FOR THE TIDEWATER GOBY

To reduce potential erosion and discharge of sediment into Rodeo Creek Gulch and eventually into the lagoon, the following measures are proposed for work conducted in the riparian zone.

Environmental Review Initial Study

ATTACHMENT 3 of 5
APPLICATION 08-0099



SECTION FOUR Adverse Effects and Avoidance and Minimization Measures

4.2.1 Erosion and Sedimentation Prevention Measures

The County would implement standard BMPs and erosion control measures during construction to minimize possible discharge of sediment into aquatic habitats. These measures include, but are not limited to, installing and maintaining silt fences immediately downgradient of disturbed areas and installing and maintaining erosion control blankets on all disturbed ground.

Construction vehicles and equipment would be maintained to prevent contamination of soil or water (from external grease and oil or from leaking hydraulic fluid, fuel, oil, and grease). Equipment would be refueled and serviced at designated construction staging areas at least 100 feet from the riparian zone. The County would prepare a plan for the emergency clean up of any spills of fuel or other material and would make this plan available on site for inspection during construction.

4.2.2 Summary of Potential Adverse Effects to the Tidewater Goby

There is no habitat suitable for the tidewater goby in the immediate action area. The proposed action would not remove habitat or cause displacement, mortality, or direct injury of tidewater gobies during construction and implementation of the proposed action. Implementation of the erosion control measures and BMPs described above during construction would avoid indirect adverse effect on tidewater gobies or degradation of habitats downstream of the action area utilized by this species. For all these reasons, the proposed action is not likely to adversely affect the tidewater goby.

4.3 POTENTIAL ADVERSE EFFECTS TO THE CALIFORNIA RED-LEGGED FROG

Suitable habitat for California red-legged frogs exists within the action area, although the nearest occurrence of a California red-legged frog is approximately 4.5 miles west of the action area in an adjacent watershed (CDFG 2006b). Twenty four California red-legged frog occurrences have been recorded to the north, east and west of the action area within a 10-mile radius (CDFG 2006b). The CNDDDB recorded occurrences for California red-legged frogs may be limited from the action area due to dispersal requirements. Dispersal habitat is described as accessible upland or riparian dispersal units between occupied locations within 1 mile of each other that allows for movement between such sites (USFWS 2005a). The dispersal of California red-legged frogs from these known occurrences to the area surrounding the action area may be limited by watershed connectivity and urban development. However, it is not known if Rodeo Creek Gulch has been surveyed for California red-legged frogs, and the absence of a CNDDDB record does not indicate the absence of the species. Due to the number and proximity of California red-legged frog occurrences surrounding the action area and the quality of red-legged frog habitat found in Rodeo Creek Gulch, the action area is considered to provide suitable habitat for California red-legged frogs.

Suitable breeding habitat in the action area for California red-legged frog includes areas of slow moving water and abundant streambank vegetation to provide shelter and predator avoidance (USFWS 2006b). Rodeo Creek Gulch has a well-shaded riparian corridor with scattered pools, undercut banks, large woody debris, and overhanging creekbank vegetation. The riparian vegetation along Rodeo Creek Gulch is continuous above and below the action area for several miles. Upland habitat is described as upland areas within 200 feet of the edge of the riparian

Environmental Review Initial Study
ATTACHMENT 3, 2 of 5
APPLICATION 08-0099

SECTION FOUR Adverse Effects and Avoidance and Minimization Measures

vegetation comprised of various vegetational series such as grasslands, woodlands, and/or wetland/riparian plant species that provides the frog shelter, forage, and predator avoidance (USFWS 2006b). The action area has dense riparian vegetation as well as adjacent grasslands and woodlands.

4.3.1 Take and Disturbance

California red-legged frog habitat occurs in Rodeo Creek Gulch and there is potential for the species to occur in the action area. Therefore, construction activities within the riparian zone could result in disturbance, injury, and/or mortality. During construction of the retaining wall and roadway embankment, incidental take of adult and juvenile frogs could occur. Construction noise may also disturb frogs in the vicinity of the action area. Adverse effects would be most likely to occur within riparian habitat where the proposed retaining wall would be anchored on the creekbank located at the toe of the slope of the roadway embankment adjacent to Rodeo Creek Gulch. Upland areas may provide dispersal and aestivation habitat for red-legged frogs.

4.3.2 Erosion and Sedimentation

Red-legged frogs could be indirectly affected by potential erosion and sedimentation during and after construction activities. There is potential for increased erosion and sedimentation due to the loss of natural substrate for riparian vegetation. Erosion control measures would be implemented along the bank of Rodeo Creek Gulch downslope of the retaining wall during construction.

4.3.3 Adverse Effects on Habitat

Permanent loss of substrate for riparian vegetation on the east side of Rodeo Creek Gulch due to the proposed action could also affect the habitat for California red-legged frog. The construction of a new retaining wall structure where no structure previously existed will result in a loss of potential substrate for riparian vegetation. Riparian habitat in the action area potentially provides foraging, breeding, and dispersal habitat for red-legged frogs.

No riparian vegetation on the east side of Rodeo Creek Gulch would be disturbed to construct the retaining wall, because there was none remaining in the damaged area after the failure of the roadway embankment. The loss of vegetation due to the erosion of the embankment has created an opening in the overstory and understory along the creek in the action area. Therefore, no measures are recommended on this topic.

4.4 AVOIDANCE AND MINIMIZATION MEASURES FOR THE CALIFORNIA RED-LEGGED FROG

The County is responsible for implementing the following measures to avoid and reduce adverse effects to California red-legged frogs and their habitat.

4.4.1 Take and Disturbance

- Construction activities in Rodeo Creek Gulch and the riparian habitat would be timed to occur during the latter part of the dry season (non-breeding season for red-legged frogs) (April 15 to October 15) to minimize take of dispersing frogs.

Environmental Review Initial Study
ATTACHMENT 3 385
APPLICATION 08-0099



SECTION FOUR Adverse Effects and Avoidance and Minimization Measures

- A qualified biologist would conduct preconstruction surveys of all ground disturbance areas within riparian habitats to determine if California red-legged frogs are present prior to the start of construction. These surveys would be conducted less than 2 days prior to start of construction activities in the riparian zone. If California red-legged frogs are found during any preconstruction surveys, the USFWS-approved biologist would contact the USFWS to determine if moving them is appropriate. If the USFWS gives approval for relocation, the USFWS-approved biologist would be allowed sufficient time to move the California red-legged frogs from the work site before activities begin. ✓
- A USFWS-approved biologist would monitor construction activities that involve retaining wall construction and installation of rock slope protection along the channel bank. If California red-legged frogs are found that are likely to be killed or injured by work activities, the USFWS-approved biologist would be allowed sufficient time to move them from the site before work activities resume. The USFWS-approved biologist would relocate the California red-legged frogs the shortest distance possible to suitable habitat that would not be affected by activities associated with the proposed action. Only California red-legged frogs that are at risk of injury or death by project activities may be moved. ✓
- Only USFWS-approved biologists would participate in activities associated with capture, handling, and monitoring of California red-legged frogs. The County would request and receive the USFWS' approval of any other biologist it wishes to employ to conduct activities with California red-legged frogs. ✓
- If more than two (2) California red-legged frogs are found dead or injured within a 12-month period, the County would contact the USFWS immediately so the USFWS can review the project activities to determine if additional protective measures are needed.
- Exclusion fences comprised of silt fence material would be installed at the margins of the work area to prevent workers from encroaching into adjacent habitat and to prevent California red-legged frogs from entering the construction area. The fence would be monitored periodically. A fine (less than 1 centimeter) mesh would be used to avoid entrapment of amphibians in the silt fence. The silt fence would be monitored periodically during construction to evaluate its effectiveness. All fencing in this area would be maintained for the duration of construction and removed on project completion.
- To avoid attracting predators, food-related trash would be kept in closed containers and removed regularly from the action area.
- To avoid transferring disease or pathogens, the USFWS-approved biologist would follow the Declining Amphibian Populations Task Force Fieldwork Code of Practice (USFWS 2005a).
- Prior to construction, a qualified biologist would conduct training sessions to familiarize all construction personnel with the following: identification of California red-legged frogs, their habitat, general provisions and protections afforded by the ESA, measures implemented to protect the species, and a review of the project boundaries. This training would also be provided within 30 days of the arrival of any new worker.
- If an injured California red-legged frog is found, the contractor will have a USFWS-approved biologist determine the extent of the injury. If the injury is minor and the frog is likely to survive without treatment, the biologist will document the injury and release the frog in an

Environmental Review Initial Study
ATTACHMENT 3
APPLICATION 08-0099



SECTION FOUR Adverse Effects and Avoidance and Minimization Measures

appropriate location previously designated by the USFWS. However, if the injured frog would require professional treatment to survive, the biologist will transport the frog to the location where a qualified professional can provide the needed treatment. The location of a qualified professional to assist the frog would have been documented prior to the start of construction. The treated frog will be released at an appropriate location as soon as its recovery will allow. Within three working days, the injured frog incident will be reported to the USFWS and reported information will include date of injury, extent of injury, and action(s) taken. If a frog were to die while being treated or a dead frog was to be located within the action area, the USFWS will be contacted within three working days. At that time, the USFWS would also provide instructions regarding the deposition of the frog.

- The County would provide the USFWS a report on the results of biological surveys and sighting records, and also document the following: the number of California red-legged frogs relocated from the action area or killed or injured during the proposed action; the dates and times of capture, mortality, or injury; specific locations of capture, mortality, or injury; approximate size and age of individuals; and a description of relocation sites.

4.4.2 Erosion and Sedimentation

- Standard BMPs and erosion control measures would be implemented during construction to minimize possible discharge of sediment into aquatic habitats. These measures include, but are not limited to, installing and maintaining silt fences immediately downgradient of disturbed areas and installing and maintaining erosion control blankets on all disturbed ground.

4.4.3 Adverse Effects on Habitat

Since no riparian vegetation on the east side of Rodeo Creek Gulch would be disturbed to construct the retaining wall, no measures are recommended on this topic.

In sum, the total impacts of the proposed action on California red-legged frogs and their habitat would be minor and restricted to a small portion of the Rodeo Creek Gulch watershed. The small amount of bank and riparian habitat to be removed by this project alone would not affect the ability of the species to persist in Rodeo Creek Gulch. California red-legged frogs are known to occur in adjacent drainages to the east and west of the action area and in 247 other streams or drainages throughout its range (USFWS 2005a). Consequently, the proposed action would not appreciably reduce the quality of red-legged frog habitat in Rodeo Creek Gulch to support the survival and recovery of California red-legged frogs (USFWS 2005a).

4.4.4 Summary of Potential Adverse Effects to the California Red-legged Frog

FEMA has determined that with the implementation of the avoidance and minimization measures identified above, the proposed action may affect the California red-legged frog.

Environmental Review Initial Study

ATTACHMENT 3, 5 of 5
APPLICATION 08-0099



SPILL PREVENTION CONTROL AND COUNTERMEASURE PLAN

WATER POLLUTION.

Attention is directed to the provisions of Section 7-1.01G, "Water Pollution," of the Standard Specifications.

Prior to beginning any construction work, the Contractor shall submit a water pollution control plan in conformance with the provisions of Section 7-1.01G for approval by the Engineer that details all methods and facilities to be implemented for control of surface, underground waters related to the Contractor's construction activities. No soils nor silt laden or polluted waters generated from the Contractor's construction activities shall be allowed to be released untreated into Rodeo Creek.

Full compensation for conforming to the provisions of this section, not otherwise provided for, shall be considered as included in prices paid for the various contract items of work involved and no separate payment will be made therefor.

CONTRACTOR RESPONSIBILITY FOR CONTAMINATION.

If, as a result of working on this project, any land, waterway, or stream becomes contaminated, including any land, waterway, or stream that contains an endangered or threatened species, the Contractor shall immediately contact the County inspector on the job and immediately act to mitigate and limit the reason for the contamination. The Contractor shall also notify the following agencies as soon as possible of the discharge or spill: The California Office of Emergency Services, National Oceanic and Atmospheric Administration, Department of Fish and Game, and Regional Water Quality Control Board. It will be the responsibility of the Contractor to remedy the situation and monitor all cleanup activities, including all efforts to mitigate the resultant damage. In addition the contractor shall limit further damage. The Contractor shall develop a response and mitigation plan and coordinate all cleanup and remediation efforts with the appropriate regulatory agencies by acquiring all permits, clearances and consents necessary to facilitate the remediation effort. The Contractor shall supply the equipment and personnel needed to implement the response and mitigation plan.

The Contractor shall assume full responsibility for and immediately undertake the cleanup and mitigation described above even if the Contractor claims the contamination was a result of differing site conditions or any other cause for which the Contractor may dispute its liability.

Full compensation for any costs occasioned by compliance with this section shall be considered included in the contract price and no separate payment shall be made therefor unless the Contractor establishes entitlement for reimbursement pursuant to a Claim made in accordance with the provisions of this Contract.

TRAFFIC CONTROL REQUIREMENTS

ORDER OF WORK.

Order of work shall conform to the provisions of Section 5-1.05, "Order of Work," of the Caltrans Standard Specifications and these special provisions. Attention is directed to "Maintaining Traffic" of these special provisions.

A minimum of one eleven foot wide north bound lane on North Rodeo Gulch at the construction site shall be kept open to public traffic at all times.

Before a lane closure will take place, warning signs for road closure shall be installed at road intersections identified elsewhere in these special provisions, with the specific locations determined by the Engineer. Coordination with the County Traffic Engineer is mandatory at least 72 hours in advance of all road closures.

The installation of temporary railings shall be complete at each required location before existing facilities are disturbed or before excavation or other work is begun. Temporary railings shall consist of Type 'K' rails per Section 12-3.08 of the Standard Specifications and shall be placed along the full length of the construction site including the staging area on North Rodeo Gulch. Temporary railings shall not be removed until such hazards no longer exist and until such removal is approved by the Engineer.

CONSTRUCTION AREA SIGNS.

Construction area signs shall be furnished, installed, maintained, and removed when no longer required in accordance with the provisions of Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications and these special provisions.

Full compensation for furnishing, installing, maintaining and removing Construction Area Signs, shall be considered as included in the contract price paid for Traffic Control System and no separate payment will be made therefor.

MAINTAINING TRAFFIC.

Attention is directed to Sections 7-1.08, "Public Convenience," 7-1.09, "Public Safety," 12-2.02, "Portable Delineators," of the Standard Specifications and these special provisions.

Lane closures shall conform to the provisions in the section of these special provisions entitled "Traffic Control System".

Personal vehicles of the Contractor's employees shall not be parked on the traveled way at any time, including any section closed to public traffic.

The Contractor shall notify local authorities of the intended date when work is to commence at least one week before work is begun. The Contractor shall cooperate with local authorities relative to handling traffic through the area and shall make arrangements relative to keeping the working area clear of parked vehicles.

The provisions in this section may be modified or altered if, in the opinion of the Engineer, public traffic will be better served and work expedited. Said modifications or alterations shall not be adopted until approved in writing by the Engineer.

The Contractor shall be responsible for installing and maintaining adequate temporary traffic control per the California MUTCD (lane markers, pavement markings and temporary traffic signs to replace existing traffic control devices removed by construction).

TRAFFIC CONTROL SYSTEM.

The traffic control system shall consist of closing the south bound traffic lane only and controlling traffic in the remaining north bound lane continuously for the full term of the construction contract in accordance with the details shown on the plans, the provisions of Section 12, "Construction Area Traffic Control Devices," of the Standard Specifications, the provisions under Section 10-1.05, "Maintaining Traffic," of these special provisions, these special provisions and an approved Traffic Control Plan.

Existing traffic control signing that is in place prior to the award of this contract shall be the full responsibility of the Contractor.

Signs for traffic control system shall conform to the provisions under Section 10-1.03, "Construction Area Signs," of these special provisions.

24 hour traffic control for the duration of the construction work is mandatory.

Stop signs or photo voltaic powered signal system may be used at either end of the construction site to provide 24 hour traffic control. If relocated stop signs are utilized, then flaggers shall be required when the line of sight from the relocated south bound stop sign to relocated north bound stop sign will be obstructed.

The provisions of this section will not relieve the Contractor from his responsibility to provide such additional devices or take such measures as may


be necessary to comply with the provisions of Section 7-1.09, "Public Safety," of the Standard Specifications.

The Contractor shall immediately repair or replace any component in the traffic control system that is damaged, displaced, or ceases to operate or function as specified.

Upon completion of the work requiring lane closure, all components of the traffic control system that are the responsibility of the Contractor to install and maintain shall be removed from the site of the work and shall become the property of the Contractor.

The contract lump sum price paid for Traffic Control System shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in placing, removing, storing, maintaining, repairing, moving to new locations, replacing and disposing of the components of the traffic control system as shown on the plans, including temporary 'K' rail, photo voltaic powered traffic control signal system, in accordance with the provisions of the Standard Specifications and these special provisions, and as directed by the Engineer, and no additional compensation will be allowed therefor.






















Environmental Review Initial Study
ATTACHMENT 5.3 of 6
APPLICATION 08-0099

Figure 6H-10 (CA). Lane Closure on Two-Lane Road Using Flaggers (TA-10)**Typical Application 10**

Environmental Review Initial Study
 ATTACHMENT 5.4 at 6
 APPLICATION 08-0099

May 20, 2004

Table 6H-2. Meaning of Symbols on Typical Application Diagrams

	Arrow panel
	Arrow panel support or trailer (shown facing down)
	Changeable message sign or support trailer
	Channelizing device
	Crash Cushion
	Direction of temporary traffic detour
	Direction of traffic
	Flagger
	High level warning device (Flag tree)
	Luminaire
	Pavement markings that should be removed for a long term project
	Sign (shown facing left)
	Surveyor
	Temporary barrier
	Temporary barrier with warning lights
	Traffic or Pedestrian signal
	Truck mounted attenuator
	Type III Barricade
	Warning lights
	Work space
	Work vehicle

Environmental Review Initial Study
ATTACHMENT 5.5a-6
APPLICATION 08-0099

**Table 6H-3. Meaning of Letter Codes on
Typical Application Diagrams**

Road Type	Distance Between Signs**		
	A	B	C
Urban (low speed)*	30 (100)	30 (100)	30 (100)
Urban (high speed)*	100 (350)	100 (350)	100 (350)
Rural	150 (500)	150 (500)	150 (500)
Expressway / Freeway	300 (1,000)	450 (1,500)	800 (2,640)

* Speed category to be determined by highway agency

** Distances are shown in meters (feet). The column headings A, B, and C are the dimensions shown in Figures 6H-1 through 6H-46. The A dimension is the distance from the transition or point of restriction to the first sign. The B dimension is the distance between the first and second signs. The C dimension is the distance between the second and third signs. (The third sign is the first one in a three-sign series encountered by a driver approaching a TTC zone.)

Table 6H-4. Formulas for Determining Taper Lengths

Speed Limit (S)	Taper Length (L) Meters	Speed Limit (S)	Taper Length (L) Feet
60 km/h or less	$L = \frac{WS^2}{155}$	40 mph or less	$L = \frac{WS^2}{60}$
70 km/h or more	$L = \frac{WS}{1.6}$	45 mph or more	$L = WS$

Where: L = taper length in meters (feet)

W = width of offset in meters (feet)

S = posted speed limit, or off-peak 85th-percentile speed prior to work starting, or the anticipated operating speed in km/h (mph)

Environmental Review Initial Study
ATTACHMENT 5, 6 of 6
APPLICATION 08-0099