# HOUSTON RESIDENCE

GRUSS DUILDING	AREA WORKSHI	EET
FLOOR AREA RATIO	AND LOT COVERAG	<u>GE</u>
ARCHITECTURAL FEATURE	FLOOR AREA RATIO CALCULATION	LOT COVERAGE
ATTIC	0 SQ. FT.	N/A
BASEMENT	0 SQ. FT.	N/A
FIRST FLOOR	1,439 SQ.FT.	1,439 SQ.FT
SECOND FLOOR	1,884 SQ.FT.	N/A
UNDERFLOOR	0 SQ. FT.	N/A
HIGH CEILINGS	0 SQ. FT.	N/A
MEZZANINE	0 SQ. FT.	N/A
INTERIOR STAIRS CREDIT	<105 SQ.FT.>	N/A
DECK OR PORCH- FULLY ENCLOSED	0 SQ. FT.	0 SQ. FT
DECK-CANTILEVERED, UNCOVERED	N/A	N/A
DECK-SUPPORTED, UNCOVERED (> 18")	N/A	0 SQ. FT
COVERED DECK/PORCH	1) 0 5Q. FT.	215 SQ.FT
AREA BENEATH PROJECTIONS-SEE DIAGRAM SHEET A2	2 SQ.FT.	N/A
DECK, 2ND FLOOR ROOFTOP	MA	N/A
EXTERIOR STAIRS AND LANDINGS	0 SQ.FT.	0 SQ.FT
TRELLIS OR ARBOR- SOLID OR OPEN	N/A	0 SQ.FT
GARAGES/ CARPORTS	(567sf-225sf) 342 SQ.FT.	567 SQ.FT
ACCESSORY STRUCTURE. GREENHOUSE	O SQ.FT.	0 SQ.FT
BAY WINDOWS	0 SQ.FT.	0 SQ. FT
CHIMNEYS	O SQ.FT.	0 SQ.FT
AWNINGS, FENCES AND WALLS	N/A	N/A
ELEVATOR SHAFTS, ATRIUMS AND UNCOVERED COURTYARDS	<30 SQ.FT.>	INCLUDED IN FIRST FLOOR CALC.
TOTALS:	3,532 SQ.FT.	2.880.5Q.FT
RATIOS (LOT AREA: 10,742 S.F. INCLUDING AREA BELOW BLUFF) 7,702 NOT INCLUDING AREA BELOW BLUFF)	3,532/7,702 = 46% TOTAL ALLOWED: 50%	2,880/7,702 = 37% TOTAL ALLOWED: 40%
HE	ATED SPACE CALC	ULATION
I . TC	DTAL HEATED SPACE:	

A) FIRST FLOOR


B) SECOND FLOOR

2. TOTAL UNHEATED SPACE:

C) BASEMENT FLOOR



# PARCEL MAP



# BUILDING INFORMATION SUMMARY

DEMOLITION OF EXISTING, TWO-STORY, 1,95 | sq.ft. 2 BR, 1.5 BA SINGLE FAMILY PROJECT DESCRIPTION: DWELLING AND CONSTRUCTION OF A NEW TWO-STORY, 3,323 sq.ft. 4 BR, 4.5 BA SINGLE FAMILY DWELLING WITH ATTACHED 567 sq.ft. GARAGE.

> 4 I 90 OPAL CLIFF DRIVE SANTA CRUZ, CA 95062

033-171-08

R-1-5

**OCCUPANCY TYPE:** LOT AREA:

SETBACK INFORMATION:

REQUIRED PROPOSED

PARKING (PROVIDED):

1,439 sq.ft.

1,884 sq.ft.

3,323 sq.ft.

567 sq.ft.

567 sq.ft.

PROJECT ADDRESS:

PARCEL NUMBER:

ZONING:

CODE NOTE:

R3 / U SPRINKLERED 10,742 sq.ft. (7,702 sq.ft. NOT INCLUDING AREA BELOW BLUFF)

FRONT YARD

SIDE YARD 5'-0" \$ 8'-0"

20-0" 20-0" 5'-0" \$ 8'-0"

2 COVERED AND 2 UNCOVERED

ALL WORK INDICATED ON THE PLANS SHALL COMPLY WITH THE FOLLOWING CODES: 2019 CALIFORNIA RESIDENTIAL CODE

REAR YARD

15'-0"

15'-0"

 2019 CALIFORNIA BUILDING CODE • 2019 CALIFORNIA FIRE CODE

 2019 CALIFORNIA PLUMBING CODE 2019 CALIFORNIA MECHANICAL CODE

2019 CALIFORNIA ELECTRIC CODE

2019 CALIFORNIA GREEN BUILDING STANDARDS

2019 CALIFORNIA ENERGY STANDARDS

SANTA CRUZ COUNTY CODE AMENDMENTS

# NOTE - ALL WORK TO COMPLY WITH:

GEOTECHNICAL REPORT: CMAG ENGINEERING PROJECT NO. 19-144-SC DATED FEBRUARY 18, 2020

GEOLOGICAL REPORT EASTON GEOLOGY JOB NO. C19009 DATED FEBRUARY 7, 2020

# FIRE PROTECTION NOTES

I) THESE PLANS ARE IN COMPLIANCE WITH CALIFORNIA BUILDING AND FIRE CODES (2019) AND CENTRAL FIRE PROTECTION DISTRICT AMENDMENTS.

2) BUILDING SHALL BE PROTECTED BY AN APPROVED AUTOMATIC SPRINKLER SYSTEM COMPLYING WITH THE EDITION OF NFPA 13D CURRENTLY ADOPTED IN CHAPTER 35 OF THE CALIFORNIA BUILDING

3) FIRE SRPINKLER DESIGNER / INSTALLER SHALL SUBMIT TWO (2) SETS OF PLANS, CALCULATIONS, AND CUT SHEETS FOR THE UNDERGROUND AND OVERHEAD RESIDENTIAL AUTOMATIC SPRINKLER SYSTEM TO CENTRAL FIRE DEPARTMENT FOR APPROVAL. INSTALLATION SHALL FOLLOW GUIDE SHEET PROVIDED BY CENTRAL FIRE DEPARTMENT.

4) AN APPROVED SPARK ARRESTOR SHALL BE INSTALLED ON TOP OF CHIMNEY. WIRE MESH NOT TO EXCEED 1 INCH.

5) ROOF COVERING SHALL BE NO LESS THAN CLASS 'B' RATED ROOF.

6) NEW/UPGRADED HYDRANTS, WATER STORAGE TANKS, AND / OR UPGRADED ROADWAYS SHALL BE INSTALLED PRIOR TO CONSTRUCTION.

7) ADDRESS NUMBERS SHALL BE MINIMUM OF FOUR (4) INCHES IN HEIGHT AND OF A COLOR CONTRASTING TO THEIR BACKGROUND.

8) A 100-FOOT CLEARANCE WILL BE MAINTAINED WITH

NON-COMBUSTIBLE VEGETATION AROUND ALL STRUCTURES.

9) FIRE HYDRANT INFORMATION: LOCATION: 4 | 50 OPAL CLIFF DRIVE

HYDRANT #803 STATIC PRESSURE (PSI): 84

RESIDUAL PRESSURE (PSI): 50

FLOW @ 20 PSI (GPM). = 1,023

FLOW (GPM): 750

# CONTACTS

# OWNER:

JERRY HOUSTON 166 ALICE AVENUE CAMPBELL, CA 95008

(408) 355-1507 jerry.houston54@icloud.com

PROJECT DESIGNER:

DEREK VAN ALSTINE RESIDENTIAL DESIGN, INC.

DEREK VAN ALSTINE 1535 SEABRIGHT AVE SUITE 200

SANTA CRUZ. CA 95062

PH: (831) 426-8400 FAX: (831) 426-8446 derek@vanalstine.com

# SURVEYOR:

WESTFALL ENGINEERS, INC. HARRY BABICKA, LS 4953 14583 BIG BASIN WAY

SARATOGA, CA 95070

PH: (831) 867-0244

**GEOLOGIST:** EASTON GEOLOGY, INC. GREGORY EASTON

P.O. BOX 3533 SANTA CRUZ, CA 95063 PH: (831) 247-4317

info@eastongeology.com SOILS ENGINEER:

## CMAG ENGINEERING, INC ADRIAN GARNER

P.O. BOX 640 APTOS, CA 95001

PH: (831) 475-1411 CIVIL ENGINEER:

RAMSEY CIVIL ENGINEERING, INC.

DAVID RAMSEY 2905 KRISTIE COURT

PH: (831) 462-2905 david@ramseyce.com

SANTA CRUZ, CA 95065

LANDSCAPE ARCHITECT ELLEN COOPER & ASSOCIATES

ELLEN COOPER

612 WINDSOR STREET SANTA CRUZ. CA 95062

# PH: (831) 426-6845 FAX: (831) 426-6845

# DRAWING INDEX

BUILDING DESIGN TI TITLE SHEET

SURVEY

LI LANDSCAPE PLAN

EXISTING AND PROPOSED SITE PLAN

FIRST FLOOR PLAN

SECOND FLOOR PLAN

ROOF PLAN

EXTERIOR ELEVATIONS

AG EXTERIOR ELEVATIONS

BUILDING SECTION

# 

CIVIL DESIGN

CI.O COVER SHEET & SITE PLAN

C2.0 GRADING & DRAINAGE PLAN

C3.0 UTILITY PLAN

C4.0 EROSION & SEDIMENT CONTROL PLAN

C5.0 DETAILS

\_\_\_\_\_

LANNING SUBMITTAI JULY 10, 2020 BUILDING SUBMITTAI

DVRD

DEREK VAN ALSTINE

DESIGNER

ALL RIGHTS RESERVED

SIDENC FF DRIVE CA 95062

HOUSTC 4190 OP. SANTA

033-171-08

ISSUE DESCRIPTION

SCHEMATIC DESIGN

APRIL 02, 2020


DESIGN DEVELOPMENT


JUNE 12, 2020

**REVISIONS:** 

P.C. #1

TITLE SHEET





HOUSTON RESIDENCE 4190 OPAL CLIFF DRIVE SANTA CRUZ, CA 95062

• 4

C

 $\alpha$ 

O

S

D

ಡ

0

0

APN:
033-171-08

ISSUE DESCRIPTION

SCHEMATIC DESIGN

DESIGN DEVELOPMENT

LANNING SUBMITTAL:
JULY 10, 2020


BUILDING SUBMITTAL:

NOV. 15, 2020 P.C. #1 DEC4, 2020

DEC 4, 2020

PROPOSED LANDSCAPE PLAN

L 1



INC. H I

DVRD<sub>IN</sub>

2020 COPYRIGHT ALL RIGHTS RESERVED

RESIDENCE CLIFF DRIVE UZ, CA 95062 HOUSTC 4190 OP/ SANTA (


033-171-08 ISSUE DESCRIPTION

SCHEMATIC DESIGN APRIL 02, 2020 DESIGN DEVELOPMENT JUNE 12, 2020 LANNING SUBMITTAI JULY 10, 2020

**REVISIONS:** ∴ OCT. 31, 2020 P.C. #1

BUILDING SUBMITTAL

DEMO AND PROPOSED SITE PLANS



П

DVRD<sub>IN</sub> DEREK VAN ALSTINE DESIGNER

2020 COPYRIGHT ALL RIGHTS RESERVED

HOUSTON RESIDENCE 4190 OPAL CLIFF DRIVE SANTA CRUZ, CA 95062

033-171-08 SSUE DESCRIPTION

SCHEMATIC DESIGN APRIL 02, 2020 DESIGN DEVELOPMENT JUNE 12, 2020


LANNING SUBMITTAI JULY 10, 2020

BUILDING SUBMITTAL

**REVISIONS:** OCT. 31, 2020

P.C. #1

PROPOSED FIRST FLOOR PLAN



口 LALSTIN DESIGN INC. RESIDENTIAL I

> DVRD INC 2020 COPYRIGHT ALL RIGHTS RESERVED

HOUSTON RESIDENCE 4190 OPAL CLIFF DRIVE SANTA CRUZ, CA 95062

033-171-08


ISSUE DESCRIPTION

SCHEMATIC DESIGN APRIL 02, 2020 DESIGN DEVELOPMENT JUNE 12, 2020 PLANNING SUBMITTAL

JULY 10, 2020 BUILDING SUBMITTAL

**REVISIONS:** OCT. 31, 2020 P.C. #1

PROPOSED SECOND FLOOR PLAN



П I ALSTINI DESIGN INC. DEREK VAN
RESIDENTIAL I

HOUSTON RESIDENCE 4190 OPAL CLIFF DRIVE SANTA CRUZ, CA 95062

DVRD IN DEREK VAN ALSTINE DESIGNER

2020 COPYRIGHT ALL RIGHTS RESERVED

033-171-08 ISSUE DESCRIPTION SCHEMATIC DESIGN

APRIL 02, 2020 DESIGN DEVELOPMENT JUNE 12, 2020 LANNING SUBMITTAI JULY 10, 2020

BUILDING SUBMITTAL REVISIONS:

OCT. 31, 2020 P.C. #1 P.C. #1

PROPOSED ROOF PLAN



1 MEST ELEVATION SCALE: 1/4"= 1'-0"



2 EAST ELEVATION SCALE: 1/4"= 1'-0"

HOUSTON RESIDENCE 4190 OPAL CLIFF DRIVE SANTA CRUZ, CA 95062

口

INC.

 $\infty$ 

 $Z_{\dashv}$ 

> L Z

REK ESIDEI

压民

DVRD INC

APN:
033-171-08

ISSUE DESCRIPTION

SCHEMATIC DESIGN

APRIL 02, 2020

DESIGN DEVELOPMENT

JUNE 12, 2020

PLANNING SUBMITTAL:

JULY 10, 2020
BUILDING SUBMITTAL:

REVISIONS:


OCT. 31, 2020

P.C. #1

EXTERIOR

ELEVATIONS

SOUTH ELEVATION
SCALE: 1/4"= 1'-0"



口 INC.  $\infty$ ESIDENTIAL
(831)426-8400 PHONE 压民

DVRD IN DEREK VAN ALSTINE DESIGNER

2020 COPYRIGHT ALL RIGHTS RESERVED

HOUSTON RESIDENCE 4190 OPAL CLIFF DRIVE SANTA CRUZ, CA 95062

033-171-08

ISSUE DESCRIPTION SCHEMATIC DESIGN APRIL 02, 2020 DESIGN DEVELOPMENT JUNE 12, 2020

BUILDING SUBMITTAL **REVISIONS:** 

LANNING SUBMITTAI JULY 10, 2020

OCT. 31, 2020

EXTERIOR ELEVATIONS

BATHROOM TALL SHOPER BATHROOM LANDRY

DEREK VAN ALSTINE
RESIDENTIAL DESIGN INC.
1535 SEABRIGHT AVENUE SUITE 200, SANTA CRUZ, CALIFORNIA
(831)426-8400 PHONE (831)426-8446 FAX

2020 COPYRIGHT
ALL RIGHTS RESERVED

HOUSTON RESIDENCE 4190 OPAL CLIFF DRIVE SANTA CRUZ, CA 95062

O33-171-08
ISSUE DESCRIPTION

SCHEMATIC DESIGN

APRIL 02, 2020

DESIGN DEVELOPMENT

JUNE 12, 2020

PLANNING SUBMITTAL:

JULY 10, 2020

BUILDING SUBMITTAL:

REVISIONS:

OCT. 31, 2020
P.C. #1

SECTIONS

# **ABBREVIATIONS**



SOUTHEAST

STANDARD

TOP OF WALL

WEST, WATER

SHEET

SINGLE FAMILY RESIDENCE

TOP OF RETAINING WALL

SANITARY SEWER CLEAN OUT

UNDERGROUND SERVICE ALERT

SE

SFR


SHT


SSCO STD

TRW

TW

USA





# **VICINITY MAP** NOT TO SCALE

# **INDEX OF SHEETS**

SHEET NO.	DESCRIPTION
C1.0	COVER SHEET & SITE PLAN
C2.0	GRADING & DRAINAGE PLAN
C3.0	UTILITY PLAN
C4.0	EROSION & SEDIMENT CONTROL PLAN
C5.0	DETAILS & SECTIONS
C6.0	DETAILS

# **SURVEY NOTES**

SURVEY FOR THIS PROJECT PROVIDED BY WESTFALL ENGINEERS, INC., DATED JANUARY, 2020.

BENCHMARK INFORMATION IS TAKEN FROM AFOREMENTIONED SURVEY.

PROPERTY LINES ARE SHOWN FOR ORIENTATION ONLY AND ARE BASED ON RECORD DATA. THEY MAY BE DISCOVERED TO BE DIFFERENT, SUBJECT TO THE RESULTS OF A COMPLETE BOUNDARY SURVEY.

# **BENCHMARK**

PROJECT BENCHMARK IS COUNTY OF SANTA CRUZ BENCHMARK #488, A BRASS DISK ON TOP OF CURB AT NORTHWEST CORNER OF INTERSECTION OF FLORAL DRIVE AND 36TH AVE

ELEVATION = 44.06' (NAVD88)

# IMPERVIOUS AREA BREAKDOWN

ON-SITE	EXISTING (SF)	NEW/REPLACED (SF)		
STRUCTURE AREA	1,860	2,007		
CONCRETE/HARDSCAPE	1,389	905		
ASPHALT	318	328		
PERVIOUS PAVERS	0	570		
TOTAL	3,567	3,525		
DED DADT O OFOTION O.4 - OF THE CANTA ODITY OCHNITY DECICAL				

PER PART 3, SECTION C.1.a OF THE SANTA CRUZ COUNTY DESIGN CRITERIA THIS PROJECT IS CONSIDERED A MEDIUM PROJECT (500SF-5,000SF) AND REQUIRES IMPLEMENTATION OF BMP's

- PERVIOUS PAVER AREA TAKEN AT 50% FOR TOTAL
- BREAKDOWN. DOWNSPOUTS WILL BE HARDPIPED TO LOW LYING
- LANDSCAPED AREA NEAR FRONT OF PROPERTY.
- LOW LYING LANDSCAPE AREAS WILL OVERFLOW TO EXISTING STORM DRAIN LINE, WHICH DISCHARGES OUT OF FACE OF CLIFF





DAVID RAMSEY RCE# 73735

APN# 033-171-08

PLAN TYPE

SITE  $\infty$ S

Ш

DRAWN BY: DESIGNED BY: DMR 12/21/2020 AS NOTE SCALE: PROJECT NO: 20-036

# RAMSEY CIVIL ENGINEERING NOTES:

- 1. SITE PLAN BASED ON TOPOGRAPHIC SURVEY, PERFORMED BY BY WESTFALL ENGINEERS, INC. (PROJECT #2019-081), DATED JANUARY, 2020.
- 2. ALL GRADING WORK AND CONSTRUCTION OF IMPROVEMENTS SHALL BE DONE IN ACCORDANCE WITH THE RECOMMENDATIONS SPECIFIED IN THE GEOLOGIC INVESTIGATION, PREPARED BY EASTON GEOLOGY, JOB NO. C19009, DATED FEBRUARY 7, 2020. THE GEOLOGICAL ENGINEER SHALL INSPECT THE COMPLETED PROJECT AND CERTIFY, IN WRITING, THAT ALL WORK CONFORMS TO THE GEOLOGIC INVESTIGATION REPORT.
- 3. NO CHANGES ON THESE PLANS SHALL BE MADE WITHOUT PRIOR APPROVAL OF RAMSEY CIVIL ENGINEERING, INC.
- 4. EROSION CONTROL PLANS SHALL BE PERMITTED AND FILED WITH THE APPLICABLE AGENCIES PRIOR TO ANY CONSTRUCTION OR GRADING OPERATIONS.
- 5. THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO, OR USES OF, THESE PLANS. ALL CHANGES MUST BE IN WRITING AND MUST BE APPROVED BY THE ENGINEER PRIOR TO CONSTRUCTION.
- 6. ROOF DOWNSPOUTS SHALL DISCHARGE AWAY FROM BUILDING FOUNDATION PER 2019 CBC, AND DIRECTED TO GRADE TO DRAIN.
- 7. TOTAL NEW/REPLACED IMPERVIOUS SURFACES IS BETWEEN 500 AND 5,000 SQUARE FEET, THEREFORE, THE PROPOSED PROJECT IS CLASSIFIED AS A "MEDIUM" PROJECT PER THE SCC DESIGN CRITERIA, FEBRUARY 2019 EDITION. BMP'S SHALL BE IMPLEMENTED
- 8. ALL COMPACTION TO BE DETERMINED USING THE LATEST EDITION OF ASTM D1557.
- 9. THE TYPES, LOCATIONS, SIZES, AND/OR DEPTHS OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THE IMPROVEMENT PLANS WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. THE CONTRACTOR SHALL PERFORM THEIR OWN FIELD INVESTIGATION PRIOR TO CONSTRUCTION TO VERIFY UTILITY LOCATIONS. CONTRACTOR IS CAUTIONED THAT ONLY ACTUAL EXCAVATION WILL REVEAL THE TYPES, EXTENT, SIZES, LOCATIONS, AND DEPTHS OF SUCH UNDERGROUND UTILITIES. THE ENGINEER CAN ASSUME NO RESPONSIBILITY FOR THE COMPLETENESS OR ACCURACY OF THE DELINEATION OF SUCH UNDERGROUND UTILITIES WHICH MAY BE ENCOUNTERED. IF AT ANYTIME THE CONTRACTOR IS UNSURE OF UTILITY LOCATIONS, A CERTIFIED UNDERGROUND UTILITY LOCATOR SHALL BE OBTAINED AT THE COST OF THE CONTRACTOR, FOR ONSITE UTILITIES, OR CONTACT U.S.A (OR 811) FOR OFFSITE UTILITIES.
- 10. ALL UTILITY STRUCTURES TO REMAIN WITHIN AREAS EFFECTED BY THE CONSTRUCTION WORK ON THIS PROJECT, INCLUDING, BUT NOT LIMITED TO CLEANOUTS, WATER VALVES, AND PULL BOXES SHALL BE ADJUSTED TO GRADE BY THE CONTRACTOR WHETHER SHOWN ON THESE PLANS OR NOT. CONTRACTOR IS RESPONSIBLE FOR COORDINATION WITH ALL PUBLIC OR PRIVATE UTILITY COMPANIES.
- 11. ALL AREAS TO BE GRADED ACCORDING TO THE GRADES SHOWN ON THESE PLANS. A 1% MINIMUM SLOPE FOR DRAINAGE SHALL BE APPLIED IF NO GRADES ARE SHOWN, SUBJECT TO THE APPROVAL OF THE PROJECT ENGINEER.
- 12. CONTRACTOR SHALL GRADE EVENLY BETWEEN SPOT ELEVATIONS.
- 13. CONTRACTOR SHALL VERIFY THE CONTENTS AND THICKNESS OF THE BUILDING SLAB SECTION (I.E. CONCRETE, SAND, ROCK) WITH THE STRUCTURAL PLANS PRIOR TO COMMENCEMENT OF GRADING OPERATIONS.
- 14. ALL GRADING, TRENCHING, SHORING, PAVING, AND CONSTRUCTION WORK SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE O.S.H.A REGULATIONS.
- WORKING HOURS. CONTRACTOR AGREES TO DEFEND, INDEMNIFY, AND HOLD DESIGN PROFESSIONALS AND CITY REPRESENTATIVES HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE DESIGN PROFESSIONAL.


15. CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF THE CONSTRUCTION OF THIS

PROJECT, INCLUDING SAFETY OF ALL PERSONNEL AND PROPERTY. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL

- 16. THE OWNER ACKNOWLEDGES THAT THE PARCEL DOES AND WILL CONTINUE TO RECEIVE UPSTREAM RUNOFF, AND THAT THEY ARE RESPONSIBLE FOR MAINTENANCE OF THE DRAINAGE PATHWAY (NATURAL AND/OR MAN-MADE) THROUGH THE PARCEL, AND THAT THE COUNTY & FLOOD CONTROL DISTRICT(S) ARE NOT RESPONSIBLE FOR THE UPSTREAM RUNOFF OR FOR THE MAINTENANCE OF THE DRAINAGE PATHWAY
- 17. A DOWNSTREAM ANALYSIS FOR STORMWATER RUNOFF WAS PERFORMED. THERE WILL BE NO SIGNIFICANT IMPACT TO DOWNSTREAM PROPERTIES DUE TO THE PROPOSED IMPROVEMENTS, SHOWN ON THESE PLANS. ONSITE STORMWATER WILL BE CONTROLLED VIA THE PROPOSED PERVIOUS PAVERS SYSTEM, WITH A SAFE OVERFLOW, VIA SHEET FLOW, TO OPAL CLIFF DRIVE.

# SANTA CRUZ COUNTY GENERAL NOTES

- 1. ALL CONSTRUCTION ACTIVITIES SHALL COMPLY WITH APPLICABLE REQUIREMENTS IN THE CURRENT EDITION OF THE "COUNTY OF SANTA CRUZ DESIGN CRITERIA."
- 2. UNLESS OTHERWISE AGREED UPON WITH THE COUNTY OF SANTA CRUZ, WORK SHALL BE LIMITED TO 8:00 A.M. TO 5:00 P.M. WEEKDAYS. NON-NOISE PRODUCING ACTIVITIES, SUCH AS INTERIOR PAINTING, SHALL NOT BE SUBJECT TO THIS RESTRICTION.
- 3. A "DISTURBANCE COORDINATOR" SHALL BE ESTABLISHED, PRIOR TO CONSTRUCTION, TO RESPOND TO CITIZEN COMPLAINTS AND INQUIRIES REGARDING CONSTRUCTION NOISE AND DUST. THE NAME, PURPOSE AND TELEPHONE NUMBER OF THE DISTURBANCE COORDINATOR SHALL BE POSTED ON A SIGN EASILY VISIBLE FROM OFF-SITE DURING THE ENTIRE TIME PROJECT GRADING AND CONSTRUCTION OCCURS. THE DISTURBANCE COORDINATOR SHALL INVESTIGATE THE CONCERN AND TAKE REMEDIAL ACTION, IF NECESSARY, WITHIN 24 HOURS OF RECEIVING A COMPLAINT OR INQUIRY.
- 4. ALL FIGURE (FIG.) REFERENCES, UNLESS OTHERWISE SPECIFIED, REFER TO STANDARD DRAWINGS IN THE CURRENT EDITION OF THE "COUNTY OF SANTA CRUZ DESIGN CRITERIA".
- 5. NO CHANGES IN THE APPROVED IMPROVEMENT PLANS SHALL BE MADE WITHOUT PRIOR APPROVAL OF THE DEPARTMENT OF PUBLIC WORKS.
- 6. NO LAND CLEARING, GRADING OR EXCAVATING SHALL TAKE PLACE BETWEEN OCTOBER 15 AND APRIL 15 UNLESS A SEPARATE WINTER EROSION CONTROL PLAN IS APPROVED BY THE PLANNING DIRECTOR. BETWEEN OCTOBER 15 AND APRIL 15, EXPOSED SOIL SHALL BE PROTECTED FROM EROSION AT ALL TIMES. DURING CONSTRUCTION SUCH PROTECTION MAY CONSIST OF MULCHING AND/OR PLANTING OF NATIVE VEGETATION OF ADEQUATE DENSITY. BEFORE COMPLETION OF THE PROJECT, ANY EXPOSED SOIL ON DISTURBED SLOPES SHALL BE PERMANENTLY PROTECTED FROM EROSION.
- 7. THE CONTRACTOR SHALL APPLY WATER TO ALL EXPOSED EARTH SURFACES AT INTERVALS SUFFICIENT TO PREVENT AIRBORNE DUST FROM LEAVING THE PROJECT SITE. ALL EXPOSED EARTH SHALL BE WATERED DOWN AT THE END OF THE WORK DAY.
- 8. THE CONTRACTOR SHALL NOTIFY THE COUNTY CONSTRUCTION ENGINEER (831-454-2160) 24 HOURS PRIOR TO START OF
- 9. UNLESS OTHERWISE INDICATED BY A GEOTECHNICAL ENGINEER, THE TOP 8" OF SUB-GRADE UNDER ALL PAVED (CONCRETE AND ASPHALT) SURFACES SUBJECT TO VEHICULAR USE SHALL BE COMPACTED TO A MINIMUM 95% RELATIVE COMPACTION.
- 10. CONTRACTOR SHALL FIELD VERIFY ALL UNDERGROUND UTILITIES AND SUBSTRUCTURES. PRIOR TO FURTHER CONSTRUCTION, THE ENGINEER MUST BE NOTIFIED, IN WRITING, OF ANY DISCREPANCIES THAT MAY EXIST.
- 11. PRIOR TO CONSIDERATION FOR FORMAL COUNTY ACCEPTANCE OF THE IMPROVEMENTS, AS-BUILT PLANS WILL BE PREPARED BY COUNTY STAFF. ANY CHANGES FROM THE IMPROVEMENT PLANS NOT PREVIOUSLY APPROVED BY THE DEPARTMENT OF PUBLIC WORKS WILL REQUIRE NEGOTIATION AND ADJUSTMENT TO THE SATISFACTION OF THE COUNTY.
- 12. THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO, OR USES OF, THESE PLANS. ALL CHANGES MUST BE IN WRITING AND MUST BE APPROVED BY THE ENGINEER PRIOR TO CONSTRUCTION.
- 13. UNLESS OTHERWISE NOTED, THE TERMS "INSTALL", "CONSTRUCT" AND "NEW (N)" INDICATE THAT THE CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL MATERIALS, PRODUCTS, EQUIPMENT, AND LABOR FOR SAID INSTALLATION AND
- CONSTRUCTION. 14. PURSUANT TO SECTIONS 16.40.040 AND 16.42.100 OF THE COUNTY CODE, IF AT ANY TIME DURING SITE PREPARATION, EXCAVATION, OR OTHER GROUND DISTURBANCE ASSOCIATED WITH THIS DEVELOPMENT, ANY
- ARTIFACT OR OTHER EVIDENCE OF AN HISTORIC ARCHEOLOGICAL RESOURCE OR A NATIVE AMERICAN CULTURAL SITE IS DISCOVERED, THE RESPONSIBLE PERSONS SHALL IMMEDIATELY CEASE AND DESIST FROM ALL FURTHER SITE EXCAVATION AND NOTIFY THE SHERIFF-CORONER IF THE DISCOVERY CONTAINS HUMAN REMAINS, OR THE PLANNING DIRECTOR IF THE DISCOVERY CONTAINS NO HUMAN REMAINS. THE PROCEDURES ESTABLISHED IN SECTIONS 16.40.010 AND 16.42.100, SHALL BE OBSERVED.
- 15. THE DIRECTOR OF PUBLIC WORKS, OR HIS AUTHORIZED REPRESENTATIVE, SHALL HAVE THE AUTHORITY TO "STOP WORK" IF THE WORK IS NOT BEING DONE IN ACCORDANCE WITH THE APPROVED IMPROVEMENT PLANS.



CENTERLINE PROFILE

FOR SLOPES OVER 15%
100mm (4") CONCRETE ON 100mm (4") SAND
OR
50mm (2") ASPHALT ON 150mm (6")
CLASS 2 BASE

REQUIREMENT FOR DRIVEWAYS WITH VALLEY GUTTER

CUBIC YARDS (BALANCE ON SITE)

# <u>NOTES</u>

- 1. ESTIMATE DOES NOT INCLUDE BUILDING OR RETAINING WALL FOUNDATIONS, UTILITY TRENCH VOLUMES OR ANY OVEREXCAVATION, IF REQUIRED BY SITE CONDITIONS.
- 2. ESTIMATE ASSUMES A 0% COMPACTION FACTOR ON ALL FILL MATERIAL AND A 0% EXPANSION FACTOR ON ALL CUT MATERIAL
- 3. PRIOR TO COMMENCEMENT OF WORK CONTRACTOR SHALL
- CONFIRM THAT ESTIMATES ARE CORRECT.




PERVIOUS PAVERS
OVER 9" CALTRANS CL 2 PERMEABLE MATERIAL, PROOF ROLL SUBBASE FOR SMOOTH/FLAT SUBBASE



LAND PLANNING

DRAWN BY:	DMR
DESIGNED BY:	DMR
DATE:	12/21/2020
SCALE:	AS NOTED
PROJECT NO:	20-036
SHEET:	



below.	<b>C</b> 3	
	SHEET:	
	PROJECT NO:	2
	SCALE:	F
11	DATE:	1
	DESIGNED BY:	
	DRAWN BY:	[

# **EROSION CONTROL NOTES**

- 1. THE EROSION CONTROL PLANS IN THIS SET SHALL BE REVIEWED AND IMPLEMENTED BY THE CONTRACTOR PRIOR TO COMMENCEMENT OF WORK.
- 2. THE CONTRACTOR SHALL ENSURE ALL MONITORING AND INSPECTIONS ARE PERFORMED AS REQUIRED ONSITE THROUGHOUT CONSTRUCTION.
- 3. NO LAND CLEARING, GRADING OR EXCAVATION SHALL BE DONE BETWEEN OCTOBER 15TH AND APRIL 15TH. ANY DEVIATION FROM THIS CONDITION REQUIRES REVIEW AND APPROVAL OF A SEPARATE WINTER EROSION CONTROL PLAN BY ENVIRONMENTAL PLANNING PRIOR TO BEGINNING CONSTRUCTION. THE DEVELOPER SHALL BE RESPONSIBLE FOR IMPLEMENTING AND MAINTAINING SITE EROSION CONTROL AT ALL TIMES.
- 4. IT SHALL BE THE RESPONSIBILITY OF THE OWNER AND THE PERMITTEE TO ENSURE THAT EROSION DOES NOT OCCUR FROM ANY ACTIVITY DURING OR AFTER PROJECT CONSTRUCTION. ADDITIONAL MEASURES, BEYOND THOSE SPECIFIED, MAY BE REQUIRED BY THE PLANNING DIRECTOR AS DEEMED NECESSARY TO CONTROL ACCELERATED EROSION.
- PRIOR TO ANY FORECAST RAIN AND ANYTIME BETWEEN OCTOBER 15 AND APRIL 15, AT THE END OF EACH WORKDAY, AT THE END OF EACH WORKWEEK, THE DEVELOPER SHALL IMPLEMENT ALL TEMPORARY MEASURES NECESSARY TO PREVENT EROSION AND SILTATION, UNTIL THE PROJECT HAS BEEN FINALIZED. THESE MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, DIRECT SEEDING OF THE AFFECTED AREAS, STRAW MULCHING, AND/OR INSTALLATION OF STRAW BALES DAMS/SILT FENCES.
- DURING CONSTRUCTION, NO TURBID WATER SHALL BE PERMITTED TO LEAVE THE SITE. USE OF SILT AND GREASE TRAPS, FILTER BERMS, HAY BALES OR SILT FENCES SHALL BE USED TO PREVENT SUCH DISCHARGE.
- 7. ALL AREAS ON- AND OFF-SITE EXPOSED DURING CONSTRUCTION ACTIVITIES, IF NOT PERMANENTLY LANDSCAPED PER PLAN, SHALL BE PROTECTED BY MULCHING AND/OR SEEDING WITH ANNUAL WINTER BARLEY.
- 8. ALL EXCAVATED MATERIAL SHALL BE REMOVED TO AN APPROVED DISPOSAL SITE OR DISPOSED OF ON-SITE IN A MANNER THAT WILL NOT CAUSE EROSION.
- 9. ANY MATERIAL STOCKPILED, FOR LONGER THAN 14 DAYS, DURING CONSTRUCTION SHALL BE COVERED WITH PLASTIC.
- 10. UPON COMPLETION OF CONSTRUCTION, ALL REMAINING EXPOSED SOILS SHALL BE PERMANENTLY REVEGETATED PER LANDSCAPING PLAN. THE PROTECTION SHALL BE INSTALLED PRIOR TO CALLING FOR FINAL APPROVAL OF THE PROJECT AND AT ALL TIMES BETWEEN OCTOBER 15 AND APRIL 15. SUCH PROTECTION SHALL BE MAINTAINED FOR AT LEAST ONE WINTER UNTIL PERMANENT PROTECTION IS ESTABLISHED.
- 11. EXPOSED SOIL ON SLOPES GREATER THAN 20% SHALL BE SEEDED, COVERED WITH 2 INCHES OF STRAW, AND AN EROSION CONTROL BLANKET. THE EROSION CONTROL BLANKET SHALL BE STAKED IN PLACE.
- 12. IT IS THE DEVELOPER'S RESPONSIBILITY TO SEE THAT ADDITIONAL MEASURES, NECESSARY TO CONTROL SITE EROSION AND PREVENT SEDIMENT TRANSPORT OFF-SITE ARE IMPLEMENTED.
- 13. ALL SPILLS AND/OR LEAKS SHALL BE IMMEDIATELY CLEANED UP AND MITIGATED PER THE CONTRACTORS O&M STANDARDS.

# STORMWATER O&M PLAN

- 1. REFER TO THE RECORDED STORMWATER MAINTENANCE AGREEMENT (SCC FIG. SWM-25A) FOR ADDITIONAL SITE/PROJECT INFORMATION AND REQUIREMENTS, AS WELL AS RESPONSIBLE PARTY AGREEMENT.
- 2. STORMWATER MAINTENANCE AGREEMENT SHALL TRANSFER WITH
- 3. BELOW MAINTENANCE SPECIFICATIONS REFER TO POST-CONSTRUCTION REQUIREMENTS, REFER TO THE PROJECT EROSION CONTROL PLAN (SHEET C4) FOR MAINTENANCE REQUIREMENTS DURING THE CONSTRUCTION PHASE OF THE PROJECT.
- 4. MAINTENANCE AGREEMENT REFERS TO ALL PRIVATELY OWNED STORMWATER FACILITIES.
- 5. SUMMARIZED MAINTENANCE REQUIREMENTS FOR DRAINAGE FACILITIES:

# 5.1. ROOF DOWNSPOUTS:

5.1.1. ALL DOWNSPOUTS AND ROOF GUTTERS SHALL BE INSPECTED YEARLY FOR SEDIMENT AND/OR TRASH BUILD-UP. ALL SEDIMENT AND TRASH SHALL BE REMOVED AND PROPERLY DISPOSED OF.


# 5.2. GRADED SWALES:


- 5.2.1. ROUTINE MAINTENANCE ON AN ANNUAL BASIS SHALL INCLUDE TRASH AND DEBRIS REMOVAL, AND REMOVAL OF LEAVES DURING AND AFTER FALL LEAF DROP.
- 5.2.2. RECOMMENDED INSPECTIONS ON AN ANNUAL BASIS INCLUDE: 5.2.2.1. ENSURE INFLOW AND OUTFLOW AREAS ARE SECURE AND NO EROSION HAS OCCURRED. ADD ROCK DISSIPATION PADS OR CHECK DAMS AS NECESSARY TO REDUCE
- FLOWS AND ELIMINATE EROSION. 5.2.2.2. IF VISIBLE SEDIMENT EXIST AT BOTTOM OF FACILITY, SEDIMENT SHALL BE REMOVED TO ENSURE PROPER FLOW THROUGH.
- 5.2.2.3. IF EXCESSIVE PONDING OF WATER IS OCCURRING (2-3 DAYS AFTER THE END OF A STORM) CONFIRM LEAF, DEBRIS OR SEDIMENT BUILD-UP IS NOT IMPEDING FLOW, REMOVE AS NECESSARY.
- 5.2.2.4. IF VEGETATED ENSURE ALL VEGETATION IS HEALTHY. REMOVE AND REPLACE ALL DEAD OR DYING VEGETATION.

# SOURCE CONTROL MEASURES

BELOW ARE THE MEANS AND METHODS TO CONTROLLING POLLUTING ACTIVITIES:

- INDOOR & STRUCTURAL PEST CONTROL ALL PEST CONTROL MEASURES SHALL BE PERFORMED TO PREVENT ANY DISCHARGES INTO THE STORM DRAIN SYSTEM.
- LANDSCAPE/OUTDOOR PESTICIDE USE PESTICIDES SHALL BE USED ONLY IF NECESSARY AND SHALL BE LIMITED TO REQUIRED TREATMENT AREA. SPOT TREATMENT WITH HANDHELD SPRAYER SHALL BE USED IN LOW QUANTITIES.
- OUTDOOR STORAGE OF EQUIPMENT OR MATERIALS ALL MATERIALS, CONSTRUCTION OR OTHER, SHALL BE STORED INDOORS OR WITHIN A COVERED (PROTECTED) AREA.
- UNAUTHORIZED NON-STORMWATER DISCHARGES ALL UNAUTHORIZED NON-STORMWATER DISCHARGES, DURING AND AFTER CONSTRUCTION, SHALL BE REPORTED TO THE COUNTY OF SANTA CRUZ. DISCHARGES SHALL BE MITIGATED PER COUNTY GUIDANCE.
- BUILDING & GROUND MAINTENANCE ANY ROUTINE MAINTENANCE PERFORMED SHALL BE COMPLETED TO REDUCE OR ELIMINATE ANY NON-STORMWATER DISCHARGES FROM THE SITE.






# INSPECTION AND MAINTENANCE

1. THE CONTRACTORS WATER POLLUTION CONTROL (WPCM) MANAGER SHALL MONITOR ON SITE CONCRETE WASTE STORAGE AND DISPOSAL PROCEDURES AT LEAST WEEKLY.


WITH ENGINEER PRIOR TO INSTALLATION

- 2. THE WPCM SHALL MONITOR CONCRETE WORKING TASKS, SUCH AS SAW CUTTING, CORING, GRINDING AND GROOVING DAILY TO ENSURE PROPER METHODS ARE EMPLOYED AS DIRECTED BY THE ENGINEER.
- 3. TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE MAINTAINED TO PROVIDE ADEQUATE HOLDING CAPACITY WITH A MINIMUM FREEBOARD OF 4 INCHES FOR ABOVE GRADE FACILITIES AND 12 INCHES FOR BELOW GRADE FACILITIES. MAINTAINING TEMPORARY CONCRETE WASHOUT FACILITIES SHALL INCLUDE REMOVING AND DISPOSING OF HARDENED CONCRETE AND RETURNING THE FACILITIES TO A FUNCTIONAL CONDITION. HARDENED CONCRETE SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR.
- 4. EXISTING FACILITIES MUST BE CLEANED, OR NEW FACILITIES MUST BE CONSTRUCTED AND READY FOR USE ONCE THE WASHOUT IS 75% FULL.
- 5. TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE INSPECTED FOR DAMAGE (I.E. TEARS IN POLYETHYLENE LINER, MISSING SANDBAGS, ETC.). DAMAGED FACILITIES SHALL BE REPAIRED.

**CONCRETE WASHOUT** 



# TYPICAL INSTALLATION



# FIBER ROLLS PART


# CONSTRUCTION SPECIFICATIONS

- 1. PREPARE SLOPE BEFORE THE FIBER ROLL PROCEDURE IS STARTED. SHALLOW GULLIES SHOULD BE SMOOTHED AS WORK PROGRESSES.
- 2. DIG SMALL TRENCHES ACROSS SLOPE ON CONTOUR, TO PLACE FIBER ROLLS IN. THE TRENCH SHOULD BE DEEP ENOUGH TO ACCOMMODATE HALF THE THICKNESS OF THE FIBER ROLL. WHEN THE SOIL IS LOOSE AND UNCOMPACTED, THE TRENCH SHOULD BE DEEP ENOUGH TO BURY THE FIBER ROLL 2/3 OF ITS THICKNESS BECAUSE THE GROUND WILL SETTLE. IT IS CRITICAL THAT FIBER ROLLS ARE INSTALLED PERPENDICULAR TO WATER MOVEMENT, PARALLEL TO THE SLOPE CONTOUR.
- 3. START BUILDING TRENCHES AND INSTALL FIBER ROLLS FROM THE BOTTOM OF THE SLOPE AND WORK UP.
- 4. CONSTRUCT TRENCHES AT CONTOUR INTERVALS OF THREE TO EIGHT FEET APART DEPENDING ON STEEPNESS OF SLOPE. THE STEEPER THE SLOPE, THE CLOSER TOGETHER THE TRENCHES.
- 5. LAY THE FIBER ROLL ALONG THE TRENCHES FITTING IT SNUGLY AGAINST THE SOIL. MAKE SURE NO GAPS EXIST BETWEEN THE SOIL AND THE FIBER ROLL. USE A STRAIGHT BAR TO DRIVE HOLES THROUGH THE FIBER ROLL AND INTO THE SOIL FOR THE WOODEN STAKES.
- 6. DRIVE THE STAKE THROUGH THE PREPARED HOLE INTO THE SOIL. LEAVE ONLY ONE OR TWO INCHES OF STAKE EXPOSED ABOVE FIBER ROLL. IF USING WILLOW STAKES REFER TO USDA SOIL CONSERVATION SERVICE TECHNICAL GUIDE, BIOENGINEERING, FOR GUIDELINES TO PREPARING LIVE WILLOW MATERIAL.
- 7. INSTALL STAKES AT LEAST EVERY FOUR FEET APART THROUGH FIBER ROLL. ADDITIONAL STAKES MAY BE DRIVEN ON THE DOWNSLOPE SIDE OF THE TRENCHES ON HIGHLY EROSIVE OR VERY STEEP SLOPES.

# INSTALLATION AND MAINTENANCE

- 8. INSPECT THE FIBER ROLL AND THE SLOPES AFTER SIGNIFICANT STORMS. MAKE SURE THE FIBER ROLLS ARE IN CONTACT WITH THE
- 9. REPAIR ANY RILLS OR GULLIES PROMPTLY.
- 10. RESEED OR REPLANT VEGETATION IF NECESSARY UNTIL THE SLOPE IS STABILIZED.


# FIBER ROLLS PART 2



- 1. FILTER FABRIC BARRIERS SHALL BE INSPECTED WEEKLY AFTER EACH SIGNIFICANT STORM - 1 INCH RAINFALL (25.4 MM) IN 24 HOUR PERIOD. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
- 2. SEDIMENT SHOULD BE REMOVED WHEN IT REACHES 3" MAXIMUM HEIGHT. AT THAT TIME INSPECT THE FILTER MATERIAL FOR TEARS AND CLEAN OR REPLACE AS REQUIRED.
- 3. THE REMOVED SEDIMENT SHALL BE DISTRIBUTED EVENLY ACROSS AREAS ON-SITE, CONFORM WITH THE EXISTING GRADE AND BE REVEGETATED OR OTHERWISE STABILIZED PER EROSION CONTROL NOTES.

# **CATCH BASIN PROTECTION** NTS





12/21/2020

AS NOTE

CIVIL ENGINEERING

LAND PLANNING PROJECT MANAGEMENT

**CONSTRUCTION SUPPORT** 

QSD AND QSP SERIVCES

2905 KRISTIE COURT

SANTA CRUZ, CA 95065

TEL (831) 462-2905

www.ramseycivilengineering.co

DAVID RAMSEY

APN# 033-171-08

PLAN TYPE

RCE# 73735

GRAPHIC SCALE: 1 INCH = 10 FEET

INSPECTION AND MAINTENANCE

