COUNTY OF SANTA CRUZ PLANNING DEPARTMENT 701 Ocean Street, 4th Floor Santa Cruz, CA 95060 (831) 454-2580

NOTICE OF PENDING ACTION

The Planning Department has received the following application. The identified planner may be contacted for specific information on this application.

APPLICATON NUMBER: 241385 APN: 029-043-13 SITUS: 2100 Chanticleer Ave, Santa Cruz CA 95062

Builder's Remedy - Proposal to demolish an existing single family dwelling and construct an eight unit multifamily building with detached garage. Requires an Administrative Site Development Permit.

Project located on the northeast corner of the intersection of Chanticleer Ave and Mattison Lane in the Live Oak Planning area (2100 Chanticleer Ave).

OWNER: 2100 Chanticleer LLC

APPLICANT: 2100 Chanticleer LLC SUPERVISORIAL DISTRICT: 1

PLANNER: Nathan MacBeth, (831) 454 -3118


EMAIL: Nathan.MacBeth@santacruzcountyca.gov

Public comments must be received by 5:00 p.m. 08/01/2025. A decision will be made on or shortly after 08/04/2025.

Appeals of the decision will be accepted until 5:00 p.m. two weeks after the decision date. Planner will provide notification of decision to any requesting party.

Information regarding the appeal process, including required fees, may be obtained by phoning (831) 454-2130.





WEST SIDE OF CHANTICLEER, NORTH OF PROPOSED SITE



WEST SIDE OF CHANTICLEER, SOUTH OF PROPOSED SITE




2105 CHANTICLEER AVE 2035 CHAN


EAST SIDE OF CHANTICLEER, NORTH OF PROPOSED SITE





EAST SIDE OF CHANTICLEER, SOUTH OF PROPOSED SITE

















RECOMMENDED BMP MAINTENANCE		
INSPECTION	MAINTENANCE ACTIVITY	SUGGESTED FREQUENCY
INSPECT DOWNSPOUTS & SWALES TO ENSURE STORMWATER IS PROPERLY CONVEYED.	REPAIR BLOCKED OR DIVERTED CONVEYANCES.	DURING MAJOR STORMS
INSPECT DOWNSPOUTS, CATCH BASINS & SWALES FOR ACCUMULATED SEDIMENT AND DEBRIS.	REMOVE SEDIMENT AND DEBRIS.	ANNUALLY IN SPRING AND AFTER MAJOR STORMS
INSPECT FOR EROSION ESPECIALLY AT SWALES & DOWNSPOUT OUTLETS.	IDENTIFY CAUSES FOR EROSION AND STABILIZE.	ANNUALLY IN SPRING AND AFTER MAJOR STORMS


AS NECESSARY

REPAIR STRUCTURAL COMPONENTS

VEHICLE STORAGE AND MAINTENANCE

- EXISTING STREET SECTION





PERMEABLE PAVER DETAIL SCALE: 1"=1'

OVER NON-COMPACTED SUBGRADE

MINIMUM PERMEABLE PAVER INFILTRATION RATE SHALL BE 100 INCHES/HOUR WHEN TESTED AFTER CONSTRUCTION USING ASTM C-1701 OR APPROVED EQUIVALENT TEST. IF PERMEABLE PAVER INFILTRATION RATE FALLS BELOW 10 INCHES/HOUR DURING FUTURE TESTING, MAINTENANCE IS REQUIRED.

GRADING NOTES

OF CALIFORNIA STANDARD SPECIFICATIONS.

- 1. UNDERGROUND UTILITIES SHOWN ARE APPROXIMATE. VERIFICATION IS THE RESPONSIBILITY OF THE CONTRACTOR. PRIOR TO EXCAVATION, CONTRACTOR SHALL LOCATE ALL EXISTING UNDERGROUND UTILITIES. CALL 811 TO HAVE UTILITIES LOCATED AND MARKED.
- 2. VEGETATION, ROOTS AND DELETERIOUS MATERIALS SHALL BE REMOVED FROM AREA TO BE GRADED PRIOR TO GRADING.
- 3. CUT SLOPES SHALL BE NO STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL IN NATIVE MATERIAL AS DETERMINED BY THE ENGINEER.
- 4. FILL SLOPES SHALL BE NO STEEPER THAN 2 HORIZONTAL TO 1 VERTICAL.
- 5. FILL SHALL BE COMPACTED TO 90% RELATIVE COMPACTION UNLESS OTHERWISE NOTED. SEE GEOTECHNICAL INVESTIGATION FOR FURTHER SPECIFICATIONS.
- 6. AFTER GRADING, SPREAD TOPSOIL FROM STRIPPINGS ON SLOPES AND LANDSCAPED AREAS 3" TO 6" DEEP.
- 7. BETWEEN OCTOBER 15 AND APRIL 15, EXPOSED SOIL SHALL BE PROTECTED FROM EROSION AT ALL TIMES. DURING CONSTRUCTION SUCH PROTECTION MAY CONSIST OF MULCHING AND/OR PLANTING OF NATIVE VEGETATION OF ADEQUATE DENSITY. BEFORE COMPLETION OF THE PROJECT, ANY EXPOSED SOIL ON DISTURBED SLOPES SHALL BE PERMANENTLY PROTECTED FROM EROSION.
- 8. CUT AND FILL SLOPES SHALL BE PLANTED WITH ANNUAL RYE GRASS (40 LBS/ACRE) AND MULCHED WITH COMPOST.
- 9. CONCRETE IN DRIVEWAYS SHALL HAVE A COMPRESSIVE STRENGTH OF 3500 PSI @ 28 DAYS.
- 10. THE UPPER 8 INCHES OF SUBGRADE IN DRIVEWAY AREAS SHALL BE COMPACTED TO 95% RELATIVE COMPACTION. SEE GEOTECHNICAL INVESTIGATION FOR FURTHER SPECIFICATIONS.

11. AGGREGATE BASE SHALL BE CLASS 2 IN CONFORMANCE WITH SECTION 26 OF THE STATE

- 12. ASPHALT CONCRETE SHALL BE TYPE B AND SHALL CONFORM TO THE PROVISIONS IN
- SECTION 39 OF CALTRANS STANDARD SPECIFICATIONS. THE AGGREGATE SHALL CONFORM TO THE GRADING SPECIFIED IN SECTION 39-2.02 OF CALTRANS STANDARD SPECIFICATIONS FOR THE 1/2" MAXIMUM MEDIUM GRADATION.
- 13. CONSTRUCTION CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY, AND THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.
- 14. ALL DEMOLITION, SITE CLEARING AND PREPARATION, SUBGRADE PREPARATION AND GRADING, ETC. SHOULD BE PERFORMED IN ACCORDANCE WITH THE RECOMMENDATIONS OUTLINE IN THE GEOTECHNICAL REPORT FOR THIS PROJECT BY CORNERSTONE EARTH GROUP, DATED AUGUST

STORM WATER POLLUTION CONTROL NOTES

1. CONSTRUCTION CONTRACTOR SHALL BE RESPONSIBLE TO MAINTAIN EROSION CONTROL MEASURES BETWEEN OCTOBER 15 AND APRIL 15. DURING AND AFTER MAJOR STORMS, EROSION CONTROL DEVICES SHALL BE INSPECTED AND MODIFIED AS REQUIRED TO PREVENT EROSION ON PROJECT SITE AND SILT FROM FLOWING INTO THE ROAD OR DRAINAGE COURSE.

STABILIZED CONSTRUCTION ENTRANCE

- 2. BETWEEN OCTOBER 15TH AND APRIL 15TH EXPOSED SOIL SHALL BE PROTECTED FORM EROSION AT ALL TIMES. HAY BALES, FILTER BERM, SILT FENCES OR OTHER MEANS HALL BE EMPLOYED TO PREVENT SEDIMENT FROM LEAVING THE SITE OR ENTERING ANY WATERCOURSE.
- 3. DURING CONSTRUCTION, NO TURBID WATER SHALL BE PERMITTED TO ENTER A DRAINAGE CHANNEL OR STORM DRAIN SYSTEM. USE OF SILT AND GREASE TRAPS, FILTER BERMS, HAY BALES OR SILT FENCES SHALL BE USED TP PREVENT SUCH DISCHARGE.
- 4. ALL AREAS ON AND OFF SITE EXPOSED DURING CONSTRUCTION ACTIVITIES, IF NOT PERMANENTLY LANDSCAPED PER PLAN, SHALL BE PROTECTED BY MULCHING AND/OR PLANTING OF ANNUAL RYE GRASS AT A RATE OF 40 LBS PER ACRE.
- 5. ANY MATERIAL STOCKPILED ON-SITE SHALL BE COVERED WITH PLASTIC, ESPECIALLY DURING THE WINTER MONTHS OR DURING PERIODS OF RAIN.
- 6. EXPOSED SOIL ON SLOPES GREATER THAN 20% SHALL BE SEEDED, COVERED WITH 2 INCHES OF STRAW, AND AN EROSION CONTROL BLANKET. THE EROSION CONTROL BLANKET SHALL BE STAKED
- 7. IT IS THE DEVELOPER'S RESPONSIBILITY TO SEE THAT ADDITIONAL MEASURES, NECESSARY TO CONTROL SITE EROSION AND PREVENT SEDIMENT TRANSPORT OFF-SITE ARE IMPLEMENTED.
- 8. EROSION AND SEDIMENT CONTROL MEASURES MUST REMAIN FUNCTIONAL AND BE MAINTAINED THROUGHOUT THE WINTER SEASON. FAILURE TO ADEQUATELY MAINTAIN EROSION AND SEDIMENT CONTROL MEASURES CONSTITUTE A VIOLATION OF THE ISSUED BUILDING OR OTHER PERMIT. MAINTAIN POSITIVE DRAINAGE AWAY FROM ALL STRUCTURES. COVER ALL DISTURVED SOIL AS NOTED ABOVE.

CONSTRUCTION MATERIALS

WATER SHALL BE PREVENTED.

ALL LOOSE STOCKPILED CONSTRUCTION MATERIALS THAT ARE NOT ACTIVELY BEING USED (I.E. SOIL, SPOILS,

INSPECT SITE FOR UNUSUAL OR

UNSAFE CONDITIONS OR DAMAGE.

- ALL CHEMICALS SHALL BE STORED IN WATERTIGHT CONTAINERS (WITH APPROPRIATE SECONDARY) CONTAINMENT TO PREVENT ANY SPILLAGE OR LEAKAGE) OR IN A STORAGE SHED (COMPLETELY ENCLOSED).
- EXPOSURE OF CONSTRUCTION MATERIALS TO PRECIPITATION SHALL BE MINIMIZED. THIS DOES NOT INCLUDE MATERIALS AND EQUIPMENT THAT ARE DESIGNED TO BE OUTDOORS AND EXPOSED TO ENVIRONMENTAL CONDITIONS (I.E. POLES, EQUIPMENT PADS, CABINETS, CONDUCTORS, INSULATORS, BRICKS, ETC.).
- BEST MANAGEMENT PRACTICES TO PREVENT THE OFF-SITE TRACKING OF LOOSE CONSTRUCTION AND LANDSCAPE MATERIALS SHALL BE IMPLEMENTED. WASTE MANAGEMENT

AGGREGATE, FLY-ASH, STUCCO, HYDRATED LIME, ETC.) SHALL BE COVERED AND BERMED.

- DISPOSAL OF ANY RINSE OR WASH WATERS OR MATERIALS ON IMPERVIOUS OR PERVIOUS SITE SURFACES OR INTO THE STORM DRAIN SYSTEM SHALL BE PREVENTED.
- SANITATION FACILITIES SHALL BE CONTAINED (E.G., PORTABLE TOILETS) TO PREVENT DISCHARGES OF POLLUTANTS TO THE STORM WATER DRAINAGE SYSTEM OR RECEIVING WATER, AND SHALL BE LOCATED A MINIMUM OF 20 FEET AWAY FROM AN INLET, STREET OR DRIVEWAY, STREAM, RIPARIAN AREA OR OTHER DRAINAGE FACILITY.
- SANITATION FACILITIES SHALL BE INSPECTED REGULARLY FOR LEAKS AND SPILLS AND CLEANED OR REPLACED
- COVER WASTE DISPOSAL CONTAINERS AT THE END OF EVERY BUSINESS DAY AND DURING A RAIN EVENT.
- DISCHARGES FROM WASTE DISPOSAL CONTAINERS TO THE STORM WATER DRAINAGE SYSTEM OR RECEIVING
- STOCKPILED WASTE MATERIAL SHALL BE CONTAINED AND SECURELY PROTECTED FROM WIND AND RAIN AT ALL TIMES UNLESS ACTIVELY BEING USED.

- SITE HOUSEKEEPING REQUIREMENTS
 - - PROCEDURES THAT EFFECTIVELY ADDRESS HAZARDOUS AND NON-HAZARDOUS SPILLS SHALL BE IMPLEMENTED.

ANNUALLY IN SPRING

AND AFTER MAJOR STORMS

- EQUIPMENT AND MATERIALS FOR CLEANUP OF SPILLS SHALL BE AVAILABLE ON SITE AND THAT SPILLS AND LEAKS SHALL BE CLEANED UP IMMEDIATELY AND DISPOSED OF PROPERLY.
- CONCRETE WASHOUT AREAS AND OTHER WASHOUT AREAS THAT MAY CONTAIN ADDITIONAL POLLUTANTS SHALL BE CONTAINED SO THERE IS NO DISCHARGE INTO THE UNDERLYING SOIL AND ONTO THE SURROUNDING

-FUTURE WIDENING

- MEASURES SHALL BE TAKEN TO PREVENT OIL, GREASE, OR FIE1 TO LEAK IN TO THE GROUND, STORM DRAINS OR SURFACE WATERS.
- ALL EQUIPMENT OR VEHICLES, WHICH ARE TO BE FUELED, MAINTAINED AND STORED ONSITE SHALL BE IN A DESIGNATED AREA FITTED WITH APPROPRIATE BMPS.
- LEAKS SHALL BE IMMEDIATELY CLEANED AND LEAKED MATERIALS SHALL BE DISPOSED OF PROPERLY. LANDSCAPE MATERIALS

CONTAIN STOCKPILED MATERIALS SUCH AS MULCHES AND TOPSOIL WHEN THEY ARE NOT ACTIVELY BEING

- . CONTAIN FERTILIZERS AND OTHER LANDSCAPE MATERIALS WHEN THEY ARE NOT ACTIVELY BEING USED.
- DISCONTINUE THE APPLICATION OF ANY ERODIBLE LANDSCAPE MATERIAL WITHIN 2 DAYS BEFORE A FORECASTED RAIN EVENT OR DURING PERIODS OF PRECIPITATION.
- APPLY ERODIBLE LANDSCAPE MATERIAL AT QUANTITIES AND APPLICATION RATES ACCORDING TO MANUFACTURER'S RECOMMENDATIONS OR BASED ON WRITTEN SPECIFICATIONS BY KNOWLEDGEABLE AND EXPERIENCED FIELD PERSONNEL.
- STACK ERODIBLE LANDSCAPE MATERIAL ON PALLETS AND COVERING OR STORING SUCH MATERIALS WHEN NOT. BEING USED OR APPLIED.

IGNED PLAN IS THE ONLY PLAN TO USED FOR CONSTRUCTION.


N

OR APN PARTMENTS
HANTICLEE


ER 00 21

SCALE: AS NOTED DESIGNED BY: JR DRAWN BY: OCT. 10, 2024 REVISED: MAY 7, 2025 JOB NO.: 24038















23 SUMMER SOLSTICE 2PM


























 $1 \frac{\text{WEST ELEVATION}}{1/4" = 1'-0"}$













 $1 \quad \frac{\text{EAST ELEVATION}}{1/4" = 1'-0"}$


















 $2 \frac{\text{SOUTH COLOR ELEVATION}}{\frac{1}{4}" = 1'-0"}$





SCALE: 1/4" - 1'-0"

FIRST WAVE APARTMENTS



