COUNTY OF SANTA CRUZ PLANNING DEPARTMENT 701 Ocean Street, 4th Floor Santa Cruz, CA 95060 (831) 454-2580

NOTICE OF PENDING ACTION

The Planning Department has received the following application. The identified planner may be contacted for specific information on this application.

APPLICATON NUMBER: 251166 APN: 053-161-17 SITUS ADDRESS: 1500 Bonita Drive, Aptos, CA 95003

Proposal to upgrade an existing water treatment system at Soquel Creek Water Districts Bonita well site, located at 1500 Bonita Drive. Project will treat hexavalent chromium (chromium-6) in compliance with the State Water Resources Control Board's Division of Drinking Water maximum contaminant levels. Project components include a new 4,000 square foot treatment building, a 100,000 gallon, partially buried backwash tank, contactor vessels, emergency generator, stormwater detention basin, sewer force main, and landscaping. A similar project approved under application 161033 has expired. Proposed project is functionally the same design as previously approved permit (161033, which has expired), but proposes to incorporate modern technology. Project requires a Coastal Development Permit, an Administrative Use Permit, and an addendum to the adopted Mitigated Negative Declaration (State Clearinghouse No. 2015062021).

Project site is located at 1500 Bonita Drive, approximately 0.5 miles north of the intersection of Bonita Drive and San Andreas Road.

OWNER: Soquel Creek Water District

APPLICANT: Skyler Murphy SUPERVISORIAL DISTRICT: 2

PLANNER: Evan Ditmars, (831) 454-3227

EMAIL: Evan.Ditmars@santacruzcountyca.gov

Public comments must be received by 5:00 p.m. September 12, 2025. A decision will be made on or shortly after September 15, 2025.


Appeals of the decision will be accepted until 5:00 p.m. two weeks after the decision date. If you would like to request a public hearing be held for this item, please contact the project planner listed on this notice.


Information regarding the appeal process, including required fees, may be obtained by phoning (831) 454-2130.

For more information, contact the project planner identified above.

SOQUEL CREEK WATER DISTRICT HEXAVALENT CHROMIUM REMOVAL PROJECT BONITA WTP AND SAN ANDREAS WELL

JULY 2025 COASTAL DEVELOPMENT PERMIT





(SCALE BAR IS 4" AT FULL SCALE) 0



SOQUEL CREEK WATER DISTRICT

DATE

APPROVED BY: ENGINEERING MANAGER

APN: 053-131-17

₽ BLACK & VEATCH

Black & Veatch Corporation
Walnut Creek, California



SOQUEL CREEK WATER DISTRICT

HEXAVALENT CHROMIUI REMOVAL PROJECT BONITA WTP AND SAN ANDREAS WELL

PRELIMINARY
NOT FOR
CONSTRUCTION

REVISIONS AND RECORD OF ISSUE
DESIGNED: CD
DETAILED: RT
CHECKED: RF

DATE: JULY 202
PROJECT NO.: 419795


APPROVED:


GENERAL

COVER SHEET, VICINITY MAP AND LOCATION MAP

G-1

C





AVOIDANCE MEASURE 2 - STORMWATER BASIN DESIGN: THE PROJECT STORM WATER BASIN SHALL BE DESIGNED TO AVOID ADVERSE EFFECTS TO SCLTS BY ENSURING THAT APPROPRIATE EXCLUSION STRUCTURES (E.G., EXCLUSION FENCING) ARE IN PLACE AROUND THE PROPOSED BASIN TO PREVENT SALAMANDERS FROM GETTING TRAPPED IN THE BASIN.

AVOIDANCE MEASURE 3 - SEWER FORCE MAIN: THE SEWER FORCE MAIN SHALL BE DESIGNED TO AVOID OPEN TRENCH CONSTRUCTION THROUGH THE SCLTS DRAINAGE.

AVOIDANCE MEASURE 4 - LIGHTING: REFER TO ELECTRICAL DWGS FOR AVOIDANCE MEASURE.

AVOIDANCE MEASURE 5 - SECONDARY CONTAINMENT: ALL TANKS AND STATIONARY EQUIPMENT THAT INVOLVE THE USE OF HAZARDOUS WASTE, CHEMICALS OR FUEL SHALL PROVIDED WITH SECONDARY CONTAINMENT AND WILL BE OPERATED IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS RELATED TO THE USE, STORAGE, AND TRANSPORT OF SUCH MATERIALS.

AVOIDANCE MEASURE 6 - FENCE REPAIR AND REPLACEMENT: THE EXISTING TREATMENT FACILITY SITE FENCING EXPECTED TO BE MAINTAINED WITH THE PROJECT. IN THE LONG-TERM, HOWEVER, FENCE REPAIRS AND ULTIMATE REPLACEMENT WILL LIKELY BE REQUIRED. ANY REPLACEMENT OF CROSSBARS AND CHAIN-LINK FENCE WILL PROVIDE FOR A SIMILAR PERMEABLE FENCE TO ALLOW FOR INDIVIDUAL SCLTS TO MOVE BACK AND FORTH. IF POLE REPLACEMENT IS REQUIRED AT SOME POINT, POLES SHALL BE REPLACED IN THE EXACT FOOTPRINT OF THE EXISTING POLES TO AVOID EXCAVATION IN UNDISTURBED HABITAT AREA.

AVOIDANCE MEASURE 7 - PROJECT TIMING: PROJECT CONSTRUCTION ACTIVITIES THAT OCCUR OUTSIDE THE PART OF THE TREATMENT FACILITY SITE PROTECTED BY EXCLUSION FENCING, IF ANY, SHALL BE TIMED TO OCCUR DURING THE DRY SEASON (NONBREEDING SEASON FOR SANTA CRUZ LONG-TOED SALAMANDER) (APRIL 15 THROUGH OCTOBER 15) TO MINIMIZE POTENTIAL EFFECTS TO SALAMANDER BREEDING AND DISPERSAL.

AVOIDANCE MEASURE 8 - ENVIRONMENTAL AWARENESS TRAINING: BEFORE THE START OF GROUND-DISTURBING ACTIVITIES AT THE TREATMENT FACILITY SITE, THE PROJECT BIOLOGIST SHALL PREPARE AND IMPLEMENT AN ENVIRONMENTAL AWARENESS TRAINING SESSION FOR WORKERS WHO WILL BE CONDUCTING THE CONSTRUCTION ACTIVITIES AND ONGOING OPERATIONS AT THE PROJECT SITE. TRAINING MATERIALS WILL INCLUDE DISCUSSION OF THE FOLLOWING:

- FEDERAL ENDANGERED SPECIES ACT, THE CALIFORNIA ENDANGERED SPECIES ACT, FISH AND GAME CODE, THE MIGRATORY BIRD TREATY ACT, AND THE CLEAN WATER ACT.
- CONSEQUENCES AND PENALTIES FOR VIOLATION OR NONCOMPLIANCE WITH THESE LAWS AND REGULATIONS AND PROJECT PERMITS.
- IDENTIFICATION AND VALUE OF SPECIAL-STATUS PLANTS, SPECIAL-STATUS WILDLIFE, AND JURISDICTIONAL WATER, AND EXPLANATIONS REGARDING THEIR VALUE. SPECIFICALLY EMPHASIZE IDENTIFICATION AND IMPORTANCE OF THE SANTA CRUZ LONG-TOED SALAMANDER AND ITS HABITAT.
- HAZARDOUS SUBSTANCE SPILL PREVENTION AND CONTAINMENT MEASURES.
- CONTACT PERSON IN THE EVENT OF THE DISCOVERY OF A SANTA CRUZ LONG-TOED SALAMANDER OR A DEAD OR INJURED WILDLIFE SPECIES.
- REVIEW OF AVOIDANCE MEASURES.

IN THE TRAINING, PROJECT RIMMING IN RELATION TO SPECIES' HABITAT AND SPECIES' LIFE STAGE REQUIREMENTS SHALL BE DETAILED AND DISCUSSED ON PROJECT MAPS, WHICH SHALL SHOW AREAS OF PLANNED AVOIDANCE MEASURES.

A FACT SHEET CONVEYING THIS INFORMATION SHALL BE PREPARED BY THE PROJECT BIOLOGIST FOR DISTRIBUTION TO THE PROJECT WORKERS AND OTHERS WHO ENTER THE PROJECT AREA. ON COMPLETION OF THE TRAINING, PROJECT WORKERS SHALL SIGN A FORM STATING THAT THEY ATTENDED THE TRAINING, UNDERSTAND THE INFORMATION PRESENTED, AND WILL COMPLY WITH THE TRAINING REQUIREMENTS. ALL SUBSEQUENT CREWS BROUGHT ONTO THE CONSTRUCTION SITE THROUGHOUT THE CONSTRUCTION PERIOD SHALL ALSO RECEIVE THIS TRAINING PRIOR TO WORKING ON THE SITE. THE CONTRACTOR SHALL KEEP THE SIGN-UP SHEETS ON SITE AT ALL TIMES.

AVOIDANCE MEASURE 9 - EXCLUSION FENCING: EXCLUSION FENCING WILL BE USED TO ESTABLISH NON-DISTURBANCE EXCLUSION ZONES TO RESTRICT PROJECT EQUIPMENT AND PERSONNEL FROM SENSITIVE AREAS AND RESTRICT FEDERAL AND STATE-LISTED WILDLIFE SPECIES (PARTICULARLY THE SCLTS) FROM ENTERING THE CONSTRUCTION AREAS. SENSITIVE AREAS LIMITS ARE INDICATED ON THE CIVIL PLANS DWGS.

THE WILDLIFE EXCLUSION FENCING WILL BE COMPOSED OF LIGHTWEIGHT PLASTIC MESH FENCE (ERTEC FENCE) DESIGNED WITH ONE-WAY ESCAPE TUNNELS TO ALLOW ANY UNIDENTIFIED SALAMANDERS WITHIN THE CONSTRUCTION AREA ACCESS TO AREAS OUTSIDE THE CONSTRUCTION AREA. THE CONTRACTOR SHALL ENSURE THAT ALL SENSITIVE AREAS ARE OFF-LIMITS TO PROJECT PERSONNEL AND EQUIPMENT. THE WILDLIFE EXCLUSION FENCING SHALL BE INSTALLED INTO THE GROUND BURIED AT LEAST 4 INCHES DEEP USING HAND TOOLS UNDER THE SUPERVISION OF THE PROJECT BIOLOGIST. EXCLUSION FENCING WILL BE INSPECTED ON A WEEKLY BASIS FOR SIGNS OF TEARS, SAGGING, OR OTHER DAMAGE, AND SHALL REPAIRED IMMEDIATELY BY THE CONTRACTOR.

AVOIDANCE MEASURE 10 - PRECONSTRUCTION SURVEY: WITHIN 24 HOURS PRIOR TO INITIAL GROUND-DISTURBING ACTIVITIES, THE TREATMENT FACILITY CONSTRUCTION AREA WILL BE SURVEYED BY QUALIFIED BIOLOGIST(S) FOR SALAMANDERS TO ASSESS THE SITE OF SALAMANDERS MOVING ABOVE-GROUND, OR TAKING REFUGE IN BURROW OPENINGS OR UNDER MATERIALS THAT COULD PROVIDED COVER, SUCH AS BOARDS, SCRAP METAL, WOODY DEBRIS, LEAF LITTER OR OTHER MATERIALS. THE QUALIFIED BIOLOGIST(S) WILL SURVEY THE ENTIRE SITE WITHIN THE EXCLUSION FENCING PRIOR TO ANY CONSTRUCTION AT THE SITE. IF ANY SCLTS ARE DISCOVERED WITHIN THE CONSTRUCTION AREA, THEN CONSTRUCTION ACTIVITIES MUST BE POSTPONED UNTIL THE SALAMANDER LEAVES THE CONSTRUCTION WORK AREA AND THE CALIFORNIA DEPARTMENT OF FISH AND WILDLIFE (CDFW) AND THE UNITED STATES FISH AND WILDLIFE SERVICE (USFWS) SHALL BE NOTIFIED BY TELEPHONE AND ELECTRONIC MAIL WITHIN 1 WORKING DAY. IF THE SCLTS DOES NOT LEAVE THE PROJECT SITE, THEN CDFW AND USFWS WILL BE CONTACTED TO DETERMINE HOW TO PROCEED. CONSTRUCTION WILL NOT BEGIN AGAIN UNTIL APPROVAL FROM CDFW AND USFWS IS OBTAINED.

AVOIDANCE MEASURE 11 - CONSTRUCTION MONITORING: A QUALIFIED BIOLOGIST SHALL BE PRESENT AT THE TREATMENT FACILITY SITE DURING THE INSTALLATION OF EXCLUSION FENCING, INSTALLATION OF THE BRIDGES, MAJOR GROUND-DISTURBING ACTIVITIES. AT A MINIMUM, THE BIOLOGIST SHALL VISIT THE SITE WEEKLY DURING CONSTRUCTION TO ENSURE THAT EXCLUSION FENCING IS IN GOOD CONDITION AND AVOIDANCE MEASURES ARE BEING IMPLEMENTED. THE BIOLOGIST(S) SHALL BE GRANTED THE AUTHORITY TO STOP ANY WORK THAT MAY RESULT IN THE TAKE OF LISTED SPECIES. IF THE BIOLOGIST(S) EXERCISED THIS AUTHORITY, THE CDFW AND THE USFWS SHALL BE NOTIFIED BY TELEPHONE AND ELECTRONIC MAIL WITHIN 1 WORKING DAY. THE BIOLOGIST IN CONSULTATION WITH CDFW AND USFWS WILL USE ADAPTIVE MANAGEMENT TO MODIFY AS NECESSARY PROJECT ACTIVITIES TO AVOID ALL IMPACTS TO LISTED SPECIES.

AVOIDANCE MEASURE 12 - ENTRAPMENT AVOIDANCE: TO PREVENT INADVERTENT ENTRAPMENT OF SCLTS OR OTHER ANIMALS DURING PROJECT CONSTRUCTION, ALL EXCAVATED, STEEP-WALLED HOLES OR TRENCHES MORE THAN 1 FOOT DEEP SHALL BE COVERED AT THE CLOSE OF EACH WORK DAY BY PLYWOOD OR SIMILAR MATERIALS, OR SHALL BE PROVIDED WITH ONE OR MORE ESCAPE RAMPS CONSTRUCTED OF EARTH FILL OR WOODEN PLANKS. BEFORE SUCH HOLES OR TRENCHES ARE FILLED, THEY SHALL BE THOROUGHLY INSPECTED FOR TRAPPED ANIMALS.

AVOIDANCE MEASURE 13 - GENERAL CONSTRUCTION GUIDELINES AND RESTRICTIONS:

- THE CONTRACTOR SHALL CONFINE ALL EQUIPMENT TO DESIGNATED WORK ZONES (INCLUDING ACCESS ROADS AND STAGING AREAS) WITHIN THE PROJECT AREA.
- VEHICLE AND EQUIPMENT MAINTENANCE OR FUELING SHALL OCCUR IN DESIGNATED STAGING AREAS AT LEAST 100 FEET FROM IDENTIFIED AQUATIC HABITATS.
- THE CONTRACTOR SHALL PROVIDE CLOSED GARBAGE CONTAINERS FOR THE DISPOSAL OF FOOD-RELATED TRASH ITEMS (E.G., WRAPPERS, CANS, BOTTLES, FOOD SCRAPS). PROJECT PERSONNEL WILL NOT FEED OR OTHERWISE ATTRACT WILDLIFE TO THE PROJECT AREA.
- NO PETS SHALL BE ALLOWED IN THE PROJECT AREA.

EROSION CONTROL MATERIALS SHALL BE WEED FREE.


- TO MINIMIZE DISTURBANCE OF NOCTURNAL AND/OR CREPUSCULAR WILDLIFE, WORK SHALL BEGIN NO SOONER THAN 15 MINUTES AFTER SUNRISE AND WILL CEASE NO LATER THAN 15 MINUTES BEFORE SUNSET, WHERE FEASIBLE.
- BIODEGRADABLE EROSION CONTROL MEASURES WILL BE USED WHENEVER POSSIBLE. SYNTHETIC EROSION CONTROL MATERIAL, INCLUDING MONOFILAMENT AND PLASTICS, SHALL NOT BE USED.


AVOIDANCE MEASURE 14 - EROSION AND SEDIMENT CONTROLS: REFER TO DWG C10 FOR AVOIDANCE MEASURE.


AVOIDANCE MEASURE 15 - INVASIVE WEED CONTROLS: THE FOLLOWING WEED CONTROL MEASURES SHALL BE IMPLEMENTED TO REDUCE THE INTRODUCTION OF INVASIVE WEEDS.


ALL EQUIPMENT SHALL BE CLEANED USING A BROOM OR SIMILAR DEVICE BEFORE IT ARRIVES ON SITE SO THAT IT IS FREE OF SOIL, SEEDS, AND PLANT PARTS.


IMPORTED FILL MATERIAL SHALL BE FREE FROM VEGETATION AND PLANT MATERIAL




















PLANTING NOTES


- 1. SEE SPECIFICATION SECTION 32 9300 FOR ADDITIONAL PLANTING REQUIREMENTS.
- 2. CONTRACTOR SHALL PROCURE PLANT SPECIES WITHIN THIRTY (30) DAYS OF AWARD OF THE CONTRACT. CONTRACTOR SHALL BE RESPONSIBLE FOR PLACING REQUIRED DEPOSITS TO ENSURE TIMELY PROCUREMENT OF THE SPECIFIED PLANTS. CONTRACTOR SHALL PROVIDE OWNER'S REPRESENTATIVE WITH WRITTEN VERIFICATION (RECEIPTS) SHOWING PROCUREMENT TO MEET THE PLANTING REQUIREMENTS. CONTRACTOR TO SUBMIT PHOTOGRAPHS OF ALL PLANTS FOR REVIEW AND APPROVAL BY OWNER'S REPRESENTATIVE. PLANTS MAY NEED TO BE CONTRACT GROWN TO ENSURE PLANT AVAILABILITY. SEE PLANTING SPECIFICATION SECTION 32 9300.
- 3. ALL EXISTING TREES TO REMAIN SHALL BE PROTECTED IN PLACE UNLESS NOTED OTHERWISE. CONTRACTOR SHALL BE RESPONSIBLE FOR DAMAGE OF ANY KIND TO EXISTING TREES DURING THE COURSE OF CONSTRUCTION.
- 4. HOLD FINISHED GRADES FOR SHRUB AREAS 1 1/2-INCHES BELOW TOP OF ADJACENT PAVEMENT OR WALLS, UNLESS OTHERWISE NOTED ON THE DRAWINGS.
- 4. GRADUALLY ROUND OFF TOPS AND TOES OF ALL PLANTED SLOPES TO PRODUCE A SMOOTH AND NATURAL TRANSITION BETWEEN EXISTING PLANTING, FINISH GRADES AND NEW PLANTING.
- 5. CONTRACTOR SHALL NOTIFY OWNER'S REPRESENTATIVE A MINIMUM OF FIVE (5) DAYS IN ADVANCE TO SCHEDULE PLANT DELIVERY DATES. OWNER'S REPRESENTATIVE SHALL INSPECT PLANTS UPON ARRIVAL AND RESERVES THE RIGHT TO REJECT PLANTS.
- 6. CONTRACTOR SHALL PLACE PLANTS AS SHOWN ON PLAN AND VERIFY LOCATION WITH OWNER'S REPRESENTATIVE. OWNER'S REPRESENTATIVE MAY REQUEST THAT CONTRACTOR ADJUST OR RELOCATE PLANTS ON-SITE AS NEEDED TO PROPERLY COMPLETE DESIGN.
- 7. CONTRACTOR TO PROTECT ALL NEW PLANTS FROM GOPHERS, RODENTS, DEER, AND OTHER ANIMALS. TYPE AND EXTENT OF PROTECTION MEASURES SHALL BE DETERMINED BY CONTRACTOR AND SUBMITTED TO OWNER'S REPRESENTATIVE FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
- 8. TYPICAL OF ALL TREES KEEP ALL SHRUBS, GRASSES, PERENNIALS, GROUNDCOVER, VINES OR SUCCULENTS PLANTINGS 18-INCHES CLEAR FROM ANY EXISTING OR NEW TREE TRUNK.

- 9. IF SOIL IS LIME TREATED, PLANTING AREAS TO BE EXCAVATED WITHIN 3-INCHES OF THE EDGE OF PAVING/CURB TO A DEPTH OF MINIMUM 18-INCHES BELOW LIME TREATMENT AND DISPOSED OF OFF-SITE. PLANTING AREAS TO BE FILLED WITH IMPORTED TOPSOIL AMENDED PER SOILS REPORT. PLANTING AREAS TO BE TESTED FOR PROPER DRAINAGE PRIOR TO PLANTING. SEE SPECIFICATION SECTION 32 9113 FOR ADDITIONAL REQUIREMENTS.
- 10. COMPACTED SOILS MUST BE TRANSFORMED TO A FRIABLE CONDITION TO MAXIMIZE WATER RETENTION.
- 11. INCORPORATE COMPOST INTO THE SOIL TO A MINIMUM OF 8-INCHES AT A MINIMUM RATE OF 6 CUBIC YARDS PER 1000 SQUARE FEET. SOILS WITH GREATER THAN 6% ORGANIC MATTER IN THE TOP 6-INCHES OF SOIL ARE EXEMPT FROM ADDING COMPOST AND TILLING.
- 12. PROVIDE A MINIMUM OF 3 INCHES OF WOOD CHIP MULCH TO SOIL SURFACE AFTER PLANTING, AROUND EXISTING TREES AND SHRUBS TO REMAIN, AND OVER ALL BARE GROUND WITHIN PROJECT BOUNDARIES. MULCH SHALL NOT BE PLACED WITHIN A 12-INCH DIAMETER OF TREE TRUNKS AND SHOULD BE KEPT FREE FROM THE CROWN OF ALL SHRUBS, GRASSES, AND PERENNIALS. SEE SPECIFICATION SECTION 32 93 00 FOR MULCH TYPE.
- 13. SOIL AMENDMENTS MUST BE INCORPORATED ACCORDING TO RECOMMENDATIONS OF THE SOIL ANALYSIS REPORT AND WHAT IS APPROPRIATE FOR THE PLANTS SELECTED.
- 14. CONTRACTOR TO REVIEW ALL PLANS AND SPECIFICATIONS FOR SUBMITTALS, TESTING, AND OTHER REQUIREMENTS. CONTRACTOR TO IMMEDIATELY NOTIFY OWNER'S REPRESENTATIVE OF ANY DISCREPANCIES BETWEEN SITE CONDITIONS AND INTENT OF THESE DRAWINGS. ANY CONFLICTS WILL BE RESOLVED PRIOR TO COMPLETING WORK.
- 15. CONTRACTOR TO COORDINATE, PAY FOR, AND SUBMIT ALL DOCUMENTATION FOR THE CERTIFICATE OF COMPLETION AS OUTLINED IN THE SPECIFICATIONS, WHICH WILL DOCUMENT COMPLIANCE WITH THE WATER EFFICIENT LANDSCAPE ORDINANCE.

PLANT IMAGES



QUERCUS AGRIFOLIA (COAST LIVE OAK)



ARCTOSTAPHYLOS X 'HOWARD MCMINN' (HOWARD MCMINN MANZANITA)



ROSA BANKSIAE 'ALBA PLENA' (WHITE LADY BANK'S ROSE)



HETEROMELES ARBUTIFOLIA

(TOYON)

CEANOTHUS 'RAY HARTMAN' (RAY HARTMAN WILD LILAC)



VITIS CALIFORNICA ROGER'S RED (ROGER'S RED GRAPE)



Black & Veatch Corporation
Walnut Creek, California



515 SWIFT ST. SANTA CRUZ CA 95060
PHONE 831.423.6040 | WWW.JLJA.COM
California Landscape Architect License 3163

SOQUEL CREEK WATER DISTRICT

HEXAVALENT CHROMIUM REMOVAL PROJECT BONITA WTP AND SAN ANDREAS WELL

50% DESIGN NOT FOR CONSTRUCTION

REVISIONS AND RECORD OF ISSUE SIGNED:

DESIGNED:
DETAILED:

APPROVED:

DATE: APRIL 11, 2025

PROJECT NO.: 419795

CHECKED:

LANDSCAPE


PLANT SCHEDULE, NOTES, AND IMAGES


L-02


PLOTTED: F07000 FILE:

(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1


L-02










(SCALE BAR IS 4" AT FULL SCALE) 0 1/2












PLOTTED: 7/3/2025 9:47:45 AM FILE: Autodesk Docs://419795 - SqCWD System Design/3D-A-EQMTB REVIT VERSION:

(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2










									DOC	OR SCHED	ULE (D)						
DOOR SIZE			DOOR								FRAME							
	DOOR							DETAILS		GLAZING						DIMENSIONS	3	7
LEVEL	No. (D)		WIDTH	HEIGHT	TYPE (D)	MATERIAL	HEAD	JAMB	SILL	TYPE (G)	HDWR	RATING	TYPE (F)	MATERIAL	HEAD	WIDTH	DEPTH	REMARKS
MAIN EQUIPMENT BUILI	DING																	
OPERATING FLOOR	101A		3'-0"	7'-2"	В	FRP	1	2	3	G1	-	-	F1	FRP	2"	2"	5 3/4"	
OPERATING FLOOR	101B		3'-0"	7'-2"	В	FRP	1	2	3	G1	-	-	F1	FRP	2"	2"	5 3/4"	
OPERATING FLOOR	101C		15'-0"	14'-8"	-	RA	-	-	-	-	-	-	-	ALUM			4"	
OPERATING FLOOR	101D	PR	3'-0"	7'-2"	В	FRP	1	2	3	G1	-	-	F1	FRP	2"	2"	5 3/4"	
OPERATING FLOOR	102A	PR	3'-0"	7'-2"	В	FRP	1	2	3	G1	-	-	F1	FRP	2"	2"	5 3/4"	
OPERATING FLOOR	103A	PR	3'-0"	7'-2"	С	FRP	1	2	3	G2	-	45 MIN	F1	FRP	2"	2"	5 3/4"	WIRE GLASS W/ SQUARE PATTERN
OPERATING FLOOR	104A		3'-0"	7'-2"	Α	FRP	1	2	3	-	-	45 MIN	F1	FRP	2"	2"	5 3/4"	
OPERATING FLOOR	105A		3'-0"	7'-2"	Α	FRP	1	2	3	_	_	45 MIN	F1	FRP	2"	2"	5 3/4"	

				LOUV	ER SCHE	EDULE (L)		
		OPE	NING	LOUVER					
LEVEL	LOUVER No. (L)	WIDTH	HEIGHT	TYPE	HEAD	JAMB	SILL	TOP ELEV AFF	REMARKS
MAIN EQUIPMENT BUILI	DING								
OPERATING FLOOR	101A	3'-4"	2'-8"	ALUM	4	5	6	12'-8"	
OPERATING FLOOR	101B	3'-4"	2'-8"	ALUM	4	5	6	12'-8"	
OPERATING FLOOR	101C	3'-4"	2'-8"	ALUM	4	5	6	12'-8"	
OPERATING FLOOR	101D	3'-4"	2'-8"	ALUM	4	5	6	12'-8"	
OPERATING FLOOR	101E	3'-4"	2'-8"	ALUM	4	5	6	12'-8"	
OPERATING FLOOR	102A	2'-0"	2'-0"	ALUM	4	5	6	12'-0"	
OPERATING FLOOR	102B	2'-0"	2'-0"	ALUM	4	5	6	12'-0"	
OPERATING FLOOR	103A	4'-0"	4'-0"	ALUM	4	5	6	14'-0"	
OPERATING FLOOR	103B	3'-6"	3'-6"	ALUM	4	5	6	13'-6"	
OPERATING FLOOR	104A	2'-0"	2'-0"	ALUM	4	5	6	12'-0"	
OPERATING FLOOR	105A	2'-0"	2'-0"	ALUM	4	5	6	12'-0"	
OPERATING FLOOR	105B	2'-0"	2'-0"	ALUM	4	5	6	12'-0"	

	GLAZING S	CHEDULE ((G)
GLAZING TYPE (G)	DESCRIPTION	RATING	COMMENTS
G1	1" INSULATED GLAZING		T
G2	1/4" FIRE RATED SAFETY GLASS	- 45 MIN	WIRE GLASS W/ SQUARE PATTERN







HEAD


12" SPLIT FACE CONCRETE BLOCK

LINTEL, SEE

DWGS

STRUCTURAL

HOLLOW METAL





- SEE MECHANICAL PROCESS DRAWINGS FOR CHEMICAL CONTAINMENT AREA COATING REQUIREMENTS.
- SEE STRUCTURAL DRAWINGS FOR VERTICAL REINFORCING AND BOND BEAMS IN MASONRY DESIGN.
- SEE SPECIFICATION SECTION 04200 FOR HORIZONTAL JOINT REINFORCING.

ARCHITECTURAL ABBREVIATIONS

ALUM - ALUMINUM

- CB CONCRETE BLOCK
- CO CONCRETE
- ETS EXPOSED TO STRUCTURE
- FRP FIBERGLASS REINFORCED PLASTIC
- FS FLOOR SEALER
- NO NONE

12" SPLIT FACE CONCRETE BLOCK

LINTEL, SEE STRUCTURAL DWGS


SUPPORT ANGLE SEE STRUCTURAL

SHIM AND CAULK

BOTH SIDES (TYP)

DWGS

PT - PAINTED RA - ROLLING ALUMINUM



BLACK & VEATCH

Black & Veatch Corporation

Walnut Creek, California

SOQUEL **CREEK WATER** DISTRICT

HEXAVALENT CHROMIUM REMOVAL PROJECT BONITA WTP & SAN ANDREAS WELL

PRELIMINARY -NOT FOR CONSTRUCTION

	REVISIONS AND RECORD OF ISSUE									
D	ESIGNE	D:	СОН							
D	ETAILED):	TAH							
С	HECKED):	PDR							
Α	PPROVE	D:								
D.	ATE:		JULY 2025							
Ы	ROJECT	NO ·	419795							

ROJECT NO.: 419795


SCHEDULES AND **DETAILS**


1 1/2" = 1'-0"


A-8


OF

CWQ 11-1-140









BLACK & VEATCH

Black & Veatch Corporation Walnut Creek, California



SOQUEL CREEK WATER DISTRICT

HEXAVALENT CHROMIUM REMOVAL PROJECT BONITA WTP & SAN ANDREAS WELL

PRELIMINARY -NOT FOR CONSTRUCTION

	REVI	SIONS	S AND I	RECO	RD OF	ISSUE	
DES	IGNE	D:	СОН				
DET	AILED	:	TAH				
CHE	CKED	:	PDR				
APP	ROVE	D:					
DAT	E:		JULY	2025			
PRO	JECT	NO.:	4197	95			


DETAILS

OF

A-9

1" = 1'-0"

1 1/2" = 1'-0"







SOQUEL CREEK WATER DISTRICT

HEXAVALENT CHROMIUM REMOVAL PROJECT BONITA WTP AND SAN ANDREAS WELL

PRELIMINARY NOT FOR CONSTRUCTION

REVISIONS AND RECORD OF ISSUE DESIGNED: DC DETAILED: BR


CHECKED: RF APPROVED: JW JULY 2025 PROJECT NO.: 419795


TREATMENT BUILDING

PROCESS MECHANICAL


TREATMENT BUILDING SECTIONS


M-2














PLOTTED: 7/3/2025 10:01:14 AM FILE: Autodesk Docs://419795 - SqCWD System Design/419795-XX-Backwash


(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3






(SCALE BAR IS 4" AT FULL SCALE) 0 1/2 1 2 3








OCCUPANCY SENSOR SCHEDULE								
SYMBOL	MTG HGT	DESCRIPTION	MANUFACTURER					
OS	AS NOTED ON PLANS	HIGH BAY, PASSIVE INFRARED, LINE VOLTAGE, CEILING MOUNTED OCCUPANCY SENSOR	WATTSTOPPER #HB350B-L3					



SOQUEL CREEK WATER DISTRICT

HEXAVALENT CHROMIUM REMOVAL PROJECT BONITA WTP AND SAN ANDREAS WELL

PRELIMINARY NOT FOR CONSTRUCTION



DETAILED: RT
CHECKED: RF
APPROVED: JW
DATE: JULY 2025
PROJECT NO.: 419795

ELECTRICAL

LIGHTING FIXTURE AND
PANELBOARD
SCHEDULES AND DETAILS

E-13