

# **Staff Report to the Planning Commission**

Application Number: 28372

**Applicant:** RMC Pacific Materials, LLC **Agenda Date:** February 24, 2021

**Owner:** RMC Pacific Materials, LLC **Agenda Item #:** 7 **APN:** 058-022-09, -10, -14, -16, 058-071-06 **Time:** After 9:30 a.m.

Site Address: 700 Highway 1, Davenport

## **Project Description**

Proposal to implement the final north cement kiln dust (CKD) area closure plan at the former Davenport Cement Plant as required by the Central Coast Regional Water Quality Control Board.

**Location**: Property located on the north side of Highway 1 on the site of the former cement plant adjacent the town of Davenport.

Permits Required: Coastal Development Permit, Riparian Exception, Grading Permit

**Supervisorial District**: 3<sup>rd</sup> District (District Supervisor: Ryan Coonerty)

## **Staff Recommendation**

- Adopt the attached Mitigated Negative Declaration (Exhibit A) per the requirements of the California Environmental Quality Act.
- Approve Application 28372, based on the attached findings (Exhibit C) and conditions (Exhibit D).

## **Exhibits**

- A. Mitigated Negative Declaration and Initial Study also available for viewing at this link: <a href="https://www.sccoplanning.com/PlanningHome/Environmental/CEQAInitialStudiesEIRs/CEQADocumentsOpenforPublicReview.aspx">https://www.sccoplanning.com/PlanningHome/Environmental/CEQAInitialStudiesEIRs/CEQADocumentsOpenforPublicReview.aspx</a>
- B. Project Plans
- C. Findings
- D. Conditions
- E. Mitigation Monitoring and Reporting Program
- F. Comments & Correspondence

## **Project Description & Setting**

The proposed Project is the closure of the North Cement Kiln Dust (CKD) landfill located at the former Davenport Cement Plant at 700 Highway 1, immediately north of the Davenport community and south of New Town in northern unincorporated Santa Cruz County (Exhibit A, Figure 1 and 2). CKD, a byproduct of the cement manufacturing process, was historically placed as fill in what is now called the North CKD Area. In summary, this project would construct an engineered cover and vegetated soil cap with drainage controls to hydrologically isolate the CKD material and prevent surface waters and some groundwater from contacting and interacting with the CKD. This North CKD landfill closure plan follows the similar closure in 1995 of a separate CKD landfill on the site.

Construction of the cement plant began in the late 1800s and included significant modifications to onsite topography, and construction of nearby bridges over steep canyons and a rail spur. Cement production began in 1906 and the facility was the second largest cement plant in the nation. Cement manufacturing at the facility included grinding of source materials, pyro processing, storage of cement products, and storage and disposal of waste products. The facility produced large quantities of CKD as a byproduct of the cement manufacturing process. Although some of the CKD was either reused in the cement process or recycled as an agricultural soil amendment (as lime), most of it was stored or disposed of onsite or on adjacent properties. Starting in the 1950s to approximately 1998 a natural canyon behind the cement manufacturing plant was filled with CKD. The CKD was combined with water and pumped as CKD slurry to a series of temporary basins of various sizes located on top of the existing CKD piles, where the CKD slurry was allowed to dry and solidify, forming cemented layers resistant to percolation and erosion.

In February 2018, the Regional Water Quality Control Board, Central Coast Region (RWQCB) issued Waste Discharge Requirement Order No. R3-2018-0001 (Order) to adopt provisions for closure, post-closure maintenance, and monitoring requirements for the North CKD Area. Together, the Order and the Final North CKD Closure Plan submitted to the RWQCB on April 1, 2018 (Closure Plan) focus on closure of the North CKD Area as a Class II Solid Waste Landfill, as defined by California Code of Regulations Title 27, §20240 and §20250. The primary goal of the Closure Plan is to minimize infiltration of water into the waste, thereby minimizing the production of contaminated leachate and potential groundwater impacts. After closure, a final landfill cover will constitute the principal waste containment feature for the North CKD Area. The Order currently requires the Applicant to complete final closure construction activities for the North CKD Area before October 1, 2022.

According to the Waste Discharge Requirements Order the CKD waste is alkaline, contains non-hazardous levels of heavy metals, and is caustic with a high pH (>9.5) when in aqueous solution. Low permeability and high porosity where fractured, generally describes the physical properties of dried CKD. CKD is commonly considered similar to agricultural lime and sets up similarly to Portland cement when hydrated. Until dried or if in contact with water, it has the potential to alter water quality by increasing alkalinity and may leach dissolved solids including metals and minerals.

The Project closure activities would occur on approximately 23 acres of the Cement Plant property, located within a larger 43.5-acre Project boundary that also includes access roads, portions of the cement facility, and adjacent lands (Exhibit A, Figure 3). The southern portion of the Project area is owned by RMC Pacific Materials, LLC. The northern portion of the Project area is on property that is owned by Trust for Public Land (TPL), a portion of which is currently leased from The Trust for Public Land (TPL). TPL has provided written authorization for CEMEX to file this application. The Assessor Parcel Numbers are shown in Exhibit A, Figure 4.

A detailed description of the project activities is provided in Exhibit A. In summary, the proposed closure activities include grading the current surface of the North CKD Area so it has the required slope for surface water flow and management, installing a new liner to cap CKD material, reapplying a protective soil cover that includes topsoil, and revegetating with native grasses and plant species. The Project also includes remediation of the Retention Pond (by removing accumulated sediment), located south of the North CKD Area, and drainage improvements in and around the North CKD Area to protect water quality in the area (Exhibit A, Figure 3). Best Management Practices (BMPs) including a Storm Water Pollution Prevention Plan (SWPPP) and Dust Mitigation Plan will be implemented to avoid and minimize potential impacts to sensitive biological resources, to protect water and air quality, and to minimize erosion.

A Coastal Development Permit (CDP) is required because the Project includes development activities in the Coastal Zone. The project includes work in and near hydrologic features such as ponds, wetlands and drainage courses that are regulated by the County Riparian Corridor and Wetland Protection ordinance. Because the project activities are necessary for landfill closure, the ordinance provides for the approval of a Riparian Exception to allow the project activities to occur under certain conditions. A grading permit is required and the overall volume of grading (approximately 165,000 cubic yards) triggers a requirement for Planning Commission review of the project. Pursuant to the California Environmental Quality Act (CEQA), the expected environmental impacts of the project are expected to be less than significant and are documented in the attached Initial Study/Mitigated Negative Declaration (Exhibit A).

## **Zoning & General Plan Consistency**

The Project area is located within unincorporated Santa Cruz County, north of the Davenport community, within the Coastal Zone. The area is zoned for Commercial Agriculture (CA) and Heavy Industry (M-2-L), which is consistent with the former cement manufacturing use. The Historic Landmark (L) designation reflects the presence of several historic buildings associated with the plant, but no buildings would be affected by the project. In summary, the Santa Cruz County General Plan land use and zoning plans, policies and regulations encourage the remediation of hazardous materials sites and improvements to water quality.

## **Environmental Review**

The following paragraphs summarize the key environmental issues from the Initial Study and describe how the project plans and technical reports address each issue along with proposed mitigation measures and conditions of approval.

## Water Quality

The Project area includes No-Name Creek, North Pond, seasonal ponds, and a retention pond (Exhibit A, Figure 2). The Project area is also located approximately 0.5 mile south of Agua Puera Creek and approximately 0.5 mile north of San Vicente Creek. The purpose of the Project is to improve the conditions within the Project area to ensure that the CKD is capped and contained to ensure that water bodies and drainages within and adjacent to the Project area are not contaminated by these materials. Though the Project has the potential to generate temporary water quality impacts throughout the implementation of construction activities, the Project has been designed in compliance with the Water Board's Waste Discharge Requirements (Exhibit A, Appendix 7a), which includes an erosion control plan, as required per Santa Cruz County Code (SCCC) 16.22.060. Construction BMPs included within the erosion control plan would minimize impacts to water bodies and drainages within and adjacent to the Project area. Refer to the Detailed Project Description in the Initial Study (Exhibit A, Construction BMPs), the Multi-Season Construction Wet Weather Preparedness Plan (Exhibit A, Appendix 4), and the erosion control plan (Exhibit A, Appendix 8 and Exhibit B, Sheets E1 and E2).

The Waste Discharge Requirements Order also requires the development and implementation of a Stormwater Pollution Prevention Plan (SWPPP), which includes a description of the Project area, erosion and sediment controls, runoff water quality monitoring, means of waste disposal, implementation of approved local plans, control of construction sediment and erosion control measures, maintenance responsibilities, and non-stormwater management controls. The SWPPP will be filed with the Water Board prior to the start of construction and includes monitoring during qualified storm events.

The Project area includes 15 groundwater monitoring wells associated with the North CKD Area to monitor the effectiveness of closure activities at the retention pond and North CKD Area. Wells would be monitored throughout Project construction and after completion to ensure Project activities do not lead to the contamination of groundwater (Exhibit A, Appendices 7a and 7b). The monitoring program also includes wet season monitoring of stormwater and visual observations of drainage systems. Semi-annual reporting of monitoring results to the RWQCB is required. It is anticipated that the removal of the residual coal and CKD sediments and capping of the North CKD Area would substantially remove source materials that may cause groundwater degradation.

Implementation of the Project in accordance with the Closure Plan would result in an overall improvement to runoff and surface water quality, and groundwater quality would be monitored to ensure that water quality continues to improve over time as hazardous materials are further contained within the Project area and water is conveyed away from the CKD.

Although water would be sprayed from a water truck for dust suppression during construction, water spraying would not be excessive as applying too much water could introduce construction challenges to achieve design compaction for fill materials and may create mud that could be tracked out onto public roadways (Exhibit A, Appendix 5, Dust Mitigation Plan). The water used for dust suppression would not be sourced from onsite groundwater. The construction contractor

North CKD Landfill Closure Project Planning Commission Staff Report

would obtain water from existing available sources. Aside from the temporary use of water for dust suppression and short-term (approximately 2 year) irrigation of plants installed at the end of closure activity, water use at the site would not change compared to existing conditions.

The Project Closure Plan was developed in accordance with the Project Hydraulic Analysis (Exhibit A, Appendix 2), Wet Weather Preparedness Plan (Exhibit A, Appendix 4), and Water Board Requirements (Exhibit A, Appendix 7a) that include details that have been included in the Project design and specifications to minimize erosion, sedimentation and water quality impacts. The Hydraulic Analysis also modeled a 24-hour, 1,000-year storm event, for which the Project was designed to convey flows without resulting in flood conditions within or adjacent to the Project area. All proposed improvements to Project area water bodies and drainages would improve both water quality and flooding conditions following project implementation.

## Noise

The temporary impacts of construction noise related to the project are analyzed in the Initial Study (Exhibit A, Section M). Because the noise impacts would be temporary and buffered from the nearest residences by distance and in some areas by intervening topography and vegetation, the noise level would not violate County noise standards (SCCC 13.15 Noise Planning). In accordance with SCCC 13.15, construction activities may occur outside of normal construction hours of 8:00 a.m. and 5:00 p.m. on weekdays with approval in advance from the Building Official. It is anticipated that such a request will be made and staff is supporting approval for grading and construction activities to occur during daylight hours starting at 7:00 a.m. or at sunrise, whichever is earlier, and continue no later than 7:00 p.m., and on Saturdays between 9:00 a.m. and 5:00 and no more than three Saturdays per month. Trucking of import fill material would not occur on Saturdays. There a couple of reasons for staff support of the request to work longer than normal construction hours. Overall, the project would be completed in shorter timeline and any disruption or inconvenience to residents would be shortened. In addition, based on the general prevailing wind conditions in the area that typically increase in the afternoon hours, maximizing work hours in the morning would help to minimize potential dust impacts (see Air Quality discussion below).

## **Biological Resources**

An overview of the habitat types and special status species and potential project-related impacts are described in Exhibit A, Appendix 9, Biotic Assessment Report. Two sensitive habitats, coastal scrub and arroyo willow riparian scrub, occur within the Biological Study Area (Exhibit A, Section D, Figure 6). To the greatest extent feasible, the proposed Closure Plan has been designed to avoid and minimize impacts to biological resources, including sensitive habitats. Closure Plan activities occur primarily within the disturbed habitat of the North CKD landfill area where CKD is mounded, in the adjacent non-native grassland habitat that currently covers portions of the North CKD landfill, and at the Retention Pond, which does not currently provide suitable conditions for most biological resources. The proposed Closure Plan activities would result in temporary and permanent impacts to coastal scrub (Exhibit A, Section D, Table 5a) and arroyo willow riparian scrub (Exhibit A, Section D, Table 5b). The Project's aquatic impacts include impacts to jurisdictional and non-jurisdictional waters. (Exhibit A, Section D, Figure 9).

North CKD Landfill Closure Project Planning Commission Staff Report

Implementation of Mitigation Measure BIO-6 (Construction Related Protective and Replacement Measures for Coastal Scrub Habitat), and Mitigation Measure BIO-7 (Construction Related Protective and Replacement Measures for Arroyo Willow Scrub Habitat) and Mitigation Measure BIO-8 (Implement Protective and Replacement Actions for Jurisdictional Wetlands And Waters of The U.S.) would minimize these impacts to a less than significant level.

The following sensitive wildlife species are present within the Biological Study Area: monarch butterfly, California red-legged frog, Allen's hummingbird, northern harrier, white-tailed kite, birds of prey, other nesting common bird species, and common roosting bat species (Exhibit A, Section D, Figure 7). The following sensitive species have potential to occur within the Biological Study Area: American peregrine falcon, olive-sided flycatcher, grasshopper sparrow, western red bat, and San Francisco dusky-footed woodrat. As further described in detail in Exhibit A, Section D Biologic Resources, the construction activities could impact these species if steps are not taken to avoid and mitigate those impacts. Therefore, Mitigation Measures BIO-1 through BIO-5 will be implemented before and during construction to reduce potential impacts to a less than significant level. In summary, the measures will include monitoring by a qualified biologist, preconstruction surveys, avoidance measures, and habitat enhancements.

The full text of Mitigation Measures BIO-1 through BIO8 can be found in Exhibit A, Appendix 12 and in Exhibit E. In addition, the Project requires authorization by State and Federal permitting agencies due to the potential impacts to habitats and sensitive species protected by State and Federal law. The applicant is currently working with these agencies to develop a Mitigation and Management Plan as the basis for their authorization of Project activities as described in Mitigation Measure BIO-8. Prior to any site disturbance, authorization from the United States Army Corps of Engineers, United States Fish and Wildlife Service, and the California Department of Fish and Wildlife (CDFW) is required.

Implementation of the Closure Plan would result in impacts to riparian vegetation, as discussed in the Initial Study (Exhibit A, Section D). The grading associated with the project would affect the two ponds above and below the CKD landfill and the wetland on the eastern margin of the landfill. General Plan Policy 5.2.3 (Activities Within Riparian Corridors and Wetlands) states: "Development activities, land alterations and vegetation disturbance within riparian corridors and wetlands and required buffers shall be prohibited unless an exception is granted per the Riparian Corridor and Wetlands Protection ordinance. Based on the Riparian Exception Findings in Exhibit B and the mitigation measures described above, staff is recommending approval of a Riparian Exception for the project.

## Air Quality

Construction activities associated with the Project would result in temporary increases in air pollutant emissions. Project construction emissions were estimated using the CalEEMod Model, version 2016.3.2, based on construction information provided by CEMEX in 2019. Based on the modeling results, the Project is not estimated to generate particulate matter ( $PM_{10}$ ) levels in exceedance of the Monterey Bay Air Resources District (MBARD) threshold of 82 lb/day during any phase or simultaneous phase of construction (Exhibit A, Section B).

However, it is well known to the applicant, Planning staff, and the community that dust impacts were associated with past operations of the cement plant and there is a concern regarding potential dust impact associated with mass grading operations for this project. Windy conditions are common on the North Coast particularly seasonally and in the afternoon. During the public comment period on the Initial Study residents expressed concern regarding potential dust impacts from the Project. As part of the Project the applicant prepared a Dust Mitigation Plan in conjunction with MBARD (Exhibit A, Appendix 5). In accordance with the Dust Mitigation Plan, the Project includes restricting vehicle speeds to a maximum of 15 miles per hour on site and watering of exposed areas as needed. These restrictions were assumed in the air quality modeling of construction activities, and an off-highway truck was added to the construction fleet in each phase as a proxy for a water truck.

The Dust Mitigation Plan describes monitoring and best practices to prevent dust that might be transported beyond the plant property perimeter and onto occupied properties in the plant vicinity. The plan consists of two parts: (1) dust prevention measures to eliminate dusting prior to its development; and (2) a real-time monitoring network will be implemented to determine locations and times when off-site dust transport might occur so that dust-generating activities and control measures can be optimized.

BMP that will be implemented during the project are described in Section 5, Table 5-1 of the Dust Mitigation Plan. The BMPs include, but are not limited to, standard practices such as using water trucks and sweeper trucks, load covers for offsite transport, on site speed limit, and truck washing. There will also be a designated on-site person available to respond to community complaints and posting of the contact information in the community. Although not included as a BMP in the Dust Mitigation Plan, alternative working hours are proposed in part to help mitigated potential dust impacts (see discussion in Noise section above). These measures will be continuously applied throughout the project, with locations and intensities of application informed by the monitoring program. Adaptive management is part of the Plan and additional measures may be used, if needed.

The monitoring network is further described in Sections 3 and 4 of the Dust Mitigation Plan and will utilize sensors (light-scattering microsensors) that will be located in source and receptor areas to detect dust emissions. These instruments are internet connected so they can be accessed and provide notifications using smartphones, such that the on-site personnel can be alerted to potential dust events. This information will complement, rather than replace, human detection of visible plumes, as not all off-site transport is detected by human observers. With this real-time information, immediate actions can be taken to remediate specific dust generating events without requiring a complete stoppage of work in most instances. Information obtained from the monitoring network will be shared with the MBARD and Planning Department staff.

Objectives of the measurement network are:

- Obtain data before the project starts to develop a meteorology and PM air quality baseline.
- Provide real-time feedback for managing earth-moving activities and minimize off-site movement of dust.
- Develop an understanding of relationships between activities, meteorology, and off-site transport to re-deploy resources that minimize off-site dust movement.
- Together, the Best Management Practices and monitoring network will concurrently work to prevent dust from being transported outside of the property boundary.

The Dust Mitigation Plan is incorporated as part of the project and is required to be fully implemented as such. Therefore, no additional conditions of approval are proposed except for the requirement to share the information obtained from the monitoring network with Planning Department staff in addition to MBARD. The Dust Mitigation Plan includes designation of a Project Director to oversee the BMPs and monitoring network, direct remedial actions, and stop work, if necessary, until remedial actions have been implemented. The Project Director will also receive any complaints from the community and will have the authority to stop work in response to such complaints. Included in the Dust Mitigation Plan BMPs is posting of signs indicating who to call if a nuisance is perceived. Nevertheless, a condition of approval is included that specifies that the contact information shall be posted at the front gate and provided through other community networks.

## **Transportation**

Implementation of the Project would temporarily result in an increase in construction-related traffic on Highway 1 near the main entrance to the plant and on Warnella Road where construction equipment and personnel would enter the Project area. Two onsite existing access roads, one that extends from the southern portion of the Project area to the North CKD Area and another that extends from Warnella Road north of the Project area to the North CKD Area would be used for construction vehicles and equipment (Exhibit A, Figure 2). The two access roads are located entirely within the Project area and are not open to the public.

Construction equipment and materials would be staged onsite (Exhibit A, Figure 3) for the duration of construction to minimize impacts to traffic that would occur through daily trips to and from the site on Highway 1. However, there would be a temporary increase in trips to and from the Project site when fill is being imported for the cover.

Approximately 47,400 cubic yards of fill would be imported from a quarry, sand plant, and/or soil farm located in north Santa Cruz County or San Mateo County (Exhibit A, Section Q). As described in the Air Quality analysis (Exhibit A, Section C, Table 3), liner/cap installation and fill import is assumed to require 6,321 one-way trips, with an average trip length of 18.4 miles, over 100 working days. Therefore, there could be an additional approximately 60 trips (120 roundtrips) on Highway 1 each day during the approximately 100 days fill could be imported to the site.

Existing traffic conditions along Highway 1 are free-flowing, with most vehicular traffic on this portion of Highway 1 occurring on weekends. Project construction would be primarily Monday-

North CKD Landfill Closure Project Planning Commission Staff Report

Friday. The increased construction-related traffic could slow traffic traveling on Highway 1 as the trucks enter and leave the site, but the overall conditions of free-flowing traffic along Highway 1 is not expected to change substantially.

During the public comment period for the Initial Study, local residents expressed a concern about the increased truck traffic and the use of Cement Plant Road. There is no need for the truck traffic to use Cement Plant Road, and truck route requirements are clarified in a condition of approval. Truck traffic will be limited to two routes to enter and exit the cement plant site. One route is the main entrance to the plant that exits off of Highway 1. The other route would exit off Highway 1 north of New Town to immediately access Warnella Road, if necessary. Trucks would not be allowed to travel on Cement Plant Road between Davenport and New Town.

Transportation and greenhouse gas emissions impacts are evaluated in terms of increased vehicle miles traveled. As noted above, there would be a temporary increase in vehicle miles traveled (VMT) associated with the fill import. Upon completion of the Project Closure Plan, the number of trips to and from the Project area would remain similar to levels consistent with existing conditions.

## **Special Community**

The project site is located in the Davenport Special Community which requires special consideration of visual resources and historic structures associated with the town. The Project area is located in an area that has been designated as the North Coast General Plan Scenic Area in the County General Plan and is considered to be an area that supports a scenic vista. The rolling grassland hills north of Highway 1 support sweeping views of open space and grazing fields that surround the former Cement Plant.

The proposed closure activities would be temporary in nature and would occur primarily within the developed footprint of the Cement Plant, including the North CKD Area, which is closed to the public and largely not visible from Highway 1 or scenic vistas. Following Project implementation, all disturbed lands would be revegetated with native plants and views within and of the Project area would improve compared to existing conditions. The Project would include construction of a permanent relatively impervious shotcrete slope to cover a portion of the CKD slope that could potentially be partially visible from limited sections of Highway 1. This is not considered a significant impact due to the limited visibility of the shotcrete cover and the overall improvement in visual quality that will result from the project. In addition, the large mound of CKD that is located just above the shotcrete cover would be re-graded into the final, gently sloping topography of the North CKD area landfill cover. This would eliminate the views of this CKD material from the Highway.

## **Local Coastal Program Consistency**

The proposed landfill closure is in conformance with the County's certified Local Coastal Program, in that the structure is sited and designed to be visually compatible, in scale with, and integrated with the character of the surrounding lands. The rolling grassland hills north of Highway 1 support sweeping views of open space and grazing fields that surround the former Cement Plant.

Implementation of the project will create gentle slopes and all disturbed lands would be revegetated with native plants, and the Cement Plant would return to conditions similar to existing conditions, and views within and of the project area would improve compared to existing conditions. The project site is not located between the shoreline and the first public road and is not identified as a priority acquisition site in the County's Local Coastal Program. Consequently, the proposed Project will not interfere with public access to the beach, ocean, or other nearby body of water.

## **California Environmental Quality Act**

Environmental review has been required for the proposed project per the California Environmental Quality Act (CEQA). The project was reviewed by the County's Environmental Coordinator and a preliminary determination to issue a Negative Declaration with Mitigations (Exhibit A) was made on November 4, 2020. The mandatory public comment period was extended based on community feedback and expired on January 22, 2021.

As described above, the environmental review process focused on the potential impacts of the Project in the areas of hydrology and water quality, noise, biological resources, and air quality. In addition, cultural resources were addressed through historical and archaeological research and on-site investigation (Exhibit A, Section E). Based on that work, impacts to historical or archaeologic resources are not expected. However, several additional mitigation measures are proposed to include on-site training of personnel in the event ground disturbing activities reveal previously unknown historical or cultural resources and a requirement to stop work if paleontological resources or human remains are discovered during construction. The environmental review process generated mitigation measures that will reduce potential impacts from the proposed development and adequately address these issues. The mitigation measures are contained in Exhibit A, Appendix 12 and Exhibit E.

## **Public Outreach/Public Comment**

During the environmental review public comment period several comments were received from Davenport residents. The comments and correspondence are contained in Exhibit F. The comments from Davenport residents highlight their concerns regarding issues including but not limited to air quality, traffic and noise. These issues are addressed in the staff report in the relevant sections. In addition, during the public comment period, two virtual community meetings were held on December 10, 2020 and January 20, 2021 to present the project to participants, answer questions from community members, and gather community feedback. Planning Department staff and CEMEX representatives participated in the first meeting organized by the Davenport North Coast Association. The second meeting was organized by CEMEX and publicized in the local community by the DNCA and CEMEX. Planning Department staff and CEMEX representatives participated in both meetings and responded to community questions both during the meeting and in follow-up in written form.

North CKD Landfill Closure Project Planning Commission Staff Report

## **Findings**

There are three sets of Findings required for the Development Permit, Coastal Development Permit, and the Riparian Exception. In addition to specific Findings, there are some that are common to all three. In general, the project as conditioned would not be detrimental to the health, safety, or welfare of persons residing or working in the neighborhood or the general public. It would be consistent with the General Plan, Local Coastal Program, and with all County ordinances. The riparian exception is necessary for the proper design and function of the Closure Plan activities proposed for the North CKD landfill and there are no feasible alternatives. Potential impacts to riparian an aquatic resources will be fully mitigated. Please see Exhibit "C" ("Findings") for a complete listing of findings and evidence related to the above discussion.

## Conclusion

As proposed and conditioned, the Project is consistent with all applicable codes and policies of the Zoning Ordinance and General Plan/LCP. Based on the Findings, staff is recommending Planning Commission approve the application as stated on the first page of this report.

Supplementary reports and information referred to in this report are on file and available for viewing at the Santa Cruz County Planning Department and are hereby made a part of the administrative record for the proposed project.

The County Code and General Plan, as well as hearing agendas and additional information are available online at: www.sccoplanning.com

Report Prepared By: David Carlson

Santa Cruz County Planning Department

701 Ocean Street, 4th Floor

Santa Cruz CA 95060 Phone Number: (831) 454-


mail: david.carlson@santacruzcounty.us

Report Reviewed By: Stephanie Hansen

Principal Planner

Sustainability and Special Projects

Santa Cruz County Planning Department



28 **C**5 OF. 2

SHEET

NOTES, LEGEND AND ABBREVIATION						
CEMENT KIFN DNZT (CKD) CFOZNK						
c/oYasha Saber-Compass Land Group						
RMC Pacific Materials, 700 Highway 1,						

SNO SE PLANS 4667-978-916

·www

AD 10	SOURCE.COM	яЯемааА
CIVI CIVI	91086 AW JAVUQ	582-99t
69 ON	STNATJUZNOO	
H.A May	вегописе	
DUFESSI	2MAQA	

740	я Кезописе. Сом
CIVIL OF SALE	91089 AW JAVUO 07
9669 ON 15	STNATJUZNOO
ATTHE A MAY	вегописе
BUŁE ZOLE E ZOLOWY	<b>2MA</b> QA

TOP OF STEEL, TOP OF SHOTCRETE

**TOP OF WALL** 

TOW

TOS

TREAD(S)

CIVIL OF CALIFORNIA CIVIL OF CALIFORNIA CIVIL OF CONTROL OF CONTRO	RCE LTANTS , 98019
2/15573	

**TEMPERATURE, TEMPORARY** 

THICKNESS

THK

THREADED

THRD

**TOP OF FLOOR DRAIN** 

TOP OF FOOTING

SLAB

TOP OF

T/SLAB

TEMP

TOP OF CONCRETE

T/CONC

T/FD

MCA	M.C.A	* 07/08/18/19/19/19/19/19/19/19/19/19/19/19/19/19/
MCA	WCA	TVNO
WAЯП	DEZIGN	k
	· ·	

			Í
			<b>    </b> *
			塩
	MCA	MCA	
	MCA	MCA	- 1-2/2
ł	ИМАЯП	DESIGN	

TOP AND BOTTOM

T&B

**TOP, TENSION** 

WCA WCA MAH 12/12/19 C1 FOR BID AND CONS	
WCA WCA MAH 04/01/18 R3 FINAL REVIE	
SIGN DRAWN REVIEW DATE REV DESCRIPTIO	D

FOR BID AND CONSTRUCTION	ιɔ	61/21/21	HAM	MCA	۸CA
FINAL REVIEW	ΣЯ	81/10/40	HAM	MCA	۸CA
DESCRIPTION	ΒEΛ	DATE	<b>BEVIEW</b>	DRAWN	SIGN

RD ABBREVIATIONS (CONT'D)	STANDAF	STANDARD ABBREVIATIONS (CONT'E
NOT APPLICABLE	SPEC	SPECIFICATION(S)
NEAR FACE	SPL	SPECIAL
NOT IN CONTRACT	SQ	SQUARE
NUMBER	SS	STAINLESS STEEL
NOMINAL	STD	STANDARD
NEAR SIDE	STIFF	STIFFENER
NOT TO SCALE	STIR	STIRRUP
OVERALL	STL	STEEL
ON CENTER	STR'L	STRUCTURAL
OUTSIDE DIAMETER	STRUCT	STRUCTURE
OUTSIDE FACE	SW	SHEAR WALL
OPENING(S)	SYM	SYMMETRICAL

	NEAR FACE  NOT IN CONTRACT  NUMBER  NOMINAL  NOT TO SCALE  OVERALL  ON CENTER  OUTSIDE DIAMETER
	OUISIDE FACE
<b>,</b> D	OPENING(S)
	OPPOSITE

N

EXISTING OR (EXISTING GRADE)

EXIST (EG)

**EACH WAY** 

EQUIP

**EXPANSION** 

EXP

**ABOVE FINISH FLOOR** 

APPROXIMATE(LY)

APPROX

ARCH

**ARCHITECTURAL** 

ARCHITECT

ARCH'T

CENTERLINE AND STATION FOR TOP OF GRADE PROFILE

PROPERTY LINE

20+00

3%

**LEASE LINE** 

DIRECTION OF SURFACE FLOW AND GRADIENT

-2.5%

**∂** PZ-6

GRADE DIRECTION (DOWNSLOPE)

MONITORING WELL LOCATION AND NUMBER

CONTROL POINT LOCATION AND NUMBER

⊕ D-100

**MASTER DRAWING LEGEND:** 

BB BC

BACK TO BACK BOTTOM CORD

BASELINE BUILDING

BLDG

۲

STANDAR

STANDARD ABBREVIATIONS (CONT'D)

STANDARD ABBREVIATIONS

 $\sim$ 

**ANCHOR BOLT** 

**ADDITIONAL** 

ADDL

ADJ

NUMBER	NOMINAL	NEAR SIDE	NOT TO SCALE	OVERALL	ON CENTER	OUTSIDE DIAMETER	OUTSIDE FACE	OPENING(S)	OPPOSITE
ON	MOM	NS	NTS	OA	00	OD	OF	OPNG	OPP



FINISH(ED) OR (FINISHED GRADE)

FIN (FG)

FRENCH DRAIN

**FABRICATION** 

FAB

FD


EXTERIOR


**FOUNDATION** 

FDN

FINISH FLOOR







HIGH-DENSITY POLYETHYLENE

HORIZONTAL

HORIZ

Η

HS

HDPE

В

HIGH POINT

**GRADE BEAM** 

GALVANIZED

GALV

ВA

**BEST MANAGEMENT PRACTICE** 

BMP

BEAM

BM

**BASE PLATE** 

BOTTOM

BOT

30-INCH CMP PIPELINE (BURIED, APPROXIMATE LOCATION)

 $\times$ 

LIMIT OF CKD PILE (APPROXIMATE)

UTILITY LINES (BURIED)

OVERHEAD POWER LINE AND POWER POLE

UNDERGROUND WATER LINE

≱

 $\Box$ 

**NEW DRAINAGE DITCHES** 

BEARING

BRACKET

BRKT

BS

BRG

GAGE OR GAUGE

FEET/FOOT/

**FAR SIDE** 


INVERT ELEVATION

HEADED STUD

INSIDE DIAMETER

 $\Box$ 

INCHES/INCH/"




PREFAB

PLUMB

PRELIM

PRMLD



POLYVINYL CHLORIDE

**PROJECTION** 

PROJ

POINT

RIGHT, RISER

PAVEMENT

PVMT

PVC

DEVELOPMENT LENGTH

KNOCKOUT

JOINT

KIPS

**CONSTRUCTION JOINT** 

CENTERLINE

CAST-IN-PLACE

CIP

 $\Box$ 

CB

CATCH BASIN

COMPRESSION

**BOTH WAYS** 

**BOTH SIDES** 

**BASEMENT** 

**BSMT** 

BEVELED

BVL

BW

JOIST

POUND

LB,#

CONCRETE MASONRY UNIT

CMU

CLR

PROPOSED MAJOR ELEVATION CONTOUR IN FEET

270

 $\bigcirc$ 

**EXISTING MINOR ELEVATION CONTOUR IN FEET** 

**EXISTING MAJOR ELEVATION CONTOUR IN FEET** 

**EXISTING DRAINAGE DITCHES** 

TEMPORARY FIBER ROLL

PROPOSED MINOR ELEVATION CONTOUR IN FEET

**EXISTING BOREHOLE LOCATION AND NUMBER** 

● BH 8

PROPOSED CKD WORK AREA LIMITS (CEMEX)

PROPOSED CKD WORK AREA LIMITS (CDLC)

PROPOSED LIMITS OF CKD GRADING LIMITS

COL

**CLEAR OR CLEARANCE** 

8

LINEAL FEET

王

**ROOF DRAIN** 

REINF

RADIUS

RAD

B RE:

LINEAR LOW-DENSITY POLYETHYLENE

LLDPE

CONSTRUCTION

CONST

CONN CONC

CONNECTION

CONCRETE

COLUMN

LONG LEG HORIZONTAL


H


UNLESS NOTED OTHERWISE


VERTICAL


STRUCTURAL TUBING


**TRANSVERSE** 














Davenport,

RUSTICATION JOINT ROUGH OPENING RETAINING WALL ROUND SOUTH

SHEAR CONNECTORS R≷ 8 SC

STORM DRAIN SCHEDULE(D) SCH SD

SECT

SHOTCRETE

SHOT

SAW JOINT SLOPE

STRUCTURAL TEE CUT FROM A MISCELLANEOUS STEEL SECTION

MISCELLANEOUS

MISC

MS

**EXPANSION JOINT** 

**EACH FACE** 

EACH

EA

**EAST** 

ELECTRICAL

ELEVATION

ELEV,EL

ELEC

EQUAL

MINIMUM

 $\frac{Z}{Z}$ 

MIDDLE

 $\frac{1}{2}$ 

Ξ

MIDDLE STRIP

MANUFACTURE(R)

MAN-HOLE

MEZZANINE

MEZZ

DAMP PROOFING

**DEAD LOAD** 

DIST

DOWN

N

Ъ

DRAWING(S)

DWG

SHOWN

DOWEL

DWL

MFR

RND

MECHANICAL, ELECTRICAL, PLUMBING

MECHANICAL

MECH

MEP

MAX

REV RH

REQD

REM

LIGHTWEIGHT CONCRETE MAXIMUM **LONG WAY** MATERIAL

LONG LEG VERTICAL LONGITUDINAL LOW POINT **LONG** LWC  $\geq$ 

MATL

DISTRIBUTION DIMENSION DIAMETER DIAGONAL DETAIL

DEGREES

CONTINUED DEPTH CONT'D DIAG DETL DEG

CONTINUOUS CONT MΩ

REVISION CLOUD

SECTION/PROFILE IDENTIFICATION

SHEET WHERE SECTION/PROFILE IS

SHEET WHERE SECTION/PROFILE IS FIRST REFERENCED  $\infty$ <u>س</u> کا

 $\square$ 

**DETAIL NUMBER** 

SHEET WHERE DETAIL IS FIRST REFERENCED SHEET WHERE DETAIL IS SHOWN 6  $\overline{\phantom{a}}$ **ω** ′

WE COMPLETED THIS WORK IN GENERAL ACCORDANCE WITH OUR CONTRACT. THIS DESIGN AND THESE DRAWINGS ARE FOR THE EXCLUSIVE USE OF RMC PACIFIC MATERIALS FOR SPECIFIC APPLICATION TO THE SUBJECT PROJECT AND SITE. USE OF THIS DESIGN BY ANYONE EXCEPT FOR WHOM IT WAS PREPARED IS PROHIBITED WITHOUT WRITTEN CONSENT FROM ADAMS RESOURCE CONSULTANTS COMPANY, THE DESIGN ENGINEER—OF—RECORD. THIS DESIGN P USE

 $\triangleleft$ 

RUCTION; **CONTRACTOR MUST CALL FOR UTILITY LOCATES PRIOR TO CONST** (Phone 811). REPLACEMENT OF S A RESULT OF

THE CONTRACTOR IS SOLELY RESPONSIBLE FOR REPAIRS AND/OR REI EXISTING UTILITIES AND FACILITIES SHOULD DAMAGE OCCUR AS A CONSTRUCTION ACTIVITIES.

NOTES GENERAL THE GENERAL CONTRACTOR IS DEFINED, FOR THE PURPOSES OF THIS DESIGN, AS THE PROJECT CONTRACTOR UNLESS OTHERWISE NOTED. THE CONTRACTOR IS RESPONSIBLE FOR THE PROJECT SITE CONSTRUCTION PROCESS AND SAFETY OF THE WORKERS, THAT INCLUDES, BUT IS NOT LIMITED TO, THE CONSTRUCTION SEQUENCE, TEMPORARY BARRIERS, EXCAVATION ACCESS, AND TRAFFIC.

APPROVAL SUBJECT TO  $\overline{S}$ ( ON LEASED PROPERTY OR IN SENSITIVE HABITAT AREAS APPROPRIATE AGENCY AND LAND OWNER. WORK THE A


CONTRACTOR MUST FIELD VERIFY ALL EXISTING DIMENSIONS AND EXISTING UNDERGROUND OBSTRUCTIONS AND UTILITIES: THE SITE


CONDITIONS.


THE OF


THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS OF ALL EXISTING UTILITIES SHOWN ON THE PLANS AND THOSE UTILITIES INCLUDING, BUT NOT LIMITED TO, OVERHEAD OR UNDERGROUND OBSTRUCTIONS.


CONTRACTOR IS RESPONSIBLE FOR INTERIM TEMPORARY CUTS OVER 4 FEET H AND FOR THE REMOVAL OF ALL ABANDONED UTILITIES, OR CHANGES TO HER EXISTING OBSTRUCTIONS THAT INTERFERE WITH THE NEW CONSTRUCTION. THE HIGH OTH











SHEET

8 OF 28 DR8


TOULION: SHOP DITCH, SOUTH DITCH #2


CEMENT KILN DUST (CKD) CLOSURE PLANS

c/oYasha Saber-Compass Land Group 916-825-4997 Pacific Materials, 700 Highway 1, Davenport,










 $\Box$ 

 $\triangleleft$ 

 $\bigcirc$ 


SEASONAL PONDS HABITAT ENHANCEMENT
CEMENT KILN DUST (CKD) CLOSURE PLANS
C/oYasha Saber-Compass Land Group 916-825-4997 WWW.ADAMSRESOURCE.COM SEASONAL PONDS HABITAT ENHANCEMENT 1682-997-927 SHEET 9 OF 28 DR9 91089 AW JAYUO 0771x08.0.9 **STNATJU2ND** 61/21/21 FOR BID AND CONSTRUCTION MCA  $\mathsf{MC} \forall$ RESOURCE RMC Pacific Materials, 700 Highway 1, Davenport, MCA MC∀ FINAL REVIEW HAM**SMAGA** NWAЯП DEZICN DESCRIPTION DATE **BEVIEW** 



 $\square$ 

 $\triangleleft$ 


 $\bigcirc$ 



 $\bigcap$ 

 $\triangleleft$ 

 $\bigcirc$ 



 $\Omega$ 

 $\bigcirc$ 

12 OF 28

SHEET

**G2** 

EINAL I INER FOLINGA (CKD) CLOSURE PLANS


c/oYasha Saber-Compass Land Group 916-825-4997


c/oYasha Saber-Compass Land Group 916-825-4997 HTROU GRADE NORTH

моэ.ээяпоеэЯемаоА.www 1682-997-927 61086 AW JJAVUO O∇∇1x08.0.9 **STNATJU2NDD** RESOURCE **SMAGA** 









28

PS1


EAST, WEST AND SOUTH PERIMETER DITCHES


CEMENT KILN DUST (CKD) CLOSURE PLANS

CAPAGE P SHEET RMC Pacific Materials, 700 Highway 1, Davenport, CA

моэ.ээяпоеэЯемааА.www l 68Z-99t-SZt 61089 AW JJAVUO OTT1X08.0.9 **STNATJU2N0** RESOURCE **SMAGA** 









SHEET 16 OF 28 PS3


CEMENT KILN DUST (CKD) CLOSURE DIANCE CAMPASS Land Group 916-825-4997





















 $\bigcirc$ 


 $\Box$ 


 $\triangleleft$ 











## GENERAL NOTES AND ABBREVIATIONS

CEMENT KILN DUST (CKD) CLOSURE PLANS c/olasha Saber-Compass Land Grouip 916-825-4997

RMC Pacific Materials, 700 Highway 1, Davenport, CA

SPACE SPECIFICATION(S) SPECIAL SQUARE STAINLESS STEEL

DRILLED NAIL LENGTH POUND DEVELOPMENT LENGTH LANDING LEFT HAND LIVE LOAD

NSIDE DIAMETER NTERIOR JOINT

# aA.wwv tz-szt X08.0.9

ROJECTION DUNDS PER SQUARE FEET DUNDS PER SQUARE INCH

OLYVINYL CHLORIDE

			OF CALPY	оьмя Кезопесе. Сом
			CIVIL CE9953 Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z	STNATJUZNOO 6 1 0 8 9 AW JAYUO 077 1 X 1 4 4 8 - 8 4
	MCA	MC∀	137/09//	и кегописе
	MCA	MCA	PROPESSION	2MAGA
1	ИМАЯП	DEZICN	* * * * * * * * * * * * * * * * * * * *	

ABBREVIATIONS (CONT.)

S	
M	

61/61/20

81/10/40 DATE

FOR BID AND CONSTRUCTION

# 700 HIGHWAY 1, DAVENPORT, CA 95017

CONTRACTOR MUST CALL FOR UTILITY LOCATES PRIOR TO CONSTRUCTION;

LELY RESPONSIBLE FOR REPAIRS AND/OR REPLACEMENT OF DAMAGE OCCUR AS A RESULT OF CONSTRUCTION ACTIVITIES.	
THE CONTRACTOR IS SOI EXISTING UTILITIES SHOULI	
	THE CONTRACTOR IS SOLELY RESPONSIBLE FOR REPAIRS AND/OR REPLACEMENT OF EXISTING UTILITIES SHOULD DAMAGE OCCUR AS A RESULT OF CONSTRUCTION ACTIVITIES.

		THE CONTRACTOR IS SOLELY RESPONSIBLE FOR REPAIRS AND/OR REPLACEMENT OF EXISTING UTILITIES SHOULD DAMAGE OCCUR AS A RESULT OF CONSTRUCTION ACTIVITI	R REPAIRS AND/OR REPLACEMENT OF A RESULT OF CONSTRUCTION ACTIVITIES.	
GENERAL NOTES General:	GENERAL NOTES, (CONT.)	ONT.)	GENERAL NOTES (CONT.)	
THE CONTRACTOR IS DEFINED, FOR THE PURPOSES OF THIS NAIL DESIGN, AS THE	REINFORCING STEEL:		NAIL BAR STEEL:	
NOTED AND IS SOLEY RESPONSIBLE FOR THE PROJECT SITE CONSTRUCTION PROCESSS AN SAFETY OF THE WORKERS THAT MAY INCLUDE BUT IS NOT LIMITED TO, THE CONSTRUCTION SEQUENCE, TEMPORARY HANDRAILS, EXCAVATION ACCESS, AND BARRIERS. IT SHOT INCLIDES I IFTING OF MATERIALS AND CONSTRUCTION		ALL REINFORCING STEEL SHALL CONFORM TO ASTM A615 / AASHTO M31, GRADE 60 FOR DEFORMED BARS, AND ASTM A185 / AASHTO M55 FOR WELDED WIRE FABRIC (WWF).	ALL NAIL BARS SHALL CONFORM GRADE 60, GRADE 75 OR ASTM AON THE PLANS.	ALL NAIL BARS SHALL CONFORM TO EITHER ASTM A615 / AASHTO M31, GRADE 60, GRADE 75 OR ASTM A722 / AASHTO M275, GRADE 150, AS INDIC/ ON THE PLANS.
EQUIPMENT ON, INTO AND OUT OF THE EXCAVATION MAREA, TEMPORARY BRACING, SINGLE—SIDED FORMWORK, TEMPORARY EXCAVATIONS, AND STABILITY OF ALL TEMPORARY CIT SLOPES, MINIMIN SLOPE PROTECTION SHALL BE PROVIDED BY THE	SUBMIT REINFORCING STEEL SHOP DRAWI ACCORDANCE WITH THE SPECIFICATIONS.	SUBMIT REINFORCING STEEL SHOP DRAWINGS TO DESIGN ENGINEER IN ACCORDANCE WITH THE SPECIFICATIONS.	ALL SHRINKAGE CRACKS, DEFICIENCES OI SHALL BE CORRECTED AND FILLED OR SI DESIGNED AND THE SPECIAL INSPECTOR	ALL SHRINKAGE CRACKS, DEFICIENCES OR OPENINGS IN THE SHOTCRETE WALL SHALL BE CORRECTED AND FILLED OR SEALED TO THE SATISFACTION OF THE DESIGNED AND THE SECOND INSECTOD
CONTRACTOR AND CONSIST OF PROVIDING ADEQUATE COVERING OVER ALL EXPOSED SLOPES. ADEQUATE COVERING SHALL CONSIST OF A FLASHCOAT OF SHOTCRETE,	ALL REINFORCING STEEL DETAIL ADOPTED ACI 318/318R MANU	ALL REINFORCING STEEL DETAILS IN ACCORDANCE WITH THE MOST RECENTLY ADOPTED ACI 318/318R MANUAL OF STANDARD PRACTICE.	DESIGNER AND THE STECTAL INST	
APPROVED BY THE DESIGN ENGINEER, ADAMS RESOURCE CONSULTANTS (ARC).	ALL REINFORCING BAR LAPS SH	ALL REINFORCING BAR LAPS SHALL BE CLASS B, IN ACCORDANCE	UEFINITIONS	
THE SOIL NAILED WALL IS A SYSTEM DESIGNED TO SUPPORT THE NEARLY VERTICAL EXCAVATION ONCE THE COMPONENTS OF THE NAILS, VERTICAL MEMBERS AND FACING SYSTEM AND COMPILERS INSTALLED FOR ALL FYCANATION LITTER	WITH THE 2006 INTERNATIONAL FOLLOWING TABLE:	L BUILDING CODE OR AS SUMMARIZED IN THE	"DESIGN ENGINEER" OR "DESIGNER" = Adams Resource of DESIGN ENGINEER OF THESE PLANS. MAY ALSO BE THE	"DESIGN ENGINEER" OR "DESIGNER" = Adams Resource Consultants (ARC), TH DESIGN ENGINEER OF THESE PLANS.  MAY ALSO BE THE GEOTECHNICAL SPECIA
MEMBERS, AND FACING STSIEM ARE COMPLETELY INSTALLED FOR ALL EXCAVATION LIFTS  UP TO AND INCLUDING THE CURRENT EXCAVATION LIFT. THE STABILITY  OF INTERIM TEMPORARY VERTICAL CUTS OVER 4 FEET HIGH THAT EXIST PRIOR  TO INSTALLATION OF NAILS AND THE SHOTCRETE WALL FACING IS THE  RESPONSIBILITY OF THE CONTRACTOR.	CLASS B LAP LAP SPLICE BAR LENGTH MEASURED SIZE IN DIAMETERS (IN.)	CLASS B LAP LAP SPLICE LENGTH MEASURED IN LENGTH (IN.)	INSPECTOR FOR THIS PROJECT. "THE ENGINEER" = GEOTECHNICAL OWNER AND APPROVED BY THE G "CONTRACTOR" = SPECIALTY SHO" "NFAT CUT" = THF FXCAVATION	INSPECTOR FOR THIS PROJECT. "THE ENGINEER" = GEOTECHNICAL SPECIAL INSPECTOR AS APPOINTED BY THE OWNER AND APPROVED BY THE GOVERNING MUNICIPALITY OR AGENCY. "CONTRACTOR" = SPECIALTY SHOTCRETE (SHORING) WALL CONTRACTOR "NFAT CLIT" = THF FXCAVATION FXPOSFD CLIT FACF PREPARFD FOR APPLICATION.

FOLLO	FOLLOWING TABLE:		
BAR	CLASS B LAP LAP SPLICE LENGTH MEASURED	CLASS B LAP LAP SPLICE LENGTH MEASURED	
SIZE	IN DIAMETERS (IN.)	IN LENGTH (IN.)	
#4	40 ¢	20	
#2	40 ¢	25	
9#	40¢	30	
<b>/#</b>	20 Φ	44	
#8	50 ↔	50	
ALL W	ALL WELDED WIRE FABRIC SPLICES SHALL BE A MINIMUM OF 6 INCHES LOP LAP AT LEAST TWO LONGITUDINAL OR TRANSVERSE WIRES. SEE PLANS FOR	LICES SHALL BE A MININAL OR TRANSVERSE	ALL WELDED WIRE FABRIC SPLICES SHALL BE A MINIMUM OF 6 INCHES LONG AND LAP AT LEAST TWO LONGITUDINAL OR TRANSVERSE WIRES. SEE PLANS FOR SPECIAL PRESENCE OF A PROPERTY AND CHARLOW OF A MACCORDANICE OF TRANSVERSE OF STANDARD OF STEAM AND CONDENSES.
-	1	1	

THE CONTRACTOR SHALL PROVIDE PROTECTION FOR SAFE PASSAGE OF PEDESTRIANS WORKERWS AND VEHICULAR TRAFFIC. LOOSE SOIL OF CUTS MAY RAVEL.

 $\bigcirc$ 

SPECIAL INSPECTION AND TESTING

IN ACCORDANCE WITH THE RWQBC AND LATEST IBC, SPECIAL INSPECTION SHALL BE PROVIDED BY THE OWNER'S REPRESENTATIVE AND CQA OFFICER FOR DESIGN EXECUTION TO COVER OBSERVATION OF THE FOLLOWING TYPES OF CONSTRUCTION WHEN APPLICABLE:

INSTALLATION OF STEEL PLATES, NUTS AND MEMBERS AND LEAN MIX PLACEMENT IF REQUIRED

SOIL NAIL INSTALLATION AND TESTING

33

ALL SHOTCRETE, SOIL NAIL GROUT AND SOIL NAIL DESIGN ADHESIONS TESTED IN ACCORDANCE WITH THE SPECIFICATIONS.

DESIGN LIVE LOADS:

SHOTCRETE WORK (SHOTCRETE AND REBAR PLACEMENT)

						ALL WELDED WIRE FABRIC SPLICES SHALL BE A MINIMUM OF 6 INCHES LONG AND LAP AT LEAST TWO LONGITUDINAL OR TRANSVERSE WIRES. SEE PLANS FOR SPECIFIC DETAILS. IF APPLICABLE, SUBMIT ALL SHOP DRAWINGS IN ACCORDANCE WITH THE SPECIFICATIONS.  SEE THE WALL PLANS SPECIFIC DETAILS AS THEY PERTAIN TO CONNECTION OF THE REINFORCED SHOTCRETE WALL AND ANY OTHER FACING. SUBMIT ALL SHOP DRAWINGS IN ACCORDANCE WITH THE SPECIFICATIONS.	
LAP SPLICE LENGTH MEASURED IN LENGTH (IN.)	20	25	30	44	50	ALL WELDED WIRE FABRIC SPLICES SHALL BE A MINIMUM OF 6 INCHES LOP LAP AT LEAST TWO LONGITUDINAL OR TRANSVERSE WIRES. SEE PLANS FOR SPECIFIC DETAILS. IF APPLICABLE, SUBMIT ALL SHOP DRAWINGS IN ACCORD WITH THE SPECIFICATIONS.  SEE THE WALL PLANS SPECIFIC DETAILS AS THEY PERTAIN TO CONNECTION THE REINFORCED SHOTCRETE WALL AND ANY OTHER FACING. SUBMIT ALL SDRAWINGS IN ACCORDANCE WITH THE SPECIFICATIONS.	
LAF SPLICE LENGTH MEASURED IN DIAMETERS (IN.)	40 <del>0</del>	40¢	40 ¢	20 ф	50 ♦	ALL WELDED WIRE FABRIC SPILAP AT LEAST TWO LONGITUDI SPECIFIC DETAILS. IF APPLICA WITH THE SPECIFICATIONS.  SEE THE WALL PLANS SPECIFICATIONS THE REINFORCED SHOTCRETE THE REINFORCED SHOTCRETE TO SHOTCRETE TO SHOTCRES TO SH	
BAR SIZE	4	#2	9#	<b>2#</b>	#8	ALL WE LAP AT SPECIFI WITH T SEE TH THE REDRANNIN	

CONCRETE	AFTER 28 DAYS, ALL CONCRETE SHALL OBTAIN A MINIMUM ULTIMATE COMPRESSIVE STRENGTH (f'c), AS MEASURED BY THE PROCEDURES IN ASTM C109/AASHTO T106, WHERE THE STRENGTH f'c SHALL ATTAIN 4000 PSI.	TEMPORARY CUT SLOPES	THE SOIL NAILED WALL DESIGN BY ARC DOES NOT INCLUDE SPECIFICATIONS OR DESIGN OF TEMPORARY OPEN CUT SLOPES UNLESS SPECIFICALLY PROVIDED ON THE DRAWINGS. ADDITIONAL DESIGN AND SPECIFICATIONS OR PERFORMANCE CRITERIA AS MAY BE REQUESTED FOR EXCAVATIONS NOT SHOWN ON THESE DRAWINGS ARE THE RESPONSIBILITY OF THE CONTRACTOR UNLESS AGREED TO
----------	---	----------------------	--

IRAFFIC/CONSIRUCTION SURCHARGE = 123 MSF. SURCHARGE LOADS SHALL	וראו טואוי סטן סרט בט
NOT BE CLOSER THAN 5 FEET (HORIZ.) FROM TOP OF SOIL NAILED WALLS OR 3 FEET (HORIZ.) FROM THE TOP OF CUT SLOPES, WHICHEVER IS GREATER. THE CONTRACTOR IS RESPONSIBLE AND SHALL VERIFY THAT THE CONSTRUCTION SURCHARGE OR CLEARANCE IS NOT EXCEEDED WITHOUT THE DESIGNER'S APPROVAL. SEE ELEVATIONS, PLANS AND SECTIONS FOR ADDITIONAL LIVE LOADS THAT MAY HAVE BEEN CONSIDERED IN DESIGN.	THE SOIL NAILED WALL DESIGN BY ARC DOES NOT INCLUD DESIGN OF TEMPORARY OPEN CUT SLOPES UNLESS SPECIFICATIONS OTHE DRAWINGS. ADDITIONAL DESIGN AND SPECIFICATIONS OF CRITERIA AS MAY BE REQUESTED FOR EXCAVATIONS NOT SURAWINGS ARE THE RESPONSIBILITY OF THE CONTRACTOR OTHERWISE IN WRITING BY ARC.
SUBSURFACE DESIGN:	CONSTRUCTION SEQUENCE
ALL SUBSURFACE SOIL AND WATER PARAMETERS USED IN THE DESIGN WERE BASED ON EXPERIENCE AND THE SUBSURFACE CHARACTERIZATION PRESENTED IN THE REPORT TITLED "FINAL DESIGN REPORT, NORTH CKD CLOSURE PLANS, CEMEX DAVENPORT PLANT, DAVENPORT, CALIFORNIA, BY ADAMS RESOURCE CONSULTANTS COMPANY, Dated APRIL 1, 2018, for CEMEX.	ARC HAS ASSUMED THE FOLLOWING FOR THIS DESIGN; 1) CONTRACTOR SHALL REMOVE ORGANICS, DELETERIOUS M FROM AREAS REQUIRING GRADING TO CREATE THE "NEAT L SHOTCRETE APPLICATION BEFORE STARTING DRILLING.

TRAFFIC/CONSTRUCTION SURCHARGE = 125 PSF. SURCHARGE LOADS SHALL NOT BE CLOSER THAN 5 FEET (HORIZ.) FROM TOP OF SOIL NAILED WALLS OR 3 FEET (HORIZ.) FROM THE TOP OF CUT SLOPES, WHICHEVER IS GREATER. THE CONTRACTOR IS RESPONSIBLE AND SHALL VERIFY THAT THE CONSTRUCTION SURCHARGE OR CLEARANCE IS NOT EXCEEDED WITHOUT THE DESIGNER'S APPROVAL. SEE ELEVATIONS, PLANS AND SECTIONS FOR ADDITIONAL LIVE LOADS THAT MAY HAVE BEEN CONSIDERED IN DESIGN.

 $\bigcap$ 

CHARACTERIZATION PRESENTED IN 10RTH CKD CLOSURE PLANS, CEMEX 3Y ADAMS RESOURCE CONSULTANTS	1) CONTRACTOR SHALL REMOVE ORGANICS, DELETERIOUS MATERIALS AND SOIL FROM AREAS REQUIRING GRADING TO CREATE THE "NEAT LINE" SURFACE FOR SHOTCRETE APPLICATION BEFORE STARTING DRILLING.
ULTIMATE U COHESION PULLOUT RESISTANCE (PSF) (K/FT)	2) DRILLING, INSTALLATION AND WALL CONSTRUCTION SHALL DONE BY EITHER A "TOP—DOWN" FASHION SUCH THAT THE TOP ROWS OF NAILS WILL BE COMPLETED FIRST OR IN A VERTICAL COLUMN FASHION SUBJECT TO APPROVAL BY ARC. IF MEANS AND METHODS REQUIRE INSTALLATION BY REACHING OVER OR ABOVE THE
50 9.5	EDGE OF A SLOPE THE CONSTRUCTION AND INSTALLATION EQUIPMENT WILL REMAIN AS FAR AWAY FROM THE STEEP SLOPE TOP OR TOE EDGE AS POSSIBLE.
THE CONTRACTOR DURING VERIFICATION TESTING MAY NEED TO MODIFY MEANS, METHODS AND/OR ADD	USE OF THIS DESIGN
ALLOWABLE PULLOUT RESISTANCE) IS CALCULATED AS QUAL TO 2.0.	ARC PREPARED THIS WORK IN GENERAL ACCORDANCE WITH OUR CONTRACT. THIS DESIGN AND THESE DRAWINGS ARE FOR THE EXCLUSIVE USE OF CEMEX FOR
MED TO EXIST BELOW THE BOTTOM	SPECIFIC APPLICATION TO THE SUBJECT PROJECT AND SITE. USE OF THIS DESIGN BY ANYONE EXCEPT FOR THOSE WHOM IT WAS PREPARED IS PROHIBITED WITHOUT
TERM" STABILITY. LOCAL AREAS OF	WRITTEN CONSENT FROM ARC COMPANY, THE WALL DESIGN ENGINEER.

MOIST UNIT WEIGHT FRICTION (PCF) (DEG)

115

CEMENT KILN DUST

BACK TO BACK
BOTTOM CORD
BASE LINE
BUILDING
BEAM
BOTTOM
BASE PLATE
BEARING
BRACKET
BOTH SIDES
BASEMENT
BEVELED
BOTH WAYS

COMPRESSION
CAST—IN—PLACE
CONSTRUCTION JOINT
CENTERLINE
CLEAR OR CLEARANCE
CONCRETE MASONRY UNIT
COLUMN
CONCRETE
CONNECTION
CONSTRUCTION
CONSTRUCTION
CONSTRUCTION
CONSTRUCTION
CONSTRUCTION
CONTINUED

ANCHOR BOLT
ADDITIONAL
ADJACENT
ABOVE FINISH FLOOR
APPROXIMATE(LY)
ARCHITECTURAL

AB ADDL ADJ AFF APPROX ARCH ARCH'T

NOTES: 1) ULTIMATE PULLOUT RESISTANCE SHALL BE CONFIRMED BY THE CONTRACTOR DURING VERIFICATION TESTING PRIOR TO STARTING SOIL NAIL WALL CONSTRUCTION. CONTRACTOR MAY NEED TO MODIFY MEANS, METHODS AND/OR ADD	USE OF THIS DESIGN
NAILS DEPENDING ON THE TEST RESULTS. 2) DESIGN ADHESION (ALLOWABLE PULLOUT RESISTANCE) IS CALCULATED AS ULTIMATE PULLOUT RESISTANCE DIVIDED BY A FACTOR OF SAFETY EQUAL TO 2.0.	ARC PREPARED THIS WORK IN GENERAL ACCO
THE REGIONAL GROUNDWATER LEVEL IS ASSUMED TO EXIST BELOW THE BOTTOM	SPECIFIC APPLICATION TO THE SUBJECT PROJI BY ANYONE EXCEPT FOR THOSE WHOM IT WAY
OF THE NAIL WALLS IN CONSIDERING "LONG—TERM" STABILITY. LOCAL AREAS OF PERCHED SEEPAGE MAY BE ENCOUNTERED IN SOME LOCATIONS AND WILL BE	WRITTEN CONSENT FROM ARC COMPANY, THE
MANAGED BY DRAIN FABRIC PLACED ON THE SOIL CUT FACE (NEAT CUT) AND COVERED BY THE STEEL REINFORCED SHOTCRETE FACING.	SHOTCRETE:
	ALL SHOTCRETE SHALL HAVE A MINIMUM 28-1
EXISTING UNDERGROUND OBSTRUCTIONS AND UTILITIES:	OF 2000 PSI.
THE CONTRACTOR MUST FIELD VERIFY ALL EXISTING DIMENSIONS AND SITE CONDITIONS.	SEE THE SPECIFICATIONS FOR REQUIREMENTS.


CONTINUE DI IIIL DIELE NEINI ONCED DIDIONEIE I ACINO.	
	ALL SHOTCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE
EXISTING UNDERGROUND OBSTRUCTIONS AND UTILITIES:	STRENGTH OF 4000 FST, AND A MINIMOM S-DAT COMPRESSIVE STRENGTH OF 2000 PST.
THE CONTRACTOR MUST FIELD VERIFY ALL EXISTING DIMENSIONS AND SITE CONDITIONS.	SEE THE SPECIFICATIONS FOR REQUIREMENTS.
THE CONTRACTOR SHALL FIELD VERIFY AND BE RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS OF ALL EXISTING UTILITIES SHOWN ON THE PLANS AND THOSE	TYPE V PORTLAND CEMENT CONFORMING TO ASTM C150 / AASHTO M85 SHALL BE USED FOR SHOTCRETE.
	SUBMIT MIX DESIGNS IN ACCORDANCE WITH THE SPECIFICATIONS.
THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVAL OF ALL ABANDONED	

THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVAL OF ALL UTILITIES, OR CHANGES TO OTHER EXISTING OBSTRUCTIONS THAT WITH OR ARE ADJACENT TO THE NEW CONSTRUCTION.

 $\triangleleft$ 

		`								
INFORCING	STEEL:			NAIL BAR STEEL:					L	
L REINFORC ADE 60 FO ELDED WIRE	SING STEEL SHAL OR DEFORMED BA FABRIC (WWF).	NFORCING STEEL SHALL CONFORM TO ASTM , 60 FOR DEFORMED BARS, AND ASTM A185 / WIRE FABRIC (WWF).	A615 / AASHTO M31, / AASHTO M55 FOR	ALL NAIL BARS SHALL GRADE 60, GRADE 75 ON THE PLANS.	SHALL CONFORM TO EITHER ASTM A615 IE 75 OR ASTM A722 / AASHTO M275,	ITHER ASTN / AASHTO	A615 / AASHTO M31, M275, GRADE 150, AS	131, AS INDICATED	E E E E E E E E E E E E E E E E E E E	
IBMIT REINF	ORCING STEEL S WITH THE SPECI	BMIT REINFORCING STEEL SHOP DRAWINGS TO DES CORDANCE WITH THE SPECIFICATIONS.	DESIGN ENGINEER IN	ALL SHRINKAGE SHALL BE CORRE	KAGE CRACKS, DEFICIENCES O CORRECTED AND FILLED OR S	OR OPENINGS IN SEALED TO THE	IGS IN THE SHOTCRETE ) THE SATISFACTION OF	ETE WALL OF THE	ELEV,EL EQ FOUIP	
L REINFORC OPTED ACI	L REINFORCING STEEL DETAILS OPTED ACI 318/318R MANUAL	DETAILS IN ACCORDANCE WITH THE MANUAL OF STANDARD PRACTICE.	VITH THE MOST RECENTLY ACTICE.	DESIGNER AND	HE SPECIAL INSPECTO	ż			EXIST	
L REINFORC TH THE 200 LLOWING TA	L REINFORCING BAR LAPS SHALL TH THE 2006 INTERNATIONAL BU LLOWING TABLE:	SHALL BE CLASS B, IN	ALL BE CLASS B, IN ACCORDANCE BUILDING CODE OR AS SUMMARIZED IN THE	DEFINITIONS "DESIGN ENGINEER"	" OR "DESIGNER" =	. Adams Resource	ssource Consultants (ARC), THE	(ARC), THE	XX OF	
CLA: LAF JAR LENGTI	CLASS B LAP LAP SPLICE LENGTH MEASURED IN DIAMETERS (IN.)	CLASS B LAP LAP SPLICE LENGTH MEASURED IN LENGTH (IN.)		INSPECTOR FOR THE INSPECTOR FOR THE THE ENGINEER. SOWNER AND APPR "CONTRACTOR."	UT THESE PLANS.  41S PROJECT.  = GEOTECHNICAL SPI OVED BY THE GOVER SPECIALTY SHOTCRE	MAT ALSO ECIAL INSPE NING MUNIC TE (SHORIN	ALSO BE THE GEOTECHNICAL SPECIAL INSPECTOR AS APPOINTED BY THE MUNICIPALITY OR AGENCY. SHORING) WALL CONTRACTOR	AL SPECIAL  BY THE  NR  APPRINGATION OF	Z Z S E E E E E E E E E E E E E E E E E	
	40 ¢	20 25		NEAL COL = 1 THE SHOTCRETE	HE EACAVALION EARO	0 C C C C C C C C C C C C C C C C C C C	ACE FRETARED FOR		GA GALV GB	
0 ## 80 ##	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	0 4 4 50 50 4 50							HDPE	
⊢ WEI	FABRIC LONGIT IF APPL		SHALL BE A MINIMUM OF 6 INCHES LONG AND OR TRANSVERSE WIRES. SEE PLANS FOR SUBMIT ALL SHOP DRAWINGS IN ACCORDANCE						Z T T S H S H S H S H S H S H S H S H S	
TH THE SPI E THE WALI E REINFORC AWINGS IN	SPECIFICATIONS.  ALL PLANS SPECIFIONS SPECIFIONS SHOULD SH	IC DETAILS AS THEY PE WALL AND ANY OTHER ITH THE SPECIFICATIONS	TH THE SPECIFICATIONS. E THE WALL PLANS SPECIFIC DETAILS AS THEY PERTAIN TO CONNECTION OF E REINFORCED SHOTCRETE WALL AND ANY OTHER FACING. SUBMIT ALL SHOP AWINGS IN ACCORDANCE WITH THE SPECIFICATIONS.						ONP 7	
NCRETE									ν Υ Ο	
TER 28 DA` RENGTH (f' 06, WHERE	TER 28 DAYS, ALL CONCRETE SHALL RENGTH (f'c), AS MEASURED BY THE 06, WHERE THE STRENGTH f'c SHALL	TE SHALL OBTAIN A MINIMUM. D BY THE PROCEDURES IN A f'c SHALL ATTAIN 4000 PSI.	OBTAIN A MINIMUM ULTIMATE COMPRESSIVE PROCEDURES IN ASTM C109/AASHTO ATTAIN 4000 PSI.						LB,# LD LDC	
MPORARY C	ARY CUT SLOPES								크	
E SOIL NAI SIGN OF TE E DRAWING ITERIA AS AWINGS AR	ILED WALL DESIGNORMS OPEN S. ADDITIONAL D. MAY BE REQUESTE THE RESPONSI	SN BY ARC DOES NOT I CUT SLOPES UNLESS: SESIGN AND SPECIFICATIONS TED FOR EXCAVATIONS BILLTY OF THE CONTRAICS.	E SOIL NAILED WALL DESIGN BY ARC DOES NOT INCLUDE SPECIFICATIONS OR SIGN OF TEMPORARY OPEN CUT SLOPES UNLESS SPECIFICALLY PROVIDED ON E DRAWINGS. ADDITIONAL DESIGN AND SPECIFICATIONS OR PERFORMANCE HTERIA AS MAY BE REQUESTED FOR EXCAVATIONS NOT SHOWN ON THESE AWINGS ARE THE RESPONSIBILITY OF THE CONTRACTOR UNLESS AGREED TO HERWISE IN WRITING BY ARC.						L L L L L L L L L L L L L L L L L L L	
NSTRUCTION	N SEQUENCE								MECH	
C HAS ASS CONTRACTO OM AREAS IOTCRETE AI	C HAS ASSUMED THE FOLLOWING FOR THE CONTRACTOR SHALL REMOVE ORGANICS, OM AREAS REQUIRING GRADING TO CREATOTCRETE APPLICATION BEFORE STARTING	C HAS ASSUMED THE FOLLOWING FOR THIS DESIGN; CONTRACTOR SHALL REMOVE ORGANICS, DELETERIOUS OM AREAS REQUIRING GRADING TO CREATE THE "NEAT STORETE APPLICATION BEFORE STARTING DRILLING.	SN; IOUS MATERIALS AND SOIL 'NEAT LINE" SURFACE FOR	ABBREVIATIONS	SNO				M M M M K K K K K K K K K K K K K K K K	
DRILLING.	INSTALLATION AN	AD WALL CONSTRUCTION	DRILLING. INSTALLATION AND WALL CONSTRUCTION SHALL DONE BY EITHER A	AB ANCHOR	IOR BOLT	Ú	COMPRESSION		ე <u>≅</u>	

SOIL NAILED WALL ELEVATION AND SECTION моэ.ээдповэдемадА.www CEMENT KILN DUST (CKD) CLOSURE PLANS 61086 AW JJAVUQ DVV [X08.0.9 **STNATJU2NDD** c/oYasha Saber-Compass Land Grouip 916-825-4997 RESOURCE RMC Pacific Materials, 700 Highway 1, Davenport, CA **SMAGA** 



-Interesection of Bottom of Shotcre' and Run-off Collector Swale, See Detail

[225.0]

Top of Shotcrete to Slope— Down Toward Ditch to East

Northwest

+(221.0)+


+(219.0)<del>+</del>


12.451

ELEVATION IN FEET

 $\Box$ 

 $\sim$ 





8. UNLESS DESIGNER APPROVES A CONTRACTOR SUBMITTAL FOR ALTERNATIVE MEANS/METHODS, EXCAVATION FOR NEXT LOWER LIFT SHALL NOT PROCEED UNTIL ALL SHOTCRETE, STEEL PLATES, NUTS AND REQUIRED NAIL TESTING IS COMPLETE AND ENGINEER HAS ACCEPTED CONSTRUCTED SOIL NAIL WALL LIFT. = NAIL ROW ELEVATION = GRADE ELEVATION NAIL ROW = NAIL 

 $\triangleleft$ 

7. THE PROVIDED DESIGN PULLOUT VALUES ARE ASSUMED AND ARE BASED ON SUBSURFACE INFORMATION THAT INCLUDES SITE OBSERVATIONS. VALUES USED IN THE NAIL PULLOUT TESTING WILL RELY ON THE ENGINEER'S (OR REPRESENTATIVE) EVALUATION OF DESIGN INPUT, CONTRACTOR'S METHODS AND ACTUAL INTERCEPTED SUBSURFACE CONDITIONS DURING CONSTRUCTION.

6. COMPACTION EQUIPMENT SHALL NOT OPERATE CLOSER THAN 2 FEET (HORIZONTAL) FROM BACK PLANE OF SOIL NAILED WALL.

5. CONSTRUCTION EQUIPMENT THAT IS NOT PART OF NAIL INSTALLATION SHALL NOT OPERATE CLOSER THAN 5 FEET (HORIZONTAL) FROM BACK NEAT—CUT PLANE AT THE TOP OF SOIL NAILED WALL.

4. CONTRACTOR IS RESPONSIBLE FOR STABILITY OF ALL TEMPORARY CUT SLOPES AND ALL CUT SLOPES REQUIRED FOR CONSTRUCTION. TEMPORARY CUT SLOPES MAY REQUIRE PLASTIC SHEETING, SHOTCRETE FLASHCOAT AND/OR STEEL REINFORCED FALSH—COAT OF SHOTCRETE FOR TEMPORARY EROSION PROTECTION.

[150.0'] (156)

 $\bigcirc$ 


1. CONTRACTOR TO ADD AT LEAST 1—FT TO NAIL LENGTHS (L) TO ACCOMODATE PLATE, WASHER AND NUT. SEE SOIL NAIL TYPICAL SECTION.

2. CONTRACTOR TO CONFIRM LOCATION OF ALL UTILITIES BEHIND OR NEAR SOIL NAILED WALL CUT FACE AND CUT-SLOPES BEFORE BEGINNING CONSTRUCTION.

 $\Box$ 

3. CONTRACTOR IS SOLEY RESPONSIBLE FOR REPAIRS AND/OR REPLACEMENT OF SHOULD DAMAGE OCCUR AS A RESULT OF CONSTRUCTION ACTIVITIES.

EXISTING UTILITIES



28 Z Z OF 25

SHEE-

E MINIMUM LOAD US AND SHOULD NOT SE ZEROED AFTER THE

THE ALIGNMENT LOAD (AL) SH REQUIRED TO ALIGN THE TESTI EXCEED 0.05DTL. DIAL GAUGE ALIGNMENT LOAD HAS BEEN A

MINUTES 10 MINUTES 10

HOLD TIME

LOAD

AT LEAST 10
LL BE MONITORED
DTL LOAD
CREEP PORTION OF
DED AT 1, 2, 3, 5,

EACH LOAD INCREMENT SHALL MINUTES. THE VERIFICATION T FOR CREEP FOR 60 MINUTES INCREMENT. NAIL MOVEMENTS THE TEST SHALL BE MEASUREE 6, 10, 20, 30, 50, AND 60 M

c/oYdsha Saber-Compass Land Grouip 916-825-4997

SOIL NAIL SPECIFICATIONS KILN DUST (CKD) CLOSURE PLANS

Pacific Materials, 700 Highway 1, Davenport,

1770-40	моо.эояпоеэЯемаоА.v	۸۸
EXP. 6/30/18  EXP. 6/30/18  EXP. 6/30/12	61086 AW JAVUO 0771X08.	
	жезописе СОИЅИСТАИТЅ	
PHOPESSION OF THE STONE	2MAGA	,

770-10	мор. эрипезяемар. w
Exp. 6/30/18	
Z Z	STNATJURNOO
	BEROURGE
ORSHOP	2MAQA
	•

H	MCA WCA	MCV MCV DEZIGN	WEER A	N. N. S.	NAIC VAIC CEGORGIA CE	DATE OF THE PARTY	1		YM 77	COL	3-
	THE ALIGNMENT LOAD (AL) SHOULD BE THE MINIMUM LOAD REQUIRED TO ALIGN THE TESTING APPARATUS AND SHOULD NOT EXCEED 0.05DTL. DIAL GAUGES SHOULD BE ZEROED AFTER THE ALIGNMENT LOAD HAS BEEN APPLIED.	ALL INCREMENTS SHALL BE MAINTAINED WITHIN 5 PERCENT OF THE INTENDED LOAD. DEPENDING ON PERFORMANCE, EITHER A 10 MINUTE OR 60 MINUTE CREEP TEST SHALL BE PERFORMED AT 1.50DTL. NAIL MOVEMENT SHALL BE MEASURED AND RECORDED AT 1 MINITES 2 3 5 6 AND 10 MINITES WHERE THE		05 TEST NAIL ACCEPTANCE CRITERIA	A TEST NAIL SHALL BE CONSIDERED ACCEPTABLE WHEN:	1. FOR VERIFICATION TESTS, A CREEP RATE LESS THAN 0.08 INCHES PER LOG CYCLE OF TIME BETWEEN THE 6 AND 60 MINUTE READINGS IS OBSERVED DURING CREEP TESTING, AND THE RATE IS LINEAR OR DECREASING THROUGHOUT THE CREEP TEST LOAD HOLD PERIOD.	2. FOR PROOF TESTS, A CREEP RATE LESS THAN 0.04	INCHES PER LOG CYCLE OF TIME BETWEEN THE TAND TO MINUTE READINGS IS OBSERVED OR A CREEP RATE LESS THAN 0.08 INCHES PER LOG CYCLE OF TIME BETWEEN THE 6 AND 60 MINUTE READINGS, AND THE CREEP RATE IS LINEAR OR DECREASING THROUGHOUT THE CREEP TEST LOAD HOLD PERIOD.	3. THE TOTAL MOVEMENT AT THE MAXIMUM TEST LOAD EXCEEDS 80 PERCENT OF THE THEORETICAL ELASTIC ELONGATION OF THE TEST NAIL UNBONDED LENGTH.	4. A PULLOUT FAILURE DOES NOT OCCUR DURING TESTING. PULLOUT FAILURE IS DEFINED AS THE LOAD AT WHICH ATTEMPTS TO INCREASE THE TEST LOAD SIMPLY RESULT IN CONTINUED PULLOUT MOVEMENT OF THE TEST NAIL.	

3.06.05

WHERE TEMPORARY CASING OF THE UNBONDED LENGTH OF TEST NAILS IS PROVIDED, THE CASING SHALL BE INSTALLED TO PREVENT ANY REACTION BETWEEN THE CASING AND THE GROUTE BOND LENGTH OF THE NAIL AND/OR THE STRESSING APPARATUS

VERIFICATION TESTS SHALL BE SELECTED BY THE CONTRACTO REPRESENTATIVE. PROOF TES LOCATIONS SELECTED BY THE RECORDED TEST DATA SHALL REPRESENTATIVE, UNLESS APP TESTING OF NAILS SHALL NOT GROUT AND SHOTCRETE FACIN PERCENT OF THEIR SPECIFIED STRENGTHS.

FOOTING DRAINS SHALL CONSIST OF A PERFORATED PVC PIPE AND SHALL BE CONSTRUCTED AT THE BOTTOM OF EACH WALL SHOWN ON THE PLANS.

NAIL INSTALLATION GENERAL

3.04

3.04.01

FOOTING DRAINS

3.06.01 GENERAL

3.06

GAUGES, A DIAL , A PUMP, AND /

TESTING EQUIPMENT SHALL IN GAUGE SUPPORT, JACK AND REACTION FRAME.

3.06.02 TESTING EQUIPMENT

TWO SUCCESSFUL VERIFICATION TESTS SHALL BE PERFORMED IN EACH SOIL UNIT IDENTIFIED ON THE PLANS PRIOR TO STARTING INSTALLATION OF PRODUCTION NAILS. THE LOCATIONS OF THE VERIFICATION TESTS ARE DETERMINED BY THE CONTRACTOR AND APPROVED BY THE DESIGN ENGINEER. ADDITIONAL VERIFICATION TESTS MAY BE REQUIRED IF THE CONTRACTOR MODIFIES THE INSTALLATION METHODS FROM THOSE USED DURING THE INSTALLATION OF THE APPROVED VERIFICATION TEST NAILS AND WILL BE CONDUCTED AT THE CONTRACTOR'S EXPENSE.

A MINIMUM OF TWO DIAL GAUGO.001—INCH SHALL BE AVAILAE THE NAIL MOVEMENT. THE DIAMINUM TRAVEL SUFFICIENT TO PERFORMED WITHOUT RE—SETTI GAUGES SHALL BE ALIGNED WITHE NAIL AND SHALL BE SUPPUCKING SET—UP AND THE WARASURE GAUGE, AND PUMPMEASURE THE TEST LOAD. TH RECENT CALIBRATION CURVES I SUBMITTALS SECTION.

NAILS SHALL BE INSTALLED PRIOR TO THE APPLICATION OF SHOTCRETE AT THE LOCATIONS AND TO THE LENGTHS INDICATED ON THE PLANS. THE DESIGNER MAY ADD, ELIMINATE, OR RELOCATE NAILS TO ACCOMMODATE ACTUAL FIELD CONDITIONS. MODIFICATIONS TO THE DESIGN RESULTING FROM ACTIONS OF THE CONTRACTOR SHALL BE DETERMINED BY THE ENGINEER.

3.04.02

SCHEDULE 40 PVC OR OTHER MATERIAL NOT DETRIMENTAL TO THE NAIL STEEL (WOOD SHALL NOT BE USED); SECURELY ATTACHED TO THE NAIL BAR; SIZED TO POSITION THE NAIL BAR WITHIN 1 INCH OF THE CENTER OF THE DRILLHOLE; SIZED TO ALLOW TREMIE PIPE INSERTION TO THE BOTTOM OF THE DRILLHOLE; AND, SIZED TO ALLOW GROUT TO FLOW FREELY UP THE DRILLHOLE.

THE GROUT SHALL BE A NEAT OR SAND/ CEMENT MIXTURE WITH A MINIMUM 3—DAY COMPRESSIVE STRENGTH OF 1500 PSI AND A MINIMUM 28—DAY COMPRESSIVE STRENGTH OF 3000 PSI PER ASTM C109 AASHTO T106.

ASTM C150 / AASHTO M85, TYPE I.

ASTM C33 / AASHTO M6.

81/61/20

31/10/40

THE UNBONDED LENGTH OF THE TEST NAIL SHALL BE AT 3 FEET. THE BONDED LENGTH OF THE TEST NAIL SHALL DETERMINED BY THE OWNER'S REPRESENTATIVE SUCH THA ALLOWABLE BAR LOAD IS NOT EXCEEDED BUT SHALL NOT THAN 10 FEET. THE ALLOWABLE BAR LOAD DURING TEST SHALL NOT EXCEED 80 PERCENT OF THE STEEL ULTIMATE STRENGTH FOR GRADE 150 BARS OR 90 PERCENT OF THIS YIELD STRENGTH FOR GRADE 60 AND GRADE 75 BARS.

PROOF TEST NAILS SHALL BE INCREMENTALLY LOADED IN 0.25DTL INCREMENTS TO A MAXIMUM LOAD OF 1.50DTL I ACCORDANCE WITH THE FOLLOWING SCHEDULE:

TEMPORARY UNBONDED LENGTH
TEST NAIL. THE TEST NAIL BATHE SHOTCRETE FACING AND TESTING. ISOLATION OF A TESTING. ISOLATION OF A TESTING. SHOTCRETE FACING SHALL NOT REINFORCING STEEL UNDER THIS TEST NAILS MAY BE INCORPORTEMPORARY TEST UNBONDED LISUBSEQUENT TO TESTING.

CONNECTION PIPES AND WEEPHOLES SHALL BE INSTALLED AS SHOWN ON THE PLANS. CONNECTION PIPES SHALL BE LENGTHS OF SOLID PVC PIPE INSTALLED TO DIRECT WATER FROM THE GEOCOMPOSITE DRAIN STRIPS INTO THE FOOTING DRAIN.

CONNECTION PIPES AND WEEPHOLES SHALL BE CONNECTED TO THE DRAIN STRIPS AS SHOWN ON THE PLANS, UNLESS APPROVED OTHERWISE BY THE ENGINEER. THE JOINT BETWEEN THE DRAIN PIPE AND THE DRAIN STRIP, AND THE DISCHARGE END OF THE CONNECTOR PIPE SHALL BOTH BE SEALED TO PREVENT SHOTCRETE INTRUSION. DAMAGE OF THE GEOCOMPOSITE DRAIN STRIP WHICH, IN THE OPINION OF THE OWNER'S REPRESENTATIVE, MAY CAUSE INTERRUPTION IN FLOW SHALL REQUIRE INSTALLATION OF ADDITIONAL CONNECTION PIPES OR WEEPHOLES ABOVE THE DAMAGED SECTION. CONNECTION PIPES SHALL BE EXTENDED TO THE EDGE OF THE FOOTING DRAIN BUT NOT THROUGH THE DRAINAGE GEOTEXTILE. THE INTERRUPTED.

NAIL GROUT SHALL HAVE A M 1500 PSI IN 3 DAYS AND 30 SHALL BE TESTED BY THE CO ASTM C109 / AASHTO T106 ONE TEST FOR EVERY 50 CUE ONCE PER WEEK, WHICHEVER

3.05.03

THE GEOCOMPOSITE DRAIN STRIPS SHALL BE AT LEAST 16 INCHES WIDE AND SHALL BE SECURED TO THE EXCAVATION FACE WITH THE GEOTEXTILE SIDE AGAINST THE GROUND BEFORE SHOTCRETING. DRAIN STRIPS SHALL BE MADE CONTINUOUS BY USING THE "SHINGLE" METHOD OF SPLICING WITH A 16 INCH MINIMUM OVERLAP SUCH THAT THE FLOW OF WATER IS NOT IMPEDED OR DIRECTED TO THE SHOTCRETE SIDE OF THE STRIPS.

3.03.03 CONNECTION PIPES AND WEEPHOLES

FOR DISTANCES AWAY FROM THE WALL FACE GREATER THAN TH CURRENT WALL HEIGHT, MASS EXCAVATION MAY OCCUR AT ANY TIME, BUT WITH SLOPES NO STEEPER THAN 1H:1V, UNLESS APPROVED OTHERWISE BY THE DESIGNER.

DRAINAGE

AND WALL

SOIL NAILS

SECTION 2350

GENERAL

DESCRIPTION

1.01

3.05.04 TEST NAIL UNBONDED LE

FOR BID AND CONSTRUCTION

B. B. A. S.	THROUGHOUT THE CREEP TEST LOAD HOLD PERIOD.  2. FOR PROOF TESTS, A CREEP RATE LESS THAN 0.04 INCHES PER LOG CYCLE OF TIME BETWEEN THE 1 AND 10 MINUTE READINGS IS OBSERVED OR A CREEP RATE LESS THAN 0.08 INCHES PER LOG CYCLE OF TIME BETWEEN THE 6 AND 60 MINUTE READINGS, AND THE CREEP RATE IS LINEAR OR DECREASING THROUGHOUT THE CREEP TEST LOAD HOLD PERIOD.  3. THE TOTAL MOVEMENT AT THE MAXIMUM TEST LOAD EXCEEDS 80 PERCRET OF THE THEORETICAL ELASTIC ELONGATION OF THE TEST NAIL UNBONDED LENGTH.  4. A PULLOUT FAILURE DOES NOT OCCUR DURING TESTING. PULLOUT FAILURE IS DEFINED AS THE LOAD AT WHICH ATTEMPTS TO INCREASE THE TEST LOAD SIMPLY RESULT IN CONTINUED PULLOUT MOVEMENT OF THE TEST NAIL.  AT THE CONTRACTOR'S OPTION, SUCCESSFUL PROOF TEST NAILS MEETING. THE ABOVE TEST ACCEPTANCE CRITERIA MAY BE INCORPORATED AS PRODUCTION NAILS, PROVIDED THAT (1) THE DURING TESTING, CJ. THE MINHUM REQUIRED HOLE DIAMETER HAS BEEN MAINTAINED, AND (3) THE TEST NAIL LENGTH AND PRODUCTION NAIL LENGTH AND BAR SIZE. TEST NAILS MEETING THESE REQUIREMENTS SHALL BE COMPLETED BY SATISFACTORILY GROUTING THE UNBONDED TEST LENGTH MAINTAINING THE TENPORARY UNBONDED TEST LENGTH MAINTAINING THE TEMPORARY UNBONDED TEST LENGTH MAINTAINING THE TEMPORARY UNBONDED TEST LENGTH SUBSEQUENT GROUTING SEQUIREMENTS SHALL BE CONSIDERED INADEQUATE. THE CONTRACTOR'S RESPONSIBILITY.  56 INADEQUATE TEST NAIL SHALL BE CONSIDERED INADEQUATE. THE CONTRACTOR SHALL PROPOSE VEHICRATION TEST NAILS SHERNATIVE METHODS AND INSIDILARY THEN THE SHALLS SHERNATIVE METHODS AND INSIDILARY THEN THE SHALLS.  THE DESIGNER SHALL EVALUATE THE CONTRACTOR SHALL PROPOSE CONSIDERED INADEQUATE. THE CONTRACTOR SHALL PROPOSE OF THE NATIVE METHODS AND INSIDILARY THEN THEN SHALL PROPOSE OF THE NATIVE METHODS AND INSIDILARY THEN THAT SHALL SHALLS  THE NATIVE METHOD THAT THEN THEN THAT SHALL
---	---

THE JACK AND PRESSURE GAINDEPENDENT TESTING LABORA GAUGE SHALL BE GRADUATED AND SHALL HAVE A RANGE N ANTICIPATED MAXIMUM PRESSUAPPROVED OTHERWISE BY THE JACK SHALL BE SUFFICIE PERFORMED WITHOUT RE—SETTING THAN 1 MINUTE.

THE CONTRACTOR SHALL SELECT DRILLING EQUIPMENT AND METHODS SUITABLE FOR THE GROUND CONDITIONS DESCRIBED IN THE GEOTECHNICAL REPORT. DRILLHOLE DIAMETER SHALL BE SELECTED TO PROVIDE THE MINIMUM SPECIFIED GROUT COVER OVER THE SOIL NAIL TENDON AND TO DEVELOP THE SPECIFIED LOAD CARRYING CAPACITY. DRILLING MUDS USED TO ASSIST IN CUTTING REMOVAL SHALL NOT BE ALLOWED. UNCASED DRILLHOLES SHALL BE OBSERVED FOR CLEANLINESS PRIOR TO INSERTION OF THE SOIL NAIL TENDON. IN CAVING GROUND, THE CONTRACTOR SHALL USE CASED DRILLHOLES.

THE JACK SHALL BE INDEPEN OVER THE NAIL SO THAT THE WEIGHT OF THE JACK. THE PLACED OVER THE NAIL IN S BEARING PLATES, AND STRESS ALIGNMENT. THE JACK SHALL BEGINNING OF THE TEST SUC REPOSITIONING OF THE JACK REQUIRED.

Ö.

THE CONTRACTOR SHALL IMMEDIATELY SUSPEND DRILLING OPERATIONS IF GROUND SUBSIDENCE IS OBSERVED, IF THE SOIL NAIL WALL IS ADVERSELY AFFECTED, OR IF ADJACENT STRUCTURES ARE DAMAGED AS A RESULT OF THE DRILLING OPERATION. THE ADVERSE CONDITIONS SHALL BE STABILIZED IMMEDIATELY AND THE DESIGNER SHALL BE NOTIFIED OF SUCH CONDITIONS WITHIN 24 HOURS.

ACK SHALL NT IN LESS		UNBONDED TEST LENGTH OF THE NAIL HODDING TESTING. (2) THE MINIMUM REOU
	HAS	BEEN MAINTAINÉD, AND (3) THE TES
D CENTERED	PRO	DUCTION VAIL LENGTH AND EASTERN TO THE CONTROL OF T
SHALL BE	MEE	IING IHESE REQUIREMENTS SHALL BE ISFACTORILY GROUTING THE UNBONDEI
HE JACK,	MAII	MAINTAINING THE TEMPORARY UNBONDED
- W	ם ס	
) NOT BF	3.06.06	3.06.06 INADEQUATE TEST NAIL PERFORMANCE
1 1 -	A. THE	THE DESIGNER SHALL EVALUATE THE RES
NN OF	VER	FICATION TEST. INSTALLATION METHO
AATION OF	200	CONSIDERED INADEQUATE. THE CONTRAC
ANY /HERE THE	ALT VFR	ALTERNATIVE METHODS AND INSTALL REPL VFRIFICATION TEST NAILS. RFPLACEMENT
TE FACING,	BE	BE INSTALLED AND TESTED AT NO ADDITI
	B. THE	THE DESIGNER MAY REQUIRE THAT THE C
	NOS:	E OR ALL OF THE PRODUCTION NAILS
	IAN!	DEQUATE PROOF TEST NAIL. ALTERNA
0	DES	IGNER MAY REQUIRE PROOF TESTING
NAILS IN	SNI	FALLED PROOF TEST NAILS BE CONDU
UMPTIONS.	ADV	ACENI PREVIOUSLY INSTALLED PRODUC
L BE	ADD	ITIONAL PROOF TESTS OR INSTALLATION
PRODUCTION	MOM	VIFIED NAILS AS A RESULT OF POOR I
	PER	FORMANCE SHALL BE AT NO ADDITION
FO & CTIACO	ĮMO	OWNER, UNLESS DETERMINED BY THE DES

NAIL TENDONS SHALL BE INSERTED INTO THE DRILLHOLE TO THE REQUIRED LENGTH WITHOUT DIFFICULTY AND IN SUCH A MANNER AS TO PREVENT DAMAGE TO THE DRILLHOLE. TENDONS THAT CANNOT BE FULLY INSERTED TO THE DESIGN DEPTH WITH RELATIVE EASE SHALL BE REMOVED FROM THE DRILLHOLE AND THE DRILLHOLE SHALL BE CLEANED SUFFICIENTLY TO ALLOW UNOBSTRUCTED INSTALLATION OF THE TENDON.

IF THE NAIL TENDON IS INSTALLED USING CASED OR HOLLOW—STEM AUGER METHODS, CENTRALIZERS ARE NOT REQUIRED PROVIDED THE INSTALLATION METHOD ENSURES THAT THE TENDON WILL REMAIN IN THE CENTRAL PORTION OF THE NAIL GROUT. IN SUCH SITUATIONS, SLUMP SHALL NOT EXCEED 8 INCHES.

ä

STEM AUGER METHODS, CENTRALIZERS ARE NOT REQUIRED	3.06.	3.06.03 VERIFICATION TESTING OF SACRIFICIAL NAILS
PROVIDED THE INSTALLATION METHOD ENSURES THAT THE TENDON WILL REMAIN IN THE CENTRAL PORTION OF THE NAIL GROUT. IN SUCH SITUATIONS, SLUMP SHALL NOT EXCEED 8	Ą.	VERIFICATION TESTING IN EACH SOIL UNIT SHALL BE PERFORMED PRIOR TO INSTALLATION OF PRODUCTION NAILS IN
INCHES.		HAN SOLL ONLING VERIFITHE CONTRACTORS INSTALLATION METHODS, NAIL PULLOUT CAPACITY, AND DESIGN ASSUMPTIONS. THE NAILS HISED FOR THE VERIFICATION TESTS SHALL BE
BOREHOLES READY FOR NAIL BAR INSTALLATION SHALL BE CLEAR OF ALL OBSTRUCTIONS SUCH AS BUT NOT LIMITED TO SOIL, ROCKS ROOTS OF OTHER MATERIALS THAT CONSTRICT THE UNIFROM		NAILS. PAYMENT FOR ADDITIONAL VERIFICATION TESTS PRODUCTION OF THE PROPERTY OF THE CONDITIONS AS
DIAMETER OF THE BOREHOLE. CAVING WILL BE CAUSE FOR REJECTION AND MAY REQUIRE A REPLACEMENT BOREHOLE.		RECOURT DOE TO DIFFERING SHE CONDITIONS, AS DEFERMINED BY THE DESIGNER, SHALL BE PER THE CONTRACT UNIT PRICE.
GROUTING	В.	TEST NAILS SHALL BE CONSTRUCTED USING THE SAME
.01 GROUTING EQUIPMENT		EQUIPMENT, METHODS, AND HOLE DIAMETER AS PLANNED FOR THE PRODUCTION NAILS. CHANGES IN THE DRILLING OR
UT EQUIPMENT SHALL PRODUCE A UNIFORMLY MIXED GROUT		INSTALLATION METHOD MAY REQUIRE ADDITIONAL VERIFICATION TESTING AS DETERMINED BY THE DESIGNER AND SHALL BE
FREE OF LUMPY AND UNDISPERSED CEMENT. A POSITIVE DISPLACEMENT GROUT PUMP SHALL BE USED. THE PUMP SHALL		PROVIDED AT NO ADDITIONAL COST TO THE OWNER.
EQUIPPED WITH A PRESSURE GAUGE THAT CAN MEASURE AT	o;	THE UNBONDED LENGTH OF THE TEST NAIL SHALL BE AT LEAS
ST TWICE BUT NO MORE THAN THREE TIMES THE INTENDED		3 FEET UNLESS APPROVED OTHERWISE BY THE DESIGNER. THI
UT PRESSURE. THE GROUTING EQUIPMENT SHALL BE SIZED enable the entide nail to be conited in one		BONDED LENGTH OF THE TEST NAIL SHALL BE DETERMINED BY

3.05.01

3.05

	ю́	TEST NAILS SHALL BE CONSTRUCTED USING THE SAME EQUIPMENT, METHODS, AND HOLE DIAMETER AS PLANNED FO THE PRODUCTION NAILS. CHANGES IN THE DRILLING OR INSTALLATION METHOD MAY REQUIRE ADDITIONAL VERIFICATIO
ED GROUT TIVE IIMP SHALI		TESTING AS DETERMINED BY THE DESIGNER AND SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.
ASURE AT	ပ	THE UNBONDED LENGTH OF THE TEST NAIL SHALL BE AT LE 3 FEET UNLESS APPROVED OTHERWISE BY THE DESIGNER.
BE SIZED		BONDED LENGTH OF THE TEST NAIL SHALL BE DETERMINED THE ENGINEER BASED ON THE BAR GRADE AND SIZE SUCH
BLE OF		THE ALLOWABLE BAR LOAD IS NOT EXCEEDED, BUT SHALL N BE LESS THAN 10 FEET. THE ALLOWABLE BAR LOAD DURIN
		TESTING SHALL NOT EXCEED 80 PERCENT OF THE STEEL ULTIMATE STRENGTH FOR GRADE 150 BARS OR 90 PERCENT
ON OF		IHE YIELD SIKENGIH FOR GRADE 60 AND GRADE /5 BARS.
IF THE INT GROUT	Ο.	THE DESIGN TEST LOAD (DTL) DURING TESTING SHALL BE DETERMINED BY MULTIPLYING THE BOND LENGTH OF THE NA
) HOUT		TIMES THE DESIGN ADHESION. VERIFICATION TEST NAILS SHALL BE INCREMENTALLY LOADED AND UNIDADED IN
BE LEFT		ACCORDANCE WITH THE FOLLOWING SCHEDULE:
NG UNLESS		LIVIE GIOLI

INICE BOI NO MORE ITAN ITREE IMES INE INTENDED. T PRESSURE. THE GROUTING EQUIPMENT SHALL BE SIZED.
VABLE THE ENTIRE WALL TO BE GROUTED IN ONE INDOUS OPERATION. THE MIXER SHALL BE CAPABLE OF INUOUSLY AGITATING THE GROUT DURING USAGE.
ROUTING METHODS
ORILLHOLE SHALL BE GROUTED AFTER INSTALLATION OF
TENDON CAN BE ALLOWED PROVIDED NEAT CEMENT GROUT
JOH THE GROUT TO THE SPECIFIED LENGTH WITHOUT
CULTY. NO PORTION OF THE NAIL HOLE SHALL BE LEFT
FOR MORE THAN 60 MINUTES PRIOR TO GROUTING UNLESS
TED AT THE LOWEST POINT OF EACH DRILLHOLE THROUGH
OUT TREMIE PIPE, CASING, HOLLOW—STEM AUGER, OR
RODS WITH THE DRILLHOLE FILLED IN ONE CONTINUOUS
ATION. COLD JOINTS IN THE GROUT PLACEMENT ARE
WED FOR CONSTRUCTION OF TEST NAILS. THE CONDUIT
ERING THE GROUT SHALL BE KEPT BELOW THE SURFACE OF
SROUT AS THE CONDUIT IS WITHDRAWN. THE GROUTING

	S.C.S.C.Z. GROOTING METHODS
	A. THE DRILLHOLE SHALL BE GROUTED AFTER IN THE NAIL TENDON. GROUTING PRIOR TO INSI
	NAIL TENDON CAN BE ALLOWED PROVIDED NE
. 14-	IS USED AND THE NAIL BAR IS IMMEDIATELY
-	DIFFICULTY. NO PORTION OF THE NAIL HOLE
1	OPEN FOR MORE THAN 60 MINUTES PRIOR TO
	APPROVED OTHERWISE BY THE ENGINEER. THIS TOWEST BOINT OF EACH DE
	A GROUT TREMIE PIPE, CASING, HOLLOW-STE
. >	DRILL RODS WITH THE DRILLHOLE FILLED IN (
_ C	OPERATION. COLD JOINTS IN THE GROUT PL.
2	ALLOWED FOR CONSTRUCTION OF TEST NAILS.
	DELIVERING THE GROUT SHALL BE KEPT BELO
	THE GROUT AS THE CONDUIT IS WITHDRAWN.
	CONDUIT SHALL BE WITHDRAWN AS THE NAIL
	IN A MANNER WHICH PREVENTS THE CREATIO
	QUANTITY OF GROUT AND THE GROUTING PRE
	RECORDED FOR EACH SOIL NAIL. GROUT PRE

Ä	THE DRILLHOLE SHALL BE GROUTE
	NAIL TENDON CAN BE ALLOWED P
FU DONING	IS USED AND THE NAIL BAR IS IN
C VICINION OF	THROUGH THE GROUT TO THE SPE
F APPROVAL	DIFFICULTY. NO PORTION OF THE
7	OPEN FOR MORE THAN 60 MINUTE
WO FBOM	APPROVED OTHERWISE BY THE EN
W C I COM	INJECTED AT THE LOWEST POINT
CONVEYED	A GROUT TREMIE PIPE, CASING, H
DAINFO PX	DRILL RODS WITH THE DRILLHOLE
TOP FXISTING	OPERATION. COLD JOINTS IN THE
	ALLOWED FOR CONSTRUCTION OF
7 -     C	DELIVERING THE GROUT SHALL BE
LL DE	THE GROUT AS THE CONDUIT IS \
	CONDUIT SHALL BE WITHDRAWN A
	IN A MANNER WHICH PREVENTS T
	QUANTITY OF GROUT AND THE GR
	RECORDED FOR EACH SOIL NAIL.
	CONTROLLED TO DREVENT EYCESS

	NAIL TENDON CAN BE ALLOWED PROV
	IS USED AND THE NAIL BAR IS IMME
	THROUGH THE GROUT TO THE SPECIF
APPROVAL	DIFFICULTY. NO PORTION OF THE NA
7 7. V 7 1. V 7 1	OPEN FOR MORE THAN 60 MINUTES
NS FROM	APPROVED OTHERWISE BY THE ENGIN
VO LICEN	INJECTED AT THE LOWEST POINT OF
A LONE	A GROUT TREMIE PIPE, CASING, HOLL
	DRILL RODS WITH THE DRILLHOLE FIL
O LINTING	OPERATION. COLD JOINTS IN THE GI
	ALLOWED FOR CONSTRUCTION OF TES
	DELIVERING THE GROUT SHALL BE KE
ir DE	THE GROUT AS THE CONDUIT IS WITH
	CONDUIT SHALL BE WITHDRAWN AS T
	IN A MANNER WHICH PREVENTS THE
	QUANTITY OF GROUT AND THE GROUT
	RECORDED FOR EACH SOIL NAIL. GR
	CONTROLLED TO PREVENT EXCESSIVE
Z	FRACTURING.

DURING TION OF THALL APPROVAL HE TURED NVEYED NVEYE	m.	THE NAIL TENDON. GROUTING PRIOR TO INSERTION OF THE NAIL TENDON CAN BE ALLOWED PROVIDED NEAT CEMENT GROUT IS USED AND THE NAIL BAR IS IMMEDIATELY INSERTED THROUGH THE GROUT TO THE SPECIFIED LENGTH WITHOUT DIFFICULTY. NO PORTION OF THE NAIL HOLE SHALL BE LEFT OPEN FOR MORE THAN 60 MINUTES PRIOR TO GROUTING UNLESS APPROVED OTHERWISE BY THE ENGINEER. THE GROUT SHALL BE INJECTED AT THE LOWEST POINT OF EACH DRILLHOLE THROUGH A GROUT TREMIE PIPE, CASING, HOLLOW—STEM AUGER, OR DRILL RODS WITH THE DRILLHOLE FILLED IN ONE CONTINUOUS OPERATION. COLD JOINTS IN THE GROUT PLACEMENT ARE ALLOWED FOR CONSTRUCTION OF TEST NAILS. THE CONDUIT THE GROUT SHALL BE KEPT BELOW THE SURFACE OF THE GROUT AS THE CONDUIT IS WITHDRAWN. THE GROUTING CONDUIT SHALL BE WITHDRAWN AS THE NAIL HOLE IS FILLED IN A MANNER WHICH PREVENTS THE CROUTING PRESSURES SHALL BE RECORDED FOR EACH SOIL NAIL. GROUT PRESSURES SHALL BE CONTROLLED TO PREVENT EXCESSIVE GROUND HEAVE OR FRACTURING.
		CASED OR AUGER—CASI METHODS, THE GROUI SURFACE WITHIN THE CASING SHALL BE CONTINUALLY MONITORED FOR MAINTENANCE OF "HEAD" SUFFICIENT TO OFFSET THE EXTERNAL GROUNDWATER/SOIL PRESSURE.

	₹.	E DRILLHOLE SHALL BE GROOIED
	王	E NAIL TENDON. GROUTING PRIO
SNIGITO	ΑN	NAIL TENDON CAN BE ALLOWED PRC
DOINING OF	<u>S</u>	IS USED AND THE NAIL BAR IS IMM
	王	THROUGH THE GROUT TO THE SPECI
STALL ADDDOVAL	H	DIFFICULTY. NO PORTION OF THE N
71 - 70 V 71 THE	PP	EN FOR MORE THAN 60 MINUTES
O FBOM	AP	PROVED OTHERWISE BY THE ENGII
OTIPED	Ź	INJECTED AT THE LOWEST POINT OF
ONVEXED	⋖	GROUT TREMIE PIPE, CASING, HOL
	DR	ILL RODS WITH THE DRILLHOLE FI
MINEU DI	P	ERATION. COLD JOINTS IN THE (
	AL	ALLOWED FOR CONSTRUCTION OF TE
	30	LIVERING THE GROUT SHALL BE K
7.05	프	E GROUT AS THE CONDUIT IS WIT
<u>.</u>	8	CONDUIT SHALL BE WITHDRAWN AS
	Z	IN A MANNER WHICH PREVENTS THE
	9	QUANTITY OF GROUT AND THE GROU
	RE	RECORDED FOR EACH SOIL NAIL. G
	S	CONTROLLED TO PREVENT EXCESSIVE
Z N	FR	FRACTURING.

	₹.	THE DRILLHOLE SHALL BE GROU
		THE NAIL TENDON. GROUTING
SNIGHT CHARLE		NAIL TENDON CAN BE ALLOWED
TE ATTENTION OF		IS USED AND THE NAIL BAR IS
APEAS SHALL		THROUGH THE GROUT TO THE !
NO THE APPROVAL		DIFFICULTY. NO PORTION OF 1
TED BY THE		OPEN FOR MORE THAN 60 MIN
TED BIOWS FROM		APPROVED OTHERWISE BY THE
I RE CAPTIRED		INJECTED AT THE LOWEST POIN
K AND CONVEVED		A GROUT TREMIE PIPE, CASING,
N AND CONVELED S DETERMINED BY		DRILL RODS WITH THE DRILLHO
S DELENMINED BI HDFS FOR FYINTING		OPERATION. COLD JOINTS IN .
OKES FOR EXISTING		ALLOWED FOR CONSTRUCTION C
NO WILL BE		DELIVERING THE GROUT SHALL
OCTIMENTS		THE GROUT AS THE CONDUIT IS
		CONDUIT SHALL BE WITHDRAWN
		IN A MANNER WHICH PREVENTS
		QUANTITY OF GROUT AND THE
		RECORDED FOR EACH SOIL NAII
		CONTROLLED TO PREVENT EXCE
D AS SHOWN		FRACTURING.
SINIO		
SE	œ.	DURING CASING REMOVAL FOR
TUDINAL AXIS		CASED OR AUGER-CAST METHO

	ATTROVED CIRERWISE DI INE DESIGNER.
œ.	SUBSEQUENT MASS EXCAVATION BENEATH A PRECEDING SHOTCRETE LIFT, NO CLOSER THAN 5 FEET FROM THE FACE OF SHOTCRETE, MAY OCCUR ANY TIME 24—HOURS AFTER SHOTCRETING THE PRECEDING LIFT. ALL TEMPORARY SLOPES THAT ARE HIGHER THAN 4 FEET SHALL NOT BE STEEPER THAN 1H:1V UNLESS APPROVED OTHERWISE BY THE DESIGNER.
· i	DURING MASS EXCAVATION OF THE DRILL BENCH FOR THE NEXT ROW OF NAILS, THE CONTRACTOR SHALL MAINTAIN A BENCH OF MATERIAL TO SERVE AS BOTH A PLATFORM FOR THE DRILLING EQUIPMENT, AND AS A STABILIZING BERM AGAINST THE FINAL WALL EXCAVATION FACE NEAT—LINE. IN ACCORDANCE WITH THAT SHOWN ON THE PLANS OR APPROVED OTHERWISE BY THE DESIGNER, THE MATERIAL NEAR THE WALL FACE MAY BE EITHER (A) A NATIVE BERM, (B) A SOFT BERM, OR (C) NEAT CUT. IN ALL THREE CASES, THE DRILL BENCH (IF COMPLETEING HORIZONTAL INSTALLATION) SHALL NOT BE MORE THAN 3 FEET BELOW THE ROW OF NAILS TO BE INSTALLED AND SHALL EXTEND OUT FROM THE WALL FACE A MINIMUM DISTANCE TO PROVIDE A SAFE WORKING BENCH FOR THE DRILL EQUIPMENT AND WORKERS. THE CONTRACTOR IS COMPLETELY RESPONSIBLE FOR THE SAFETY AND STABILITY OF THE TEMPORARY DRILL BENCH AND WALL FACE CUT, UNTIL THE CORRESPONDING SHOTCRETE LIFT WITH CONNECTION HARDWARE IS CONSTRUCTED AS SHOWN ON THE PLANS.
á	SUBSEQUENT MASS EXCAVATION BENEATH A PRECEDING SHOTCRETE LIFT, CLOSER THAN 5 FEET FROM THE FACE OF SHOTCRETE, SHALL NOT OCCUR UNTIL: (1) NAIL GROUT AND SHOTCRETE ON THE PRECEDING LIFT SHALL HAVE REACHED 50 PERCENT OF THEIR SPECIFIED 28—DAY COMPRESSIVE STRENGTHS; AND (2) INSTALLATION OF CONNECTION HARDWARE AND NAIL TESTING FOR THE PRECEDING LIFT ARE COMPLETE AND ACCEPTABLE TO THE OWNER'S REPRESENTATIVE. MASS EXCAVATION CLOSER THAN 5 FEET TO THE SHOTCRETE FACE MUST BE IN ACCORDANCE WITH THE DRILL BERM, BENCH AND EMBANKMENT REQUIREMENTS PREVIOUSLY DESCRIBED ABOVE AND SHOWN ON THE PLANS.
E. 6.	EXCAVATION OF THE GROUND BEYOND THE FINAL WALL FACE SHALL NOT BE ALLOWED. INADVERTENT OVEREXCAVATION BEYOND THE FINAL WALL FACE SHALL BE RESTORED BY THE CONTRACTOR USING A METHOD APPROVED BY THE DESIGNER AND AT NO ADDITIONAL COST TO THE OWNER.
<b>.</b> .	CAVATION TO NE) SHALL BE SOUND LOSS, NIMIZE DEGRAI FERLYING PORT OF NAME CORRESENT CENTER SEVENT GROUN OR SHOTCRETE
3.02. A. 3.02.	WHERE THE CONTRACTOR'S CONSTRUCTION SEQUENCING RESULTS IN A DISCONTINUOUS LIFT ALONG ANY NAIL ROW, THE ENDS OF THE LIFT SHALL EXTEND BEYOND THE ENDS OF THE NEXT LOWER LIFT BY AT LEAST 10 FEET. SLOPES/BERMS IMMEDIATELY BENEATH THESE STEPPED LIFTS SHALL BE CONSTRUCTED TO PREVENT SLOUGHING OR FAILURE THAT WOULD RESULT IN LOSS OF THE FACE SUPPORT PROVIDED BY THE SLOPES/BERMS.
•	IRS, R. THE S. THE S. TOR. TOR. TOR. TOR. TOR. TOR. TOR. THE S. TOR. THE S. TOR. THE S. THE S
3.03	WALL DRAINAGE 01 DESCRIPTION
Ą.	THE DRAINAGE NETWORK SHALL CONSIST OF INSTALLING THE PREFABRICATED GEOCOMPOSITE DRAINAGE STRIPS, PVC CONNECTION PIPES, AND WALL FOOTING DRAINS AS SHOWN ON THE PLANS OR AS DIRECTED BY THE DESIGNER. EXCLUSIVE OF THE WALL FOOTING DRAINS, ALL ELEMENTS OF THE DRAINAGE NETWORK SHALL BE INSTALLED PRIOR TO SHOTCRETING.
3.03.	TROL
÷	LOCALIZED AREAS OF PERCHED WATER MAY BE ENCOUNTERED. THE CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE IF GROUNDWATER OCCURS, IS ENCOUNTERED, OR OBSERVERED IN AT OR ADJACENT TO THE EXCAVATION FACE.
œ.	THE CONTRACTOR SHALL PROVIDE POSITIVE CONTROL AND DISCHARGE OF ALL SURFACE WATER ENCOUNTERED DURING CONSTRUCTION TO THE EXTENT NECESSARY TO PREVENT ADVERSE CONDITIONS AS DETERMINED BY THE OWNER'S REPRESENTATIVE.
ပ	EXISTING SUBSURFACE DRAINAGE FEATURES ENCOUNTERED DURING

AASHTO M291, GRADE B, HEXAGONAL FITTED WITH BEVELED WASHER OR SPHERICAL SEAT TO PROVIDE UNIFORM BEARING.

WASHERS

ASTM A307 OR APPROVED EQUAL.

ASTM A709 / AASHTO M270, GRADE 36.

ASIM ASU/ OK APPROVED EQUAL.	OF THE PROPOSED ME
E70XX AND IN ACCORDANCE WITH AWS	PROTRUSIONS AT LEASTITE WORK. SHOULD I
UI.  100.	RESULT IN VOIDS BEYC
NEEDLE PUNCHED, NON-WOVEN, PUNCTURE	LINE), THE CONTRACTO
RESISTANCE (ASTM D4833) 335 N, GRAB	METHOD OF BACKFILLIN SLICH METHOD(S) AT 1
STRENGTH (ASTM D4632) 690 N, FABRIC	THE WORK.
WEIGHT (ASTM 3776) 0.2 KG/M2,	
APPARENT OPENING SIZE (AOS) (COE	3 03 WALL DRAINAGE
CW-02215) 70.	1000
	3.03.01 DESCRIPTION
MIDANDAIN GOOD ON AMEDDAIN SOO	
	A. THE DRAINAGE NETWOR
	PREFABRICATED GEOCOI
OCHEDIII E AO DVC	PIPES, AND WALL FOOT

.IN 500.			HALL BE ADEQUATELY STORED TO PREVENT MOISTURE ION AND PARTIAL HYDRATION. CEMENT THAT HAS AKED OR LUMPY SHALL NOT BE USED.	REINFORCEMENT SHALL BE CAREFULLY HANDLED AND STORED ON SUPPORTS TO KEEP THE STEEL FROM
MIRADRAIN 6000 OR AMERDRAIN 500.			HALL BE ADEQUATELY STORED TO PREVENT MOISTI ION AND PARTIAL HYDRATION. CEMENT THAT HAS AKED OR LUMPY SHALL NOT BE USED.	REINFORCEMENT SHALL BE CAREFULLY HANDLED , STORED ON SUPPORTS TO KEEP THE STEEL FROM
OR	ς.		D T	CAR
0009	SCHEDULE 40 PVC.	AGE	STORE ATION	L BE 70 x
RAIN	DULE	STOR	TELY SHYDR SHALL	SHALI
MIRAD	SCHE	NG AND	ADEQUAT PARTIAL LUMPY	CEMENT ON SUPF
DRAIN	ш	S HANDLING AND STORAGE	HALL BE ADEQUATELY STORED TO PREVION AND PARTIAL HYDRATION. CEMENT:AKED OR LUMPY SHALL NOT BE USED.	. REINFOR STORED

2.02 MATERIALS HANDLING AND STORAGE	A. CEMENT SHALL BE ADEQUATELY STORED TO PREVENT MOISTURE DEGRADATION AND PARTIAL HYDRATION. CEMENT THAT HAS BECOME CAKED OR LUMPY SHALL NOT BE USED.	B. ALL STEEL REINFORCEMENT SHALL BE CAREFULLY HANDLED AND SHALL BE STORED ON SUPPORTS TO KEEP THE STEEL FROM CONTACT WITH THE GROUND. STEEL BARS SHALL BE PICKED UP IN SUCH A WAY AS TO PREVENT OVERSTRESSING. DAMAGE TO THE NAIL STEEL AS A RESULT OF OVERSTRESSING, ABRASION, CUTS NICKS, WELDS, AND WELD SPLATTER SHALL BE CAUSE FOR REJECTION BY THE OWNER'S REPRESENTATIVE. GROUNDING OF WELDING LEADS TO THE NAIL STEEL SHALL NOT BE ALLOWED. NAIL STEEL SHALL BE PROTECTED FROM AND SUFFICIENTLY FREE OF DIRT, RUST, AND OTHER DELETERIOUS SUBSTANCES PRIOR TO INSTALLATION. HEAVY CORROSION OR PITTING OF NAILS SHALL BE CAUSE FOR REJECTION BY THE OWNER'S REPRESENTATIVE. LIGHT RUST THAT HAS NOT RESULTED IN PITTING IS ACCEPTABLE.
-------------------------------------	--	--

DRAIL STEEL REINFORCEMENT SHALL BE CAREFULLY HANDLED AND SHALL BE STORED ON SUPPORTS TO KEEP THE STEEL FROM CONTACT WITH THE GROUND. STEEL BARS SHALL BE PICKED UIN SUCH A WAY AS TO PREVENT OVERSTRESSING. DAMAGE TO THE NAIL STEEL AS A RESULT OF OVERSTRESSING, ABRASION, CINCKS, WELDS, AND WELD SPLATTER SHALL BE CAUSE FOR WELDING LEADS TO THE NAIL STEEL SHALL NOT BE ALLOWED. NAIL STEEL SHALL NOT BE ALLOWED. NAIL STEEL SHALL NOT BE ALLOWED. NAIL STEEL SHALL BE PROTECTED FROM AND SUFFICIENTLY FREIOF DIRT, RUST, AND OTHER DELETERIOUS SUBSTANCES PRIOR TO INSTALLATION. HEAVY CORROSION OR PITTING OF NAILS SHALL BE CAUSE FOR REJECTION BY THE OWNER'S REPRESENTATIVE. LIGHT RUST THAT HAS NOT RESULTED IN PITTING IS ACCEPTABL BROVIDED IN ROLLS WRAPPED WITH A PROTECTIVE COVERING AND STORED IN A MANNER THAT PROTECTIVE REBOUND. PROTECTIVE WRAPPING SHALL NOT BE REMOVED UNTIL	<b>ங்</b> ப்	
IMMEDIATELY BEFORE THE GEOTEXTILE OR DRAIN STRIP IS INSTALLED. EXTENDED EXPOSURE TO ULTRA-VIOLET LIGHT		
PROVIDED IN ROLLS WRAPPED WITH A PROTECTIVE COVERING AND STORED IN A MANNER THAT PROTECTS THE FABRIC FROM MUD, DIRT, DUST, DEBRIS, AND SHOTCRETE REBOUND.  PROTECTIVE WRAPPING SHALL NOT BE REMOVED UNTIL		
DRAINAGE GEOTEXTILE AND GEOCOMPOSITE DRAINS SHALL BE	ပ်	
BE CAUSE FOR REJECTION BY THE OWNER'S REPRESENTATIVE. LIGHT RUST THAT HAS NOT RESULTED IN PITTING IS ACCEPTAB		
NAIL STEEL SHALL BE PROTECTED FROM AND SUFFICIENTLY FR OF DIRT, RUST, AND OTHER DELETERIOUS SUBSTANCES PRIOR NETALLATION OF NAMES SHALL		
REJECTION BY THE OWNER'S REPRESENTATIVE. GROUNDING OI WELDING LEADS TO THE NAIL STEEL SHALL NOT BE ALLOWED.		
THE NAIL STEEL AS A RESULT OF OVERSTRESSING, ABRASION, NICKS, WELDS, AND WELD SPLATTER SHALL BE CAUSE FOR		
CONTACT WITH THE GROUND. STEEL BARS SHALL BE PICKED IN SUCH A WAY AS TO PREVENT OVERSTRESSING. DAMAGE T		
ALL STEEL REINFORCEMENT SHALL BE CAREFULLY HANDLED AN SHALL BE STORED ON SUPPORTS TO KEEP THE STEEL FROM	B	
BECOME CARED OR LOMPT SHALL NOT BE USED.		

PART 3 — EXECUTION	3.01 GENERAL	THE CONSTRUCTION SEQUENCE SHALL BE AS SHOWN ON THE PLANS, IN STAGED LIFTS OR IN ACCORDANCE WITH THE APPROVED SUBMITTAL, UNLESS APPROVED OTHERWISE BY THE DESIGNER. NO EXCAVATIONS STEEPER OR HIGHER THAN THOSE SPECIFIED HEREIN SHALL BE MADE ABOVE OR BELOW THE SOIL NAIL WALL WITHOUT WRITTEN APPROVAL OF THE DESIGNER.
PART	3.01	Ą

36

ASTM A615 / AASHTO M31, GRADE 75 OR ASTM A722 / AASHTO M275, GRADE 150.

BAR COUPLERS SHALL DEVELOP THE FULL ULTIMATE TENSILE STRENGTH OF THE BAR AS CERTIFIED BY THE MANUFACTURER.

# RMC Pacific Materials, 700 Highway 1, Davenport, CA


# SOIL NAIL SPECIFICATIONS CEMENT KILN DUST (CKD) CLOSURE PLANS c/oYasha Saber-Compass Land Grouip 916-825-4997



ıA.w∖
(08.C
<u>*</u>

						OF CACE	SOURCE, COM	эЯгмадА.w
						Exp. 6/30/18	61086 AW JAVUO 1-	077 I X08. P48-842-2
						Z N	STNATJUZNOO	
FOR BID AND CONSTRUCTION	ιo	61/61/20	MM	MCA	MCA	13 /8//	RESOURCE	
LINAL REVIEW	ГЯ	81/10/40	MM	MCA	MCA	PROFESSION .	2MA QA	
DESCRIPTION	ΚΕΛ	DATE	<b>BEVIEW</b>	ИМАЯП	DEZIGN	*		
_								

The reserve a provide a colon and more analysis of the colon analysis of the colon and more analysis of the colon and more analysis of the colon and more a
PRODUCTION ADDRESS COUNTY.  MOUNTAIN WERE STORY OF PROCESS.  MOUNTAIN WERE STORY OF PROCESS.  MOUNTAIN WERE STORY OF THE S
4. By Charles S. Anderson, S. Aller, S. A. S. Anderson, S. A. S. Anderson, S. A. S. Anderson, S. A. S.
A. THE WARD CRESSED IN THIS STEDDY SHALL CORRECT OF THE WARD CRESSED IN THIS STEDDY SHALL CORRECT OF THE WARD CRESSED IN THIS STEDDY SHALL CORRECT OF THE WARD CRESSED IN THIS STEDDY SHALL CORRECT OF THE WARD CRESSED IN THIS STEDDY SHALL CORRECT OF THE WARD CRESSED IN THIS STEDDY SHALL CORRECT OF THE WARD CRESSED IN THE WARD CREEKED IN THE WARD CRESSED IN THE WARD CREEKED IN THE WARD



28

OF

28

SHEET

**E**2

oYasha

# EROSION CONTROL NOTES AND DETAILS CFORNKE KIFN DNZL -978-916 Group 2aper-Compass Materials,

# мор. эрипезявмась. сом 1682-997-927 91089 AW JJAVUO O771x08.0.9 **STNATJUSNO** RESOURCE **ADAMS**





# MCA MCA

ALL TRAFFIC IS PROHIBITED FROM CROSSING DRAINAGE DITCHES, SWALES, AND STREAMS EXCEPT WHERE ALLOWED BY THE CM, AND ONLY USING ROAD PLATES AS APPROVED BY THE CM.

WHEN ADJACENT LAND IS DISTURBED NEAR DRAINAGE DITCHES, INSTALL FIBER ROLLS ALONG UPSTREAM EDGE OF THE NEAREST DITCH AND EROSION CONTROL MATERIALS, AS NEEDED.

4.

რ.

**CHECK DAM** 

**DETAIL - TEMPORARY**NOT TO SCALE

PROFILE ALONG DRAINAGE DITCH

L = THE DISTANCE SUCH THAT POINTS A AND B ARE OF EQUAL ELEVATION

Si

HYDROSEEDING AND REVEGETATION SHALL BE ACCOMPLISHED ON AREAS OF DISTURBANCE, IN ACCORDANCE WITH "REVEGETATION PLAN FOR CLOSURE OF TWO CEMENT KILN DUST (CKD) STORAGE AREAS," BY GREENING ASSOCIATES (2002). REVEGETATION IN RETENTION POND, SEASONAL PONDS AND NORTH POND SHALL BE COMPLETED USING APPROVED PLANT MIX FOR PONDED OR WET AREAS.

INSTALL FIBER ROLLS ALONG INSIDE EDGE OF DRAINAGE DITCHES IMMEDIATELY AFTER SOIL COVER IS CONSTRUCTED

THE COUNTY OF SANTA CRUZ AND OTHER REGULATORY AUTHORITIES MUST BE NOTIFIED BY THE CONTRACTOR AT LEAST ONE (1) WEEK PRIOR TO COMMENCING LAND DISTURBING ACTIVITY.

SLOPES SHALL BE MADE UNIFORM AND FREE OF IRREGULARITIES THAT COULD CONCENTRATE RUNOFF

APPLY TEMPORARY EROSION CONTROL ON DISTURBED AREAS THAT ARE INACTIVE FOR 14 DAYS OR MORE

ACCORDANCE WITH SLOPE LENGTH REQUIREMENTS APPLY LINEAR SEDIMENT CONTROL DEVICES IN

THROUGHOUT

×

×

and

Street Sweeping

SE-7: Stree Vacuuming

SE-5: Fiber Rolls

THROUGHOUT

THROUGHOUT

**BMPs** 

SEDIMENT CONTROL

Sediment/Desilting Basin

SE-2:

Silt Fence

SE-1:

 $\Box$ 

Sediment Trap

SE-3:

**Check Dams** 

SE-4:

THROUGHOUT

×

PERIODIC INSPECTIONS AND MAINTENANCE MUST BE PROVIDED, ESPECIALLY AFTER EACH SIGNIFICANT STORM EVENT INSPECTIONS SHALL INCLUDE OBSERVATION OF THE FOLLOWING:

PONDS FOR DAMS, INLETS/OUTLETS AT NORTH PONDS AND AT SEASONAL

SPANS BETWEEN CONSTRUCTION SEASONS AND EXTENDS INTO THE OCTOBER THROUGH APRIL:

: PLAN APPENDIX E. WATER GENERAL CONSTRUCTION PERMIT, B) PROVIDE WRITTEN INESS PLAN FOR PROJECT WINTERIZING PLANS. ALL IMPROVEMENTS

E LOCATION OF WINTERIZING MEASURES.
ROCK PLACEMENT, EARTH BERMING, COVER AND/OR PROTECTION OF STOCKPILES, CKD AND OTHER ELEMENTS OF THE PROJECT ARE EPOSITION OR EXCESSIVE RUNOFF. PERSUANT TO THE CONDITIONAL APPROVAL LETTER, THE PROJECT WINTERIZING PLANS SHALL INCLUDE BUT MAY NOT BE LIMITED TO:

1. SITE DRAWING SHEETS THAT INDICATE LOCATION OF WINTERIZING MEASURES.

2. TEMPORARY CHECK DAMS, CRUSHED ROCK PLACEMENT, EARTH BERMING, COVER AND/OR PROTECTION OF PROJECT SITE WHERE EARTHWORKS, STOCKPILES, CKD AND OTHER ELEMENTS OF THE PROJECT ARE EXPOSED TO POTENTIAL EROSION, DEPOSITION OR EXCESSIVE RUNOFF.

3. ALSO SEE STORMWATER CONSTRUCTION GENERAL PERMIT AND STORMWATER POLLUTION PREVENTION PLAN

**EROSION AND SEDIMENT CONTROL NOTES** 

ROCK MUST COMPLETELY COVER THE BOTTOM AND SIDES OF THE DITCH

(MIN) NI 9

2H:1V SLOPES

4

EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES (BMPs) SHALL COMPLY WITH THE CALIFORNIA STORMWATER QUALITY ASSOCIATION (CASQA) BEST MANAGEMENT PRACTICES HANDBOOK- CONSTRUCTION (LATEST VERSION). WORK SHALL CONFORM TO THE APPROVED PROJECT SWPPP.

FOR BID AND CONSTRUCTION

INAL REVIEW

DESCRIPTION

 $\Box$ 

12/15/18

1/10/70

ΣЯ

**BEV** 

 $\mathsf{MC} \forall$ 

MCA

DRAWN

**BEAIEM** 

ONTROL MEASURES SEQUENCE OF CONSTRUCTION AND EROSION C IF POSSIBLE, CONSTRUCTION SHALL BE SEQUENCED SUCH THAT CLOSURE, GRADING, AND DRAINAGE CONSTRUCTION WORK IS COMPLETED IN ALL AREAS SO THAT REVEGETATION ACTIVITIES CAN BE COMPLETED BEFORE OCTOBER 1 AS REQUIRED BY WDR. E SITE IN THE FOLLOWING SEQUENCE, UNLESS OTHERWISE APPROVED: CONSTRUCTION ACTIVITIES WILL OCCUR ON TH

**DRAINAGE DITCH** 

SECTION

RIPRAP

<u>m</u>

 $\leq$ 

RUCTION ENTRANCES SHALL BE PROVIDED AT THE LOCATIONS THE OWNER, ENGINEER OR CONSTRUCTION MANAGER (CM). TO THESE ACCESS POINTS. PRIOR TO EARTHWORK, TEMPORARY CONSTI SHOWN ON THE PLANS, OR AS INDICATED BY CONSTRUCTION TRAFFIC SHALL BE LIMITED 1

MINOR CUTTING TH POND, SEASONAL PONDS, CONSTRUCT DRAINAG AND FILLING AS NECE CONSTRUCTION OF TI AND PLACEMENT OF F

SHOWN ON THE COVER, AND WHERE DESIGN GRADES STALLED WHERE AN EROSION CONTROL BLANKET SHALL BE IN EXCEED 15 PERCENT.

6

IMPLEMENTATION

PERIOD

**NECESSARY** 

REQUIRED

DESCRIPTION

 $\bigcirc$ 

**EROSION CONTROL BMPs** 

×

×

EC-2: Preservation of Existing

EC-1: Scheduling

×

EC-3: Hydraulic Mulch

Vegetation

EC-4: Hydroseeding

×

THROUGHOUT

THROUGHOUT

BEST MANAGEMENT PRACTICES
SEE BMP FACT SHEET IN STORMWATER BEST MANAGEMENT PRACTICE HANDBOOK FOR
BMP DETAILS AND INSTALLATION INSTRUCTIONS

# GENERAL NOTES

Oct. 1 – Apr. 15\*

AS NEEDED

×

×

×

EC-7: Geotextiles and Mats

EC-6: Straw Mulch

EC-5: Soil Binders

EC-10: Velocity Dissipation

**Devices** 

EC-11: Slope Drains

EC-8: Wood Mulching

Oct. 1 - Apr. 15\*

Oct. 1 – Apr. 15\*

Apr.

Oct.

15\*

Apr.

 $\overline{\phantom{a}}$ 

Oct.

×

TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES (I.E., FIBER ROLLS) SHALL BE REMOVED WITHIN THIRTY (30) DAYS AFTER FINAL STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED, UNLESS OTHERWISE AUTHORIZED BY LOCAL REGULATORY AUTHORITIES. ONLY BIODEGRADEABLE MATERIALS WILL BE ALLOWED TO STAY.

AVOID THE USE OF PLASTIC IN BMPs

INSPECT AND REPORT: TEMPORARY CHECK DAMS, INLETS/OUTLETS AT NORTH PONDS AND AT SEASONA SEDIMENT ACCUMULATION AND EROSION.
 CHECK FIBER ROLLS FOR UNDERMINING, DETERIORATION, AND BUILDUP/CLOGGING OF SEDIMENT. TAKE CORRECTIVE ACTIONS IMMEDIATELY TO ENSURE CONTINUED FUNCTION.
 CHECK ALL SEEDED AND PLANTED AREAS REGULARLY TO ENSURE THAT A GOOD STAND IS MAINTAINED.

GREENING ASSOCIATES (2002) FOLLOW RECOMMENDATIONS BY

NERS REPRESENTATIVE, THE RWQCB AND APPROPIATE GOVERNING WINTERIZE PROJECT SITE: PROVIDED PROJECT SF WINTER (NON-CONSTRUCTION SEASON) FROM OCT 1. ALSO REFER TO TABLE 1 IN THE CLOSURE PL 2. CONTRACTOR: A) TO FOLLOW THE STORMWA MULTI-SEASON WET WEATHER PREPAREDNE SHALL BE APPROVED BY THE OWNER, OWNEI ENTITIES.

რ

THROUGHOUT

**BMPs** 

TRACKING CONTROL

×

TC-1: Stabilized Construction Entrance/Exit TC-2: Stabilized Construction

 $\triangleleft$ 

Roadway TC-3: Entrance/Outlet Tire

Wash

×

WE-1: Wind Erosion Control

Ps

WIND EROSION BIN

×

Straw Bale Barrier

SE-9:

Sandbag Barrier

SE-8:

Storm Drain Inlet

SE-10:

Protection

THROUGHOUT

THROUGHOUT

3.1.

3.3.

stabilization

\* As needed throughout for temporary or final

# **Coastal Development Permit Findings**

1. That the project is a use allowed in one of the basic zone districts that are listed in LCP Section 13.10.170(D) as consistent with the LCP Land Use Plan designation of the site.

This finding can be made, in that the property is zoned Heavy Industry (M-2-L), a designation which allows industrial uses. The proposed landfill closure project related to the industrial use is an allowed use within the zone district, and the zoning is consistent with the site's Heavy Industry (I) General Plan designation.

2. That the project does not conflict with any existing easement or development restrictions such as public access, utility, or open space easements.

This finding can be made, in that no such easements or restrictions are known to encumber the project site. There are water supply and wastewater lines that cross the project site and these will be located and marked prior to land disturbance.

3. That the project is consistent with the design criteria and special use standards and conditions of this chapter pursuant to SCCC 13.20.130 and 13.20.140 et seq.

This finding can be made, in that the proposed landfill closure is in conformance with the County's certified Local Coastal Program, in that the structure is sited and designed to be visually compatible, in scale with, and integrated with the character of the surrounding lands. The rolling grassland hills north of Highway 1 support sweeping views of open space and grazing fields that surround the former Cement Plant. Implementation of the project will create gentle slopes and all disturbed lands would be revegetated with native plants, and the Cement Plant would return to conditions similar to existing conditions, and views within and of the project area would improve compared to existing conditions. The project site is not located between the shoreline and the first public road and is not identified as a priority acquisition site in the County's Local Coastal Program. Consequently, the proposed project will not interfere with public access to the beach, ocean, or other nearby body of water.

The project site is located in the Davenport Special Community which requires special consideration of visual resources and historic structures associated with the town. The Project area is located in an area that has been designated as the North Coast General Plan Scenic Area in the County General Plan (Santa Cruz County, 1994) (Santa Cruz County GIS Mapping, 2016), and is considered to be an area that supports a scenic vista. The rolling grassland hills north of Highway 1 support sweeping views of open space and grazing fields that surround the former Cement Plant.

The proposed closure activities would be temporary in nature and would occur primarily within the developed footprint of the Cement Plant, including the North CKD Area, which is closed to the public and largely not visible from Highway 1 or scenic vistas. Furthermore, there are no public recreation lands or facilities with views of the Project area. Following project implementation, all disturbed lands would be revegetated with native plants, and the Cement

Plant would return to conditions similar to existing conditions, and views within and of the project area would improve compared to existing conditions. The project would include construction of a permanent relatively impervious shotcrete slope to cover the CKD slope that could potentially be partially visible from limited sections of Highway 1. This is not considered a significant impact due to the limited visibility of the shotcrete cover and the overall improvement in visual quality that will result from the project. Therefore, this impact would be **less than significant.** No mitigation would be required.

4. That the project conforms with the public access, recreation, and visitor-serving policies, standards and maps of the LCP Land Use Plan, including Chapter 2: Section 2.5 and Chapter 7.

This finding can be made, in that the project site is not identified as a priority acquisition site in the County Local Coastal Program and public beach access is available at multiple nearby North Coast beaches.

5. That the project conforms to all other applicable standards of the certified LCP.

This finding can be made, in that the structure is sited and designed to be visually compatible and integrated with the character of the surrounding lands. Additionally, the industrial uses is an allowed uses in the Heavy Industry (M-2-L) zone district, as well as the General Plan and Local Coastal Program land use designation of Heavy Industry (I). Implementation of the project will create gentle slopes and all disturbed lands would be revegetated with native plants, and the Cement Plant would return to conditions similar to existing conditions, and views within and of the project area would improve compared to existing conditions.

6. If the project is located between the nearest through public road and the sea or the shoreline of any body of water located within the Coastal Zone, that the project conforms to the public access and public recreation policies of Chapter 3 of the Coastal Act.

This finding can be made, in that the project site is not located between the shoreline and the first public road. Consequently, the landfill closure will not interfere with public access to the beach, ocean, or any nearby body of water. Further, the project site is not identified as a priority acquisition site in the County Local Coastal Program.

# **Development Permit Findings**

 That the proposed location of the project and the conditions under which it would be operated or maintained will not be detrimental to the health, safety, or welfare of persons residing or working in the neighborhood or the general public, and will not result in inefficient or wasteful use of energy, and will not be materially injurious to properties or improvements in the vicinity.

This finding can be made, in that the project is located in an area designated for industrial uses. Grading and construction will comply with prevailing civil engineering and building technology, the California Building Code, and the County Grading Regulations to ensure the optimum in safety and the conservation of energy and resources.

2. That the proposed location of the project and the conditions under which it would be operated or maintained will be consistent with all pertinent County ordinances and the purpose of the zone district in which the site is located.

This finding can be made, in that the proposed location of the landfill closure project and the conditions under which it would be operated or maintained will be consistent with all pertinent County ordinances and the purpose of the Heavy Industry (M-2-L) zone district as the primary use of the property will be industrial which meets all current site standards for the zone district.

3. That the proposed use is consistent with all elements of the County General Plan and with any specific plan which has been adopted for the area.

This finding can be made, in that the proposed landfill closure project is consistent with the use and density requirements specified for the Heavy Industry (I) land use designation in the County General Plan. The General Plan land use and zoning plans, policies and regulations allow for the remediation of hazardous materials sites and for improvements to water quality (Santa Cruz County General Plan, Chapters 6, 7 and 13, 1994).

The proposed landfill closure project is consistent with General Plan policies 8.5.2 and 8.5.3 regarding compatibility with surrounding uses and the Davenport Special Community. Implementation of the project will create gentle slopes and all disturbed lands would be revegetated with native plants, and the Cement Plant would return to conditions similar to existing conditions, and views within and of the project area would improve compared to existing conditions. The project site is located in the Davenport Special Community which requires special consideration of visual resources and historic structures associated with the town. The Project area is located in an area that has been designated as the North Coast General Plan Scenic Area in the County General Plan (Santa Cruz County, 1994) (Santa Cruz County GIS Mapping, 2016), and is considered to be an area that supports a scenic vista. The rolling grassland hills north of Highway 1 support sweeping views of open space and grazing fields that surround the former Cement Plant.

The proposed closure activities would be temporary in nature and would occur primarily within the developed footprint of the Cement Plant, including the North CKD Area, which is closed to the public and largely not visible from Highway 1 or scenic vistas. Furthermore, there are no public recreation lands or facilities with views of the Project area. Following project implementation, all disturbed lands would be revegetated with native plants, and the Cement Plant would return to conditions similar to existing conditions, and views within and of the project area would improve compared to existing conditions. The project would include construction of a permanent relatively impervious shotcrete slope to cover the CKD slope that could potentially be partially visible from limited sections of Highway 1. This is not considered a significant impact due to the limited visibility of the shotcrete cover and the overall improvement in visual quality that will result from the project. Therefore, this impact would be **less than significant**. No mitigation would be required.

A specific plan has not been adopted for this portion of the County.

4. That the proposed use will not overload utilities, and will not generate more than the acceptable level of traffic on the streets in the vicinity.

This finding can be made, in that the proposed landfill closure project will occur on an existing industrial site. The expected level of traffic generated by the proposed project is anticipated to be 60 trips per day (120 round trips) on a temporary basis during project construction and importation of fill material. This temporary increase in traffic will not adversely impact existing roads or intersections in the surrounding area. There will be no permanent increase in traffic as a result of the project.

5. That the proposed project will complement and harmonize with the existing and proposed land uses in the vicinity and will be compatible with the physical design aspects, land use intensities, and dwelling unit densities of the neighborhood.

This finding can be made, in that Implementation of the project will create gentle slopes and all disturbed lands would be revegetated with native plants, and the Cement Plant would return to conditions similar to existing conditions, and views within and of the project area would improve compared to existing conditions. The project site is located in the Davenport Special Community which requires special consideration of visual resources and historic structures associated with the town. The project would include construction of a permanent relatively impervious shotcrete slope to cover the CKD slope that could potentially be partially visible from limited sections of Highway 1. This is not considered a significant impact due to the limited visibility of the shotcrete cover and the overall improvement in visual quality that will result from the project. Therefore, this impact would be less than significant. No mitigation would be required.

6. The proposed development project is consistent with the Design Standards and Guidelines (sections 13.11.070 through 13.11.076), and any other applicable requirements of this chapter.

This finding is not applicable.

# **Riparian Exception Findings**

1. That there are special circumstances or conditions affecting the property;

There are special circumstances or conditions affecting the property. The seasonal wetland that would be permanently lost during CKD landfill closure is located within the boundary of the existing CKD landfill atop CKD materials historically placed as fill. Grading of this area would be necessary to install the LLDPE liner/cap system and to direct surface and subsurface water away from the CKD landfill in order to prevent pooling on top of the liner/cap system and avoid potential water quality impacts to No-Name Creek, groundwater, and the Pacific Ocean. Proposed work within the aquatic features (ponds) is for the purpose of improving drainage, water quality and/or enhancing habitat for CRLF. The loss of the seasonal wetland would be fully mitigated through implementation of conditions of approval, including obtaining and implementing permits and conditions imposed by the U.S. Army Corps of Engineers.

2. That the exception is necessary for the proper design and function of some permitted or existing activity on the property;

The riparian exception is necessary for the proper design and function of the Closure Plan activities proposed for the existing CKD landfill, a permitted activity.

3. That the granting of the exception will not be detrimental to the public welfare or injurious to other property downstream or in the area in which the project is located;

The granting of the riparian exception will not be detrimental to the public welfare or injurious to other property downstream or in the area in which the Project is located; proposed Closure Plan activities have been designed for the purpose of protecting water quality in compliance with WDR No. R3-2018-0001, conditionally approved by the Water Board.

4. That the granting of the exception, in the Coastal Zone, will not reduce or adversely impact the riparian corridor, and there is no feasible less environmentally damaging alternative; and

The granting of the exception, in the Coastal Zone, would not reduce or adversely impact the riparian corridor; no impacts to the riparian corridor are anticipated as a result of the proposed Project and there is no feasible less environmentally damaging alternative.

5. That the granting of the exception is in accordance with the purpose of this chapter, and with the objectives of the General Plan and elements thereof, and the Local Coastal Program Land Use Plan.

The granting of the exception is in accordance with the purpose of the Riparian Ordinance. The proposed Project would ultimately help preserve, protect, and restore the riparian corridor and wetlands within the immediate area, including for the protection and enhancement of wildlife

North CKD Landfill Closure Project Planning Commission Staff Report

habitat; water quality; aquatic habitat; and open space, as well as the other values listed in the purpose of the Riparian Ordinance. The project has been designed for the 1000-year (24-hour) storm event; water quality protections and erosion control measures have also been included in the Closure Plan designs and associated documentation (ARC 2018 and ARC 2019a).

# **Conditions of Approval**

Exhibit B: Project plans, prepared by Adams Resource Consultants, dated 12/12/2019.

- I. This permit authorizes the construction of the North CKD Area landfill closure as indicated on the approved Project plans for this permit (Exhibit B). This approval does not confer legal status on any existing structure(s) or existing use(s) on the subject property that are not specifically authorized by this permit. Prior to exercising any rights granted by this permit including, without limitation, any construction or site disturbance, the applicant/owner shall:
  - A. Sign, date, and return to the Planning Department one copy of the approval to indicate acceptance and agreement with the conditions thereof.
  - B. Obtain a Building Permit from the Santa Cruz County Building Official prior to construction of the soil nail wall or retention pond wall.
    - 1. Any outstanding balance due to the Planning Department must be paid prior to making a Building Permit application. Applications for Building Permits will not be accepted or processed while there is an outstanding balance due.
  - C. Obtain a Grading Permit from the Santa Cruz County Building Official.
    - 1. Any outstanding balance due to the Planning Department must be paid prior to making a Building Permit application. Applications for Building Permits will not be accepted or processed while there is an outstanding balance due.
  - D. Obtain an Encroachment Permit from the Department of Public Works for all offsite work performed in the County road right-of-way.
- II. Prior to issuance of a Building Permit or Grading Permit the applicant/owner shall:
  - A. Submit final grading and retaining wall plans for review and approval by the Planning Department. The final plans shall be in substantial compliance with the plans marked Exhibit "B" on file with the Planning Department. Any changes from the approved Exhibit "B" for this development permit on the plans submitted for the Building Permit or Grading Permit must be clearly called out and labeled by standard architectural methods to indicate such changes. Any changes that are not properly called out and labeled will not be authorized by any Building Permit that is issued for the proposed development.

- B. Comply with all requirements of the letter dated July 20, 2020 accepting the geotechnical report for the project as repeated below.
  - 1. For County records, please revise page 5 of the Response to Comments on Design Analyses for Soil Nail Wall Davenport Cement Plant Santa Cruz County, California dated 2 July 2020, to read 5 inches instead of 5 cm as outlined in the 6 July 2020 email from Wayne Adams, PE.
  - 2. Public access to the project site area is to be restricted. Monitoring and maintenance programs for the soil nail wall as well as the site drainage system are required to be implemented in accordance with project plans and specifications.
  - 3. All project design and construction shall comply with the recommendations of the subject geotechnical investigation report.
- III. Prior to any site disturbance or physical construction on the subject property the following condition(s) shall be met:
  - A. Pre-Construction Meeting: In order to ensure that the mitigation measures are communicated to the various parties responsible for constructing the project, prior to any disturbance on the property the applicant shall convene a preconstruction meeting on the site. The following parties shall attend: the applicant, grading contractor supervisor, the project biologist, and Santa Cruz County Planning Department staff.
  - B. Background information obtained from the air quality monitoring network shall be submitted to Monterey Bay Air Resources District and the Planning Department.
  - C. Submit a copy of the Storm Water Pollution Prevention Plan as required by the Regional Water Quality Control Board Waste Discharge Order.
  - D. Submit documentation of authorization from the United States Army Corps of Engineers (USACE) for all project activities within their jurisdiction including the Biological Opinion from the United States Fish and Wildlife Service (USFWS).
  - E. Submit documentation of authorization from the California Department of Fish and Wildlife (CDFW) for all project activities within their jurisdiction.
  - F. Submit a copy of the Mitigation and Management Plan as approved by USACE and CDFW.
- IV. During construction of the project the following conditions shall be met:

- A. All required mitigation measures required prior to and during construction to protect biological and cultural resources shall be implemented.
- B. All best management practices and requirements of technical reports for the project intended to prevent water quality impacts shall be implemented at all times during construction.
- C. All best management practices and monitoring requirements contained in the Dust Management Plan intended to prevent air quality impacts shall be implemented at all times during construction.
- D. A contact person shall be designated to respond to any complaints related to project construction activities, including but not limited to air quality impacts. The contact information shall be posted at the entrance to the facility and provided through other community networks.
- E. All trucks shall access the site from Highway 1 using the main cement plant entrance or by exiting Highway 1 north of New Town to access Warnella Road. Trucking shall not occur on Cement Plant Road between Davenport and New Town.
- F. Information obtained from the air quality monitoring network shall be submitted on a weekly basis to the Monterey Bay Air Resources District and the Planning Department.
- V. All construction shall be performed according to the approved plans for the Building Permit and Grading Permit. Prior to final building and grading inspection, the applicant/owner must meet the following conditions:
  - A. All required mitigation measures shall be implemented construction, as specified in the Mitigation Monitoring and Reporting Program attached to these conditions.
  - B. All site improvements shown on the final approved Building Permit and Grading Permit plans shall be installed.
  - C. All inspections required by the building permit shall be completed to the satisfaction of the County Building Official.
  - D. The project must comply with all recommendations of the approved soils reports.
  - E. The project applicant is responsible for the entire drainage pathway from their site to the ocean discharge including inspection, maintenance, repair, replacement,

capacity, condition and water quality. The drainage pathway crosses Cement Plant Road (county-maintained road), the railroad, and Highway 1.

- F. The sanitary sewer line within Tunnel B shall be identified as to ownership and the locations is serves. If the line is still in use, it shall be removed from the tunnel and relocated.
- G. Pursuant to Sections 16.40.040 and 16.42.080 of the County Code, if at any time during site preparation, excavation, or other ground disturbance associated with this development, any artifact or other evidence of an historic archaeological resource or a Native American cultural site is discovered, the responsible persons shall immediately cease and desist from all further site excavation and notify the Sheriff-Coroner if the discovery contains human remains, or the Planning Director if the discovery contains no human remains. The procedures established in Sections 16.40.040 and 16.42.080, shall be observed.

# VI. Operational Conditions

A. In the event that future County inspections of the subject property disclose noncompliance with any Conditions of this approval or any violation of the County Code, the owner shall pay to the County the full cost of such County inspections, including any follow-up inspections and/or necessary enforcement actions, up to and including permit revocation.

### VII. Indemnification

The applicant/owner shall indemnify, defend with counsel approved by the COUNTY, and hold harmless the COUNTY, its officers, employees, and agents from and against any claim (including reasonable attorney's fees, expert fees, and all other costs and fees of litigation), against the COUNTY, its officers, employees, and agents arising out of or in connection to this development approval or any subsequent amendment of this development approval which is requested by the applicant/owner, regardless of the COUNTY's passive negligence, but excepting such loss or damage which is caused by the sole active negligence or willful misconduct of the COUNTY. Should the COUNTY in its sole discretion find the applicant's/owner's legal counsel unacceptable, then the applicant/owner shall reimburse the COUNTY its costs of defense, including without limitation reasonable attorney's fees, expert fees, and all other costs and fees of litigation. The applicant/owner shall promptly pay any final judgment rendered against the COUNTY (and its officers, employees, and agents) covered by this indemnity obligation. It is expressly understood and agreed that the foregoing provisions are intended to be as broad and inclusive as is permitted by the law of the State of California and will survive termination of this development approval.

- A. The COUNTY shall promptly notify the applicant/owner of any claim, action, or proceeding against which the COUNTY seeks to be defended, indemnified, or held harmless. The COUNTY shall cooperate fully in such defense.
- B. Nothing contained herein shall prohibit the COUNTY from participating in the defense of any claim, action, or proceeding if both of the following occur:
  - 1. COUNTY bears its own attorney's fees and costs; and
  - 2. COUNTY defends the action in good faith.
- C. <u>Settlement</u>. The applicant/owner shall not be required to pay or perform any settlement unless such applicant/owner has approved the settlement. When representing the COUNTY, the applicant/owner shall not enter into any stipulation or settlement modifying or affecting the interpretation or validity of any of the terms or conditions of the development approval without the prior written consent of the COUNTY.
- D. <u>Successors Bound</u>. The "applicant/owner" shall include the applicant and/or the owner and the successor'(s) in interest, transferee(s), and assign(s) of the applicant and/or the owner.

Minor variations to this permit which do not affect the overall concept or density may be approved by the Planning Director at the request of the applicant or staff in accordance with Chapter 18.10 of the County Code.

Please note: This permit expires three years from the effective date listed below unless a building permit (or permits) and a grading permit are obtained for the retaining walls and earthwork described in the development permit (does not include demolition, temporary power pole or other site preparation permits, or accessory structures unless these are the primary subject of the development permit). Failure to exercise the building and grading permits and to complete all of the construction under the building permit and grading under the grading permit, resulting in the expiration of the building and grading permits, will void the development permit, unless there are special circumstances as determined by the Planning Director.

Approval Date:	-	
Effective Date:		
Expiration Date:		

Appeals: Any property owner, or other person aggrieved, or any other person whose interests are adversely affected by any act or determination of the Planning Commission, may appeal the act or determination to the Board of Supervisors in accordance with chapter 18.10 of the Santa Cruz County Code.

# County of Santa Cruz

**PLANNING DEPARTMENT**701 OCEAN STREET, 4<sup>TH</sup> FLOOR, SANTA CRUZ, CA 95060 (831) 454-2580 FAX: (831) 454-2131 TDD: (831) 454-2123

# MITIGATION MONITORING AND REPORTING PROGRAM for Application No. 28372

No.	Mitigation Measures	Responsibility for Compliance	Method of Compliance	Timing of Compliance
Biologi	Biological Resources			
BIO-1	Conduct monarch butterfly surveys. During each proposed construction year, a qualified biologist will conduct autumnal and winter roost surveys, if work is scheduled to occur during monarch roost season (September through March). Surveys will occur beginning September 1. If no monarchs are detected, surveys will occur on a weekly basis until construction concludes for the year or until November 30 (when stable winter aggregates will have formed). If autumnal or winter roosts are present, the biologist will determine the protective buffer necessary to avoid impacts to the roost and develop a site-specific monarch butterfly roost management plan following the guidelines described in Xerces Society 2017.	Applicant	Compliance monitoring by the County Planning Department	Autumnal and winter roost surveys during each construction year
BIO-2	<ul> <li>Implement Construction Related Protective Measures for California Red Legged Frog. The following protective measures for CRLF will be implemented for the duration of construction activities: <ul> <li>Prior to the initiation of construction activities, a USFWS- and CDFW-approved biologist will prepare a construction monitoring plan that identifies all areas to be protected with exclusion fencing on a 1:1500 scale map (or similar scale determined to be practicable), and all areas requiring monitoring by a USFWS- and CDFW-approved biologist.</li> <li>Prior to the initiation of construction activities, a USFWS-approved biologist will conduct an environmental training for all construction personnel. The training will include a description of CRLF and its habitat, measures to protect CRLF, and other sensitive wildlife species known or with potential to occur in the Project area and surroundings (sensitive and native nesting bird species, potential roosting bats species, and potential San Francisco dusky-footed woodrat).</li> <li>If it is determined through consultation with USFWS that exclusion fencing (solid silt fencing) is necessary for minimizing impacts to CRLF, prior to the initiation of construction activities, the construction contractor will inspect the fence will be maintained in working order for the duration of construction activities. The USFWS-approved biologist or designated trained construction monitor shall inspect the fence will allow for wildlife passage across the Project area at intervals to be determined in conjunction with USFWS and CDFW.</li> <li>Construction activities will take place during the dry season and before the first rain of the season, especially vegetation removal and work in or near aquatic features, including ditch wetlands. Work shall not take place at night or during rain events when special-status</li> </ul> </li> </ul>	Applicant	Compliance monitoring by the County Planning Department	Issuance of Biological Opinion by USFWS, protective measures in place, and daily monitoring during construction activities in areas with regulated waters and habitats
	amphibians are generally more active. The Project contractor will consult weather forecasts from the National Weather Service at least 72 hours prior to performing work.			

O N		Mitigation Measures	Responsibility for Compliance	Method of Compliance	Timing of Compliance
	•	Ground-disturbing activities in upland areas including clearing, grubbing, and grading shall not occur between November 1 and March 31, unless authorized by the USFWS, because that is the time period when CRLF are most likely to be moving through upland areas.			
	•	If the project seeks and obtains winter grading approval from the County and disturbance of upland areas between November 1 and March 31 is authorized by USFWS, measures to prevent CRLF from entering the Project area shall be implemented. These measures shall include installation of exclusion fencing and all other recommendations and conditions provided through consultation with USFWS.			
	•	Prior to commencement of construction, a Service-approved biologist(s) will identify suitable relocation sites for CRLF. If it is determined that individual CRLF must be relocated to avoid harm, a plan shall be developed in consultation with USFWS to relocate individual CRLF prior to initiation of disturbance in aquatic habitat. The biologist shall be given enough time to move the animals from the work site before ground disturbance is initiated.			
	•	A Service-approved biologist(s) shall be onsite during all activities that may result in take of the CRLF, to be determined at the discretion of the Service-approved biologist in consultation with USFWS. The approved biologist shall have the authority to stop work that may result in the "take" of a special-status species. If a CRLF is encountered during Project construction, the approved biologist shall be given enough time to move the animals from the work site to a designated relocation site.			
	•	The approved biologist will have the authority to stop work that may result in the "take" of a special-status species.			
	•	Capturing and handling CRLF is not permitted unless a project-specific Take Permit has been obtained from USFWS.			
	•	Only USFWS-approved biologists shall participate in activities associated with surveying, capturing, handling, and monitoring of CRLF.			
	•	The USFWS-approved biologist or construction monitor will check under all equipment for wildlife before use. If any special-status wildlife is observed under equipment or within the work area, the approved biologist will be permitted to handle and relocate it.			
	•	At the end of each work day, excavations will be secured with a cover, or a ramp installed to prevent wildlife entrapment.			
	•	All trenches, pipes, culverts or similar structures will be inspected for animals prior to burying, capping, moving, or filling the structures.			
BIO-3	Conduct I Species. T	Conduct Preconstruction Surveys and Construction Related Protective Measures for Avian Species. The following protective measures for avian species will be implemented for the duration of construction activities:	Applicant	Compliance monitoring by the County Planning	Prior to initiation of any phase of construction activity
	The a practic bird se biolog	The avian breeding season occurs between February 1 and September 15. To the greatest extent practicable, initiate non-native tree and ruderal vegetation removal activities outside of the breeding bird season to avoid direct harm or mortality to potential nesting bird species and other sensitive biological resources.		Department	or two-week lapse in construction between February 1 and September 15
	• For all a peric	For all Project activities initiated during the breeding bird season, or if construction activities lapse for a period of two weeks or more during breeding bird season, a qualified biologist will conduct a breeding bird survey for nesting birds, including raptors. Surveys will be conducted within 15 days			

No.	Mitigation Measures	Responsibility for Compliance	Method of Compliance	Timing of Compliance
	prior to beginning Project activities and will include all work, staging, and access areas and a minimum buffer radius of 150 meters (or more as determined by the resource agencies). The survey will include potential habitat for raptors and sensitive and common nesting avian species known to occur within the Biological Study Area [arroyo willow riparian scrub, coastal scrub, eucalyptus grove (adjacent to the Seasonal Ponds), other non-native forest (adjacent to the Retention Pond), large cypress/eucalyptus groves, non-native grassland, and the Pre-heater Tower and Coal Mill buildings].			
	<ul> <li>If no nesting sensitive or common avian species are observed during breeding bird surveys no additional measures will be required.</li> </ul>			
	If nesting birds are observed within vegetation proposed for removal, postpone vegetation removal activities until young have fledged to avoid direct harm or mortality of nesting birds.			
	<ul> <li>Sensitive bird species, if nesting in or near the Project area, will be given special consideration and may require additional protective measures as determined through consultation with the relevant agency (USFWS or CDFW), such as protective buffers recommended in PG&amp;E et al. 2015:</li> </ul>			
	<ul> <li>American peregrine falcon: 150 meters (500 feet)</li> <li>Northern harrier, white-tailed kite, and other raptors: 90 meters (300 feet).</li> </ul>			
	<ul> <li>Olive-sided flycatcher and grasshopper sparrow: 25 meters (75 feet)</li> <li>Allen's hummingbird: 15 meters (50 feet).</li> </ul>			
	• If the biologist determines that a smaller avoidance buffer will provide adequate protection for nesting birds, a proposal for alternative avoidance/protective measures, potentially including a smaller avoidance buffer and construction monitoring, may be submitted to USFWS and CDFW for review and approval prior to removal of vegetation, grading activity, or other use of heavy equipment.			
	<ul> <li>If removal of vegetation, grading activity, or other use of heavy equipment stops for more than two weeks during the nesting season (February 1st - August 31st) a new survey shall be conducted prior to re-commencement of construction.</li> </ul>			
BIO-4	Implement Construction Related Protective Measures for San Francisco dusky-footed woodrat.  The following protective measures for San Francisco dusky-footed woodrat will be implemented for the duration of construction activities:	Applicant	Compliance monitoring by the County Planning	Prior to initiation of construction activities
	<ul> <li>Within one month prior to the onset of construction activities, a CDFW qualified biologist will conduct a preconstruction survey for woodrat houses, and clearly flag all houses within the construction impact area and immediate surroundings.</li> </ul>		Department	
	The construction contractor will avoid woodrat houses to the greatest extent feasible by installing a minimum 10-foot (preferably 25-foot) buffer with silt fencing or other material that will prohibit encroachment. If this buffer and avoidance is not feasible, the qualified biologist will allow encroachment into the buffer, but preserve microhabitat conditions such as shade, cover and adjacent food sources.			
	<ul> <li>If avoidance of woodrat houses is not possible, in coordination with CDFW and County         Environmental Planning staff, a qualified biologist will develop and implement a San Francisco         dusky-footed woodrat Relocation Plan and the following conditions or conditions of a CDFW         agreement shall be adhered to:</li> </ul>			
	<ul> <li>Prior to house disturbance, the biologist shall obtain from CDFW a scientific collection permit for the trapping of the dusky-footed wood rats.</li> </ul>			

No.	Mitigation Measures		Responsibility for Compliance	Method of Compliance	Timing of Compliance
	<ul> <li>Houses shall be disturbed/dismantled only during the non-breeding season, generally between late summer and early fall, as determined in consultation with the project biologist and CDFW</li> </ul>	n, generally project biologist			
	<ul> <li>If trapping is utilized as part of the relocation plan, prior to house disturbance, wood rats shall be trapped at dusk of the night set for relocation of the nest(s).</li> </ul>	nce, wood rats			
	Any existing house that may be disturbed by construction activities shall be mostly dismantled and the material spread in the vicinity of identified house relocation site(s).	e mostly ation site(s).			
	o In order to avoid the potential health effects associated with handling rodents and their milieu, all workers involved in the handling of the wood rats or the house materials should wear protective gear to prevent inhalation of contaminant particulates, contact with conjunctiva (eyes), and protection against flea bites; a respirator, eye protection and skin protection should all be used.	nts and their naterials should itact with ection and skin			
	Dismantling shall be done by hand, allowing any animals not trapped to escape either along existing woodrat trails or toward other available habitat.	scape either			
	<ul> <li>If a litter of young is found or suspected, house and nest material shall be replaced, and the house left alone for 2-3 weeks before a recheck to verify that young are capable of independent survival before proceeding with house dismantling.</li> </ul>	replaced, and the			
	<ul> <li>Woody debris shall be collected from the area and relocated houses shall be partially constructed in an area determined by the qualified biologist to be both suitable for the wood rats and far enough away from the construction activities that they will not be impacted.</li> </ul>	be partially able for the wood be impacted.			
	<ul> <li>If trapping is utilized as part of the relocation plan, rats that were collected at dusk shall be released hours before dawn near the newly constructed nests to allow time for rats to find refuge.</li> </ul>	at dusk shall be e for rats to find			
BIO-5	Implement Construction Related Protective Measures for Bats. The following protective measures for bats will be implemented throughout the duration of construction activities.		Applicant	Compliance monitoring by the	Prior to initiation of any phase of
	To the greatest extent feasible, conduct limbing/tree removal operations between September 15 and November 1 to avoid bat maternity roosts and winter hibernacula, as well as other sensitive biological resources.	september 15 and sensitive		County Planning Department	construction
	To avoid impacts to potential roosting bats, a qualified biologist shall conduct a pre-construction survey for bats during all months as follows:	-construction			
		any e-roosting bats, e-roosting bats, is are present. es. If roosting e exclusion sible, exclusion ber 1) to avoid n CDFW is			
	o If established maternity colonies are found, in coordination with CDFW, a buffer will be established around the colony to protect pre-volant young from construction disturbances until the young can fly; or implement other measures acceptable to CDFW.	buffer will be on disturbances '			

No.	Mitigation Measures	Responsibility for Compliance	Method of Compliance	Timing of Compliance
	<ul> <li>If a tree is determined not to be an active roost site for roosting bats, it may be immediately limbed or removed as follows:</li> </ul>			
	• If foliage roosting bats are determined to be present, limbs will be lowered, inspected for bats by a bat biologist, and chipped immediately or moved to a dump site. Alternately, limbs may be lowered and left on the ground until the following day, when they can be chipped or moved to a dump site. No logs or tree sections will be dropped on downed limbs or limb piles that have not been in place since the previous day.			
	<ul> <li>If the tree is not limbed or removed within four days of the survey, the survey efforts shall be repeated.</li> </ul>			
BIO-6	Implement Construction Related Protective And Replacement Measures For Coastal Scrub Habitat. The following protective and replacement measures for coastal scrub habitat will be implemented throughout the duration of construction activities.	Applicant	Compliance monitoring by the County Planning	Approval of Mitigation and Management Plan,
	<ul> <li>Construction equipment will be staged in ruderal and developed areas only and, to the greatest extent feasible, equipment will access the ditch system from the south side in ruderal and developed habitat.</li> </ul>		Department	and protective measures in place prior to initiation of
	<ul> <li>Coastal scrub habitat will be fenced off to prevent encroachment from construction related equipment and materials, and the construction footprint adjacent to this habitat will be minimized to the greatest extent practicable.</li> </ul>			activities in areas with regulated waters and habitats;
	<ul> <li>Permanent impacts to coastal scrub will be mitigated through replacement at a 3:1 ratio in suitable upland locations east of the Seasonal Ponds, east of the North Pond, and along the top of the embankment to No-Name Creek where poison hemlock currently dominates the area. Plantings will consist of locally-sourced native coastal scrub plantings (such as coastal sage brush, coffeeberry, coyote bush, California blackberry, California wild rose, and lizard tail) in accordance with the Mitigation and Management Plan required by Mitigation Measure BIO-8.</li> </ul>			Revegetation prior to project completion; Post project monitoring
	<ul> <li>Where temporary impacts to coastal scrub occur, the area will be allowed to resprout from stumps and roots and will be re-vegetated, as needed, with locally-sourced native coastal scrub plantings (as listed above for permanent impacts) in accordance with the Mitigation and Management Plan required by Mitigation Measure BIO-8. Adjacent non- native grassland and ruderal habitats may also be planted with coastal scrub vegetation, where appropriate, to support the revegetation of this habitat.</li> </ul>			

No.	Mitigation Measures	Responsibility for Compliance	Method of Compliance	Timing of Compliance
BIO-7	<ul> <li>Implement Construction Related Protective and Replacement Measures for Arroyo Willow Scrub Habitat. The following protective and replacement measures for arroyo scrub habitat will be implemented throughout the duration of construction activities.</li> <li>To the greatest extent feasible, minimize removal of arroyo willow scrub and protect the remaining habitat from construction activities through installation of protective fencing.</li> <li>At a minimum, the Project will result in no net loss of arroyo willow scrub habitat. Replace arroyo willow scrub at a ratio to be determined by the County and other state and federal agencies in accordance with the Mitigation and Management Plan required by Mitigation Measure BIO-8.</li> <li>To mitigate for permanent impacts, arroyo willow pole cuttings will be planted in other suitable locations within and immediately adjacent to the Project area as described in the Mitigation and Management Plan: along the southwestern comer of the North Pond, at the outfall structure from the North Pond bypass pipe to No-Name Creek, on the northem side of the proposed mitigation seasonal willow pond in the remediated coal storage area, and along the western edge of the "frog swale", a feature located west of the wastewater treatment pond immediately west of the Project boundary area within CEMEX property.</li> <li>Where temporary impacts to arroyo willow scrub occur, the area will be allowed to resprout from summes and roots, through natural recruitment, and will be re-vegetated, as needed, with locally-sourced willow pole cuttings in accordance with the Mitigation and Management Plan required by Mitigation Measure BIO-8.</li> </ul>	Applicant	Compliance monitoring by the County Planning Department	Approval of Mitigation and Management Plan, and protective measures in place prior to initiation of construction activities in areas with regulated waters and habitats; Revegetation prior to project completion; Post project monitoring
BIO-8	<ul> <li>Implement Protective and Replacement Actions for Jurisdictional Wetlands And Waters of The U.S. Implementation of the following measures would minimize potential temporary and permanent impacts on jurisdictional wetlands and waters of the U.S.</li> <li>Avoid or minimize disturbance to wetlands, aquatic features (ponds), as well as to other sensitive habitats (coastal scrub, arroyo willow scrub, and edge habitats) through the installation of construction fencing around staging and work areas, and access routes, outside of which no activities would occur and no materials would be stored. The construction fencing will be placed in accordance with the stages of work being implemented in specific areas throughout the Biological Study Area, as feasible, to allow a corridor for wildlife movement along the southern boundary of the Project area.</li> <li>Where feasible, avoid grubbing and construction within 100 feet of the edge of wetlands, ponds, and No-Name Creek, per the County of Santa Cruz General Plan/LCP and Sensitive Habitats Ordinance.</li> <li>Restrict access roads that must enter into aquatic features to one location, and minimize the area of impact that results from these access roads to the greatest extent feasible.</li> <li>Construct a replacement seasonal wetland at a ratio of 3:1, as included in the Closure Plan. A shallow mitigation feature of approximately 0.7 acre would be excavated along (outside of) the eastern fringe of the Seasonal Ponds, planted mix locally sourced native wetland vegetation, including, but not limited to, a seed mix composed of California oat grass, Mediterranean barley, and seep monkey flower; plugs of spreading rush and Pacific rush; and stakes of arroyo willow, where applicable.</li> </ul>	Applicant	Compliance monitoring by the County Planning Department	Authorization by USACE, approval of Mitigation and Management Plan, and protective measures in place prior to initiation of construction activities in areas with regulated waters and habitats; Wetland mitigation and revegetation prior to project completion; Post project monitoring

	No.	Mitigation Measures	Responsibility for Compliance	Method of Compliance	Timing of Compliance
		• As detailed in the Mitigation and Management Plan, to mitigate for permanent impacts to aquatic habitat in the Seasonal Ponds, develop a replacement seasonal willow pond in the coal storage area north of Retention Pond. To mitigate for permanent impacts to riparian and poison oak wetlands, the northern portion of the mitigation pond will be planted with riparian wetland plantings and willow pole cuttings. Container plants and/or willow pole cuttings will also be planted along the northern margin of the Retention Pond, in the wetland fringe east of the Seasonal Ponds, along the southwestern corner of the North Pond, at the outfall structure from the North Pond Bypass Pipe to No-Name Creek, and along the western edge of the "frog swale", a feature located west of the wastewater treatment pond immediately west of the project boundary area within CEMEX property. In addition to arroyo willow pole cuttings, plantings will consist of locally-sourced native riparian plantings including red elderberry, beaked hazelnut, California blackberry, and coffeeberry, as well as those wetland species listed above. Develop and implement a Mitigation and Management Plan that will include the following:			
		_ ,•			
Producing long-term quantitative and documenting the ability of the					
		Producing long-term quantitative and documenting the ability of the			

No.	Mitigation Measures	Responsibility for Compliance	Method of Compliance	Timing of Compliance
	criteria.  5-year management plan for maintenance and monitoring of restored areas to maintain 100% survival of installed container stock in year 1, 90% survival rate in year 2, and at least 80% survival in years 3-5. Replacement plants shall be installed as needed during the monitoring period to meet survival rates. Annual reports shall be submitted to the County Planning Department by December 31 of each monitoring year.  O Developing adaptive management strategies to ensure the long-term viability of mitigation areas.  Developing strategies to protect remaining wetland and aquatic/riverine habitats.			
Cultura	Cultural Resources			
CR-1	<b>Conduct Awareness Training and Stop Work in the Event of Unexpected Occurrence of Cultural or Historic Resources During Construction.</b> Prior to the onset of construction activities at the Cement Plant, a qualified archaeologist (who meets the Secretary of the Interior's Professional Qualifications Standards as promulgated in 36 CFR 61 and who has experience with precontact, historic period, and tribal resources) shall be present at the construction site to conduct awareness training. The aware training will inform the construction crew of historic activities that may result in the presence of cultural or historic resources throughout the Project area, and will provide photographic examples of the types of resources that may be found.  Pursuant to Sections 16.40.040 and 16.42.080 of the County Code, if at any time during site preparation, excavation, or other ground disturbance associated with this development, any artifact or other evidence of an historic archaeological resource or a Native American cultural site is discovered, the responsible persons shall immediately cease and desist from all further site excavation and notify the Sheriff-Coroner if the discovery contains human remains, or the Planning Director if the discovery contains no human remains. The procedures established in Sections 16.40.040 and 16.42.080, shall be observed. If previously unknown cultural or historic resources are encountered, an archaeological report must be prepared by a archaeological sind evelopment approval. The archaeological way included extending the materials encountered and development approval. The archaeological way fake place except as authorized by an archaeological sind evelopment approval. The archaeological such development experience of action. Such actions may include identifying alternative construction methodologies or the placement of Project materials/structures in alternative locations, with the ultimate goal of providing the ability for the project to move forward while protecting the resources in place.	Applicant	Compliance monitoring by the County Planning Department	Prior to initiation of construction activities and if cultural or historic resource discovered during construction
CR-2	Stop Work in the Event of Unexpected Occurrence of Human Remains During Construction. If human remains and/or associated/or unassociated funerary objects are discovered during ground disturbing activities, construction crews will stop work and immediately notify the Santa Cruz County Coroner, the Planning Director, and a qualified archeologist, in accordance with applicable local and State laws. In the event that the Coroner determines that the human remains are Native American, the County will notify the Native American Heritage Commission (NAHC) according to the requirements in PRC Section 5097.98. NAHC will appoint a Most Likely Descendent (MLD). A qualified archeologist, County and MLD will make all reasonable efforts to develop an agreement for the treatment, with appropriate dignity, of any human remains and associated or unassociated funerary objects (CEQA Guidelines Section 15064.5[d]). The agreement will take into consideration the appropriate preservation measures, with the	Applicant	Compliance monitoring by the County Planning Department	If human remains discovered during construction

No.	Mitigation Measures	Responsibility or Compliance	Method of Compliance	Timing of Compliance
	preference to preserve all resources intact and in place. The County will work with RMC Pacific Materials, LLC to develop an alternative pipeline route, or excavate, remove, record, analyze, take custody of, and finally respectfully dispose of the human remains and associated or unassociated funerary objects. The PRC allows 48 hours to reach agreement on these matters.			

Geolo	Geology and Soils				
GEO-1	Stop Work in the Event of Unexpected Paleontological Resources or Unique Geological Features   Applicant	licant	Compliance	If paleontological	
	During Construction. If paleontological resources or unique geologic features are discovered during soil-		monitoring by the	resources or unique	
	disturbing activities, the construction crew will stop work and immediately notify the County Planning		County Planning	geological features	
	Director and a qualified paleontologist. The procedures established in Santa Cruz County Code Section		Department	discovered during	
	16.44.070, shall be observed. A paleontological resource or fossil is any evidence of ancient life preserved			construction	
	in a geologic context (e.g., leaves, bones, teeth, shells). A paleontologist will inspect the discovery and				
	determine whether further investigation is required. If the discovery can be avoided, no further mitigation				
	will be required. If the resource cannot be avoided, the qualified paleontologist will evaluate the resource				
	and determine whether it meets the definition of "unique". If the resource is determined to not be unique,				
	work may continue in the area. If the resource is determined to be unique, work will remain halted, and a				
	preservation or recovery plan will be prepared. Preservation in place is the preferred protective measure.				
	If preservation in place is not possible, resources and/or fossils will be recovered, prepared, identified,				
	catalogued and analyzed according to current professional standards under the direction of the qualified				
	paleontologist. Work may commence at the time of completion of the treatment. A final summary report				
	will be completed and submitted to the County. The report will include a discussion of the methods used,				
	stratigraphy exposed, fossils collected, and the significance of the recovered fossils. The report will also				
	include an itemized inventory of all the collected and catalogued fossil specimens.				

From: David Carlson

Sent: Friday, December 11, 2020 3:37 PM

To: David Carlson

Subject: FW: Public Comments: Environmental Impact Analysis of Davenport Cement Plant Closure

**Dust Plan** 

From: Alison Edwards <alison.edwards02@gmail.com>

**Date:** December 11, 2020 at 10:03:50 AM PST

To: Kathy Molloy < <a href="mailto:Kathy.Molloy@santacruzcounty.us">Kathy.Molloy@santacruzcounty.us</a>, Alison Edwards <a href="mailto:alison.edwards02@gmail.com">Alison.edwards02@gmail.com</a>> Subject: Public Comments: Environmental Impact Analysis of Davenport Cement Plant Closure Dust Plan

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

To: SC County Planning Director Kathy Molloy

From: Alison Edwards, resident at 101 San Vicente St, Davenport CA.

Dear Planning Director Molloy,

As a resident/homeowner of the town of Davenport just downwind of the cement plant, I am genuinely concerned about the current plans the county has to remediate the CKD pile on that property. I am happy that there is finally something being done about that CKD pile, clearly it needs to happen. But, I want to county, the state, and the owners of the cement plant to fix that CKD pile in a process which has the absolutely least impact on the health and well being of the current residents of Davenport. As you know - we have already had a very difficult time lately - with the fire here, as well as the pandemic and now with mandatory evacuations for debris flows throughout the winter. We need the County to work with us to make this CKD pile work happen in a way that does not negatively impact us.

Your current plan has a number of issues which must be adjusted in order to not adversely impact all of us who live here. My biggest concern is windblown dust. I was able to observe the area around the CKD pile a few weeks ago during windy conditions and there were very large plumes of dust being blown toward Old Town from the flat area inland of the pile and from around the water plant. If this is happening before disturbance I'm scared of what will occur when they're regrading the whole area.

The number one issue which needs to be addressed and adjusted is timing. Due to the very strong north winds which happen on the North Coast each Spring, doing the grading work on this pile during that time would have significant negative health impacts on all of us who live downwind of the CKD pile. As you know, that fine particulate matter is unhealthy, and that CKD dust does have some hazardous materials in it as

well. For both of those reasons, the timing of the grading of the CKT pile is the number one management issue of this project. Fall and Winter are the best times to do this work. Oct - Feb are the absolutely best months to do this work from this perspective. I believe that the county might have been avoiding those months due to avoidance of impact on red legged frogs. I understand and respect that, but while red legged frog habitat is important (though questionable on the highly industrial use land of the cement plant) - it should not take precedence over the physical health and well being of the people of the town of Davenport.

Your current plan puts this work being done during the windiest time of the year - spring through summer. That is unacceptable for those of us who live downwind from the CKD pile. If you insist on doing this work during those months (which I do not agree with) then the timing of the work should be adjusted so that it is ONLY done at night (when there is no wind). If the work was done from evening through the night and wrapping up by 10 am then it could possibly be done during the Spring/summer - if and only if the entire graded area was deeply watered down each morning to keep dust from impacting the town during the high winds which start each day around 10 am and last until dusk.

It appears that the planning process, as currently outlined, is primarily concerned with/focused on water quality. While important, water quality is not the biggest impact of this project on the residents of Davenport - rather, air quality is. The county needs to re-do this plan with air quality being front and center in the planning process. Fugitive dust has the potential to be a significant air quality health issue for the residents of Davenport. This plan needs to be re-made with every attempt to manage the project for the least air quality impact on those of us who live, work and go to school here.

As the plan currently stands - dust generating activities are upwind of much of Davenport. All activities will be during the dry (windy) season. This is likely due to the fact that the consultants did not use the best available science for background wind data. The data they cite are from 1998 (a strong La Nina year which has been associated with lower wind velocities in our area) and from non-overlapping window of months of the proposed activity: 6/13-11/20/1998 vs 4/1-10/31 (see attached from Appendix 5 Table 2-1 and Figure 2-6). These data are old and appear to be cherry picked (only 4 DAYS with winds over 15mphs during the entire time) - suggesting little potential impact on the Town of Davenport. We are all familiar with predominant of very strong NW daytime wind direction especially during the spring April 1 - Oct 31. I think the consultant should reference representative wind data.

In addition, the consultants do not mention dust and control of dust from the degraded plastic sheeting that is disintegrating atop the CKD

pile. Which becomes air born and rains down on the town of Davenport.

We have an elementary school downwind of these operations. The health of school students, teachers, and residents would be best protected with an adaptive management operations protocol where work occurs outside of high wind events with appropriate onsite dust mitigation (water hoses) not just on roads but on active operations where soil is scraped, dumped and transported.

When CEMEX removed the Ball Mill there was lots of fugitive dust that impacted the town of Davenport. They worked during some of the windiest days of that season. The structures that were removed contained significant amounts of dust and contained signage that said "Caution - Respirator Required for Entry". The contractor did not use hoses to water down the site to control dust. The trucks leaving the site were not tarped and billowed dust from Davenport all the way to the recycler's yard in South County. There were no monitoring stations. I could visually see the dust in the air, in our home, and feel it in my mouth and lungs.

The County must adapt this CKD project planning to avoid such air quality impacts going forward.

I have reviewed the Dust Monitoring Plan - Appendix 5 and they are using some poor data and questionable assumptions about wind speed that I believe need to be addressed. In particular, they use a wind speed study that was conducted at the "schoolhouse" (Presumably Pacific School) that was conducted June to November 1998. There are two obvious problems. First, Pacific school is protected from the prevailing winds from the eucalyptus forest to the North. Anyone with direct experience here knows wind speeds are much lower at the school than in open area such as the CKD pile. Second, Spring is the windiest time of year here, but the study was conducted during summer and fall and therefore does not represent actual conditions. The fact that best highlights that the wind study is not representative is that the study found only 4 days with wind speeds above 15 mph during 6 months of monitoring! Any quick glance at weather data shows this is very far from actual conditions.

I'm also concerned about the report's assumptions about the size of materials that are present at the site. This is not my area of expertise, but it appears that no field measurements were taken to establish the size of the materials, especially the CKD dust. Instead the study appears to assume a midpoint particle size based on previous studies conducted elsewhere. Smaller particles are blown more easily are the particles that will be exposed during this project large or small?

Incorrect information about the wind and no information about the size of local materials raises a red flag about the validity of this

mitigation plan. At a minimum these issues need to be addressed and the plan modified to accommodate the findings. In addition I recommend the county address the need to change the timing of the work (both time of year and time of day) as well as add significant planning to keep any portion of the disturbed CKD pile watered down multipal times a day. I also suggest that the plan be adapted so that portions of the CKT pile which are disturbed are capped or covered as by section as the work progresses - in order to keep those graded portions from releasing fugitive dust and creating unhealthy air quality for the residents of Davenport for the duration of the work.

Please keep us posted on how our concerns are being addressed and how the consultants and county will be changing the project plan to address the negative impacts outlined here.

Thank you so much,

Alison Edwards

101 San Vicente St, Davenport CA

From: **David Carlson** 

Sent: Monday, December 7, 2020 2:34 PM

To: **David Carlson** 

Subject: FW: Comments on Davenport North Cement Kiln Dust Area Closure Project

# Begin forwarded message:

From: Brian McElroy <a href="mailto:briancareymcelroy@gmail.com">briancareymcelroy@gmail.com</a>

Date: December 3, 2020 at 2:10:11 PM PST

To: Kathy Molloy < Kathy. Molloy@santacruzcounty.us >

Subject: Comments on Davenport North Cement Kiln Dust Area Closure Project

\*\*\*\*CAUTION: This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

Santa Cruz County Planning Department Planning Director Kathy Molloy 701 Ocean Street, 4th Floor Santa Cruz, CA 95060

Via email at kathy.molloy@santacruzcounty.us

**Brian McElroy** 13 First Ave. Davenport, CA 95017

briancarevmcelrov@gmail.com

Comments on Initial Study Davenport North Cement Kiln Dust Area Closure Project

I only became aware of this plan on 12/3 – the day before comments were due. I am supportive of the project to remediate the Kiln Dust pile, but would like to better understand the project and be better informed. This late notification precludes any sort of careful analysis or input. However, I have comments below from other community members and my own review of the documents.

 There has been insufficient notification of the local stakeholders (residents, businesses, local school) to allow careful study and timely comments. I request an extension of the comment period to allow sufficient public input. My home is adjacent to the Cement Plan Property on First Ave, only separated by the road. Perhaps this is not technically "adjacent" but I protest the lack of notification. Please provide me with a list of all parties notified of this action. If I was notified and failed to acknowledge the notice then I stand corrected.

- 2. There has been insufficient assessment of the characteristics of the material to be mitigated. The CKD pile has been covered for years with a combination of petroleum-based plastic tarping and used tires. What is the potential for this material to become suspended during operations, what are the potential health effects, and will they be properly mitigated. The consultants do not mention dust and control of dust from the degraded plastic sheeting that is disintegrating atop the CKD pile. Which becomes air born and rains down on the town of Davenport.
- 1. There has not been a direct analysis of the CKD material. It appears instead that an analysis of similar material from another location has formed the basis of the prediction of the physical quality of the material likely forming dust during operations. This is inadequate as particle sizes and composition is likely different at the RMC site in Davenport compared to the material presented in the analysis.
- 2. The data on wind are severely outdated (climate models are showing intensification of NW winds in the Central California coastal region), based upon a location that does not represent what will be present at the mitigation site (the wind-protected "schoolhouse" site rather than the actual mitigation site), seasonally incorrect (Summer/Fall rather than Spring), and taken from an anomalous year (La Nina – 1998). It is well established that the strongest and most consistent winds occur in the area in the Spring between March and June. However, the wind data used in the analysis was from the LEAST windy period in the region (June-November - Summer/Fall). We understand the mitigation effort will occur during the Spring season (April-October). Specifically, the consultants do not use the best available science for background wind data. The data they cite are from 1998 (a strong La Nina year which has been associated with lower wind velocities in our area) and from non-overlapping window of months of the proposed activity: 6/13-11/20/1998 vs 4/1-10/31 (see attached from Appendix 5 Table 2-1 and Figure 2-6). Indeed, these old data appear to be cherry picked (only 4 DAYS with winds over 15mphs during the entire time) - suggesting little potential impact on the Town of Davenport. We are all familiar with predominant NW daytime wind direction especially during the spring April 1 - Oct 31. More representative wind data should be used.
- 3. Dust mitigation plan. We have an elementary school downwind of these operations. The health of school students, teachers, and residents would be best protected with an adaptive management operations protocol where work occurs outside of high wind events with appropriate onsite dust mitigation (water hoses) not just on roads but on active operations where soil is scraped, dumped and transported. Our experience when CEMEX removed the Ball Mill was that there was significant fugitive dust that impacted the town of Davenport. Indeed, the work was conducted during some of the windiest days of that season. The structures that were removed contained significant amounts of dust and contained signage that said "Caution Respirator Required for Entry". The contractor did not use hoses to water down the site to control dust. The trucks leaving the site were not tarped and billowed dust from Davenport all the way to the recycler's yard in South County. There were no monitoring stations. I could visually see the dust in the air, in our home, and feel it in my mouth and lungs. We are fearful of a similar scenario developing under this plan with inadequately defined timing and dust mitigation procedures.

4. Traffic planning. The project will require a significant amount of heavy truck traffic. The reports does not address impacts on Cement Plant Road. The report could define measures to be taken to reduce traffic on Cement Plant Road and avoid residential areas at First and Third Avenues. The report addresses impacts to HWY 1 and Warrannela Road but fails to mitigate dust, and safety concerns. What measures will be taken to reduce dust from truck loads, tires and truck bodies?

As mentioned above, these comments have been developed with the most cursory review of the proposal due to the inadequate prior nofication. I respectfully request an extension of 30 days to allow our community to more fully assess this important and impactful activity likely to affect the quality and health of our community, school, and businesses. Thank you for your time and effort reading my comments.

Brian McElroy

From: Clint Biddle <clintjbiddle@gmail.com>
Sent: Tuesday, January 19, 2021 10:53 AM

To: David Carlson
Subject: CEMEX CKD Project

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

Hi David,

I live on First Avenue in Davenport and plan to attend, and would like to briefly speak/comment at, the public phone call meeting tomorrow (1/20) at 5pm regarding the implementation of the final North CKD Area Closure Plan at the former Davenport Cement Plant.

While I support the project, I have significant concern at the prospect of the trucks passing by the "Newtown" neighborhood (1st, 2nd, and 3rd Avenues) of Davenport along Cement Plant Road and the associated noise, traffic and CKD that is likely to blow off of the trucks as they pass our neighborhood.

I think that the trucks should either have to exit through the Cement Plant's main entrance/exit near highway 1, or if they must go down Waranella Road they should only be on Cement Plant Road for the short distance between the Warrenella Road gate and the railroad crossing entrance to highway 1 just south of the gate. They will then only be on Cement Plant Road for 40 yards give or take and will not pass by the Newtown neighborhood. That entrance to highway 1 has much better visibility and runway for big slow trucks then the ones south of Newtown anyway making it safer all around.

I am also concerned about:

- Dust impacts from excavation, fill dumping, and grading.
- Impacts to current drainage issues that are eroding the hill behind New Town.

Thank you, Clint Biddle 1st Avenue Davenport, CA

From: Kathy Molloy

Sent: Saturday, December 19, 2020 12:23 AM

**To:** David Carlson

**Subject:** Fwd: Davenport Cement Plant Closure Dust Plan

### Begin forwarded message:

From: Clint Biddle <clintjbiddle@gmail.com>
Date: December 18, 2020 at 11:12:42 PM PST

To: Kathy Molloy < Kathy. Molloy@santacruzcounty.us> Subject: Davenport Cement Plant Closure Dust Plan

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

Hello Kathy,

My name is Clint Biddle and I am a resident of New Town, Davenport.

I have read over the comments on the Plant Mitigation Study done by the DNCA and strongly agree with their points below:

- 1. There has been insufficient notification of the local stakeholders (residents, businesses, local school) to allow careful study and timely comments. DNCA strongly urges an extension of the comment period to allow sufficient public input.
- 2. There has been insufficient assessment of the characteristics of the material to be mitigated. The CKD pile has been covered for years with a combination of petroleum-based plastic tarping and used tires. What is the potential for this material to become suspended during operations, what are the potential health effects, and will they be properly mitigated. The consultants do not mention dust and control of dust from the degraded plastic sheeting that is disintegrating atop the CKD pile. Which becomes air born and rains down on the town of Davenport.
- 3. There has not been a direct analysis of the CKD material. It appears instead that an analysis of similar material from another location has formed the basis of the prediction of the physical quality of the material likely forming dust during operations. This is inadequate as particle sizes and composition is likely different at the RMC site in Davenport compared to the material presented in the analysis.
- 4. The data on wind are severely outdated (climate models are showing intensification of NW winds in the Central California coastal region), based upon a location that does not represent what will be present at the mitigation site (the wind-protected "schoolhouse" site rather than the actual mitigation site), seasonally incorrect (Summer/Fall rather than Spring), and taken from an anomalous year (La Nina 1998). It is well established that the strongest and most consistent winds occur in the area in the Spring between March and June. However, the wind data used in the analysis was from the LEAST windy period in the region (June-November Summer/Fall). We understand the mitigation effort will occur during the Spring season (April-October). Specifically, the consultants do not use the best available science for background wind data. The data they cite are from 1998 (a strong La Nina year which has been associated with lower wind

velocities in our area) and from non-overlapping window of months of the proposed activity: 6/13-11/20/1998 vs 4/1-10/31. Indeed, these old data appear to be cherry picked (only 4) **DAYS** with winds over 15mphs during the entire time) - suggesting little potential impact on the Town of Davenport. We are all familiar with predominant NW daytime wind direction especially during the spring April 1 - Oct 31. More representative wind data should be used. Dust mitigation plan. We have an elementary school downwind of these operations. The health of school students, teachers, and residents would be best protected with an adaptive management operations protocol where work occurs outside of high wind events with appropriate onsite dust mitigation (water hoses) not just on roads but on active operations where soil is scraped, dumped and transported. Our experience when CEMEX removed the Ball Mill was that there was significant fugitive dust that impacted the town of Davenport, Indeed, the work was conducted during some of the windiest days of that season. The structures that were removed contained significant amounts of dust and contained signage that said "Caution - Respirator Required for Entry". The contractor did not use hoses to water down the site to control dust. The trucks leaving the site were not tarped and billowed dust from Davenport all the way to the recycler's yard in South County. There were no monitoring stations. I could visually see the dust in the air, in our home, and feel it in my mouth and lungs. We are fearful of a similar scenario developing under this plan with inadequately defined timing and dust mitigation procedures. Our understanding based upon our read of the process and requirements is that properties considered "contiguous" we be notified of the process and plan with opportunity for comment. None of the Davenport residents contacted by the DNCA had received notification of the plan. This seems to violate the regulatory requirements of the process.

Thank you for your consideration, Clint Biddle Resident at 9 1st Ave., Davenport, CA, 95017

From: Colin Hannon <colinhannon@cruzio.com>
Sent: Monday, January 18, 2021 9:13 PM

**To:** David Carlson

**Subject:** Davenport CKD closure comments/concerns

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

### Dear David.

I am a homeowner in New Town, Davenport adjacent to the project site where I live with my wife and 2 young children. We are concerned about dust, traffic, and noise connected with the Davenport CKD project. I was grateful to be on the very informative zoom call recently where information was shared with local residents and the DNCA etc. The amount of planned earthmoving and its potential to create dust, traffic, and noise that could significantly impact our neighborhood was concerning. The Cemex representative said in that meeting that their goal was 'no dust whatsoever' leaving the site. This seems unrealistic and leads one to wonder if other mitigations in the plan are realistic and adequate. We are very glad that this site is going to be cleaned up, and hopeful that every effort will be made to ensure that it is safe for Davenport residents and that any negative impacts will be minimized and mitigated adequately. Thank you for you time and consideration.

Best, Colin Hannon 831-345-4372 20 3rd Ave Davenport, CA 95017

From: Courtney Scruggs <courtneyrscruggs@gmail.com>

**Sent:** Monday, January 18, 2021 11:27 AM

**To:** David Carlson

**Subject:** CKD Pile - Davenport Cement Plant

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

Hello David,

First, I want to thank you for heading this and tell you how excited we are that this is being managed!

As a resident of New Town Davenport I *am* a bit concerned with the dust, traffic and damage that may be done to our road. We are hoping that the dust will be mitigated with water trucks especially with our high winds in the spring time and the truck drivers will be warned that they are driving through an area with neighbors, kids and lots of pets. We are a tight knit community and would love it if the people working on this project could treat this as if it were their neighborhood and take it slow. When they put in the pond just north of us, they severely damaged the road and when it was over, they did repairs as necessary. I am hoping there is a plan to do the same on this project.

I am one of many who live and work out of the house here in New Town so my hope is that we will not be too impacted by this clean up process. Thank you again for your hard work and I look forward to seeing you on the call scheduled for the 20th.

Best regards, Courtney Scruggs

Resident of: 8 3rd Ave. Davenport, CA, 95017

--

Courtney Renee Scruggs P.O. Box 167 Davenport, CA, 95017 CourtneyRScruggs@gmail.com (831) 205- 0285

http://www.courtneyrenees.com

https://www.instagram.com/courtneyrenees/https://www.facebook.com/courtneyreneescruggs

From: Kathy Molloy

Sent: Saturday, December 19, 2020 12:21 AM

**To:** David Carlson

**Subject:** Fwd: CKD Pile Comments - Davenport

#### Begin forwarded message:

From: Courtney Scruggs < courtneyrscruggs@gmail.com>

Date: December 18, 2020 at 9:14:41 PM PST

To: Kathy Molloy < Kathy. Molloy@santacruzcounty.us>

**Subject: CKD Pile Comments - Davenport** 

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

# Hello Kathy,

My name is Courntey Scruggs and I am a resident of New Town, Davenport. It has come to my attention that there is a severe lack of information/planning associated with the proposed cleanup of the CKD pile on the Cemex property. I can literally see it out of my kitchen window so, as thrilled as I am that it is going to be cleaned up, I am concerned with the process being dangerous for our residents.

I have read over the comments on the Plant Mitigation Study and comments by the DNCA and Noel and strongly agree with their points as noted below.

- 1. There has been insufficient notification of the local residents to allow careful study and timely comments. I am requesting an extension of at least 30 days to allow our community to assess the impact of this activity likely to affect us.
- 2. There has been insufficient assessment of material to be cleaned up. I have lived here for 5 years and seen plenty of tarp, plastic and other debris flying away in the 30+ knots of breeze we see here in Davenport.
- 3. As stated in section 2, our winds can be unruly here and based on what time of day and what time of year, wind models could be inaccurate. There is a reason we are known as the windsurfing capital of the world. I would like to suggest a cap of 10 knots of wind in order to contain the debris that floats down on Davenport. I was not a resident when the Cement plant was in operation but I have heard horror stories of cars being covered in cement dust and would hate to see something like that happen again especially considering the legal battle that ensued causing Cemex to compensate residents and provide car covers. It would be unfortunate to see history repeat itself.
- 5. Dust mitigation plan. We have an elementary school and the heart of the town downwind of these operations. The health of residents would be best protected with proper watering prior to removal of the debris to keep down dust and other airborne particulates.

I know how hard it is to make everyone happy in matters like these but we're a small town of very loyal and caring residents and we've already dealt with a lot this year from Covid to the fires and potentially mudslides this winter. It would be nice to see things go smoothly in this operation with a little careful planning and we would all be eternally grateful for your kindness. This is our home and we would greatly appreciate it if you could remember that when considering how to go forward with this proposal.

Thank you for your consideration, Courtney Scruggs Resident at 8 3rd Ave., Davenport, CA, 95017

--

Courtney Renee Scruggs
P.O. Box 167
Davenport, CA, 95017
CourtneyRScruggs@gmail.com
(831) 205- 0285

http://www.courtneyrenees.com

https://www.instagram.com/courtneyrenees/ https://www.facebook.com/courtneyreneescruggs

From: Kathy Molloy

Sent: Saturday, December 19, 2020 12:21 AM

**To:** David Carlson

**Subject:** Fwd: CKD Pile Restoration Project Davenport, Ca.

## Begin forwarded message:

From: Eric Ruderman <rudy161@gmail.com> Date: December 18, 2020 at 8:54:11 PM PST

To: Kathy Molloy < Kathy. Molloy@santacruzcounty.us> Subject: CKD Pile Restoration Project Davenport, Ca.

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

Kathy,

I am just becoming aware of this restoration project this evening, the last evening to comment. Was there a community outreach program that I somehow missed? The community that will be effected should know all the details sooner than later. In this case, it seems to be later.

There are many valid concerns about the CKD pile, inaccurate wind data used, risk assessment to the local community, as well a study of the actual pile for particulate make up and size. As a home owner in Davenport - 6 3rd Ave. I am voicing my concerns to you to be addressed and mitigated before the restoration project is underway.

We need you to at minimum, to water down the pile before, during and after any movement of materials to help limit airborne particulates.

Please update your wind data with accurate readings from proposed period - Spring, which is by far the winiest season here.

Your decisions will impact the health and safety of our community. We all want the pile dealt with, but it needs to happen with the safety of the community at the forefront.

Sincerely,

Eric Ruderman

**From:** David Carlson

Sent: Friday, December 11, 2020 3:38 PM

**To:** David Carlson

Subject: FW: Public Comments: Environmental Impact Analysis of Davenport Cement Plant Closure Dust Plan

### Begin forwarded message:

From: Josto Puddu < jpuddu@ucsc.edu > Date: December 11, 2020 at 10:25:54 AM PST

To: Kathy Molloy <Kathy.Molloy@santacruzcounty.us>

Subject: Public Comments: Environmental Impact Analysis of Davenport Cement Plant Closure Dust

Plan

\*\*\*\*CAUTION: This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

## Dear Planning Director Molloy,

I am an homeowner in the town of Davenport just <u>downwind</u> of the cement plant, I am very concerned about the current plans the county has to remediate the CKD pile on that property.

I am happy that there is finally something being done about it.

But, I want to county, the state, and the owners of the cement plant to fix that CKD pile in a process which has the absolutely least impact on the health and well being of the current residents of Davenport.

As you know - we have already had a very difficult time lately - with the fire here, as well as the pandemic and now with mandatory evacuations for debris flows throughout the winter. We need the County to work with us to make this CKD pile work happen in a way that does not negatively impact us, now or in long term health risks.

Your current plan has a number of issues which must be adjusted in order to not adversely impact all of us who live here.

The concern is windblown dust. I was able to observe the area around the CKD pile a few weeks ago during windy conditions and there were very large plumes of dust being blown toward Old Town from the flat area inland of the pile and from around the water plant.

If this is happening before disturbance I'm scared of what will occur when they're regrading the whole area. [3]

The number one issue which needs to be addressed and adjusted is mainly the timing.

Due to the very strong north winds which happen on the North Coast each Spring, doing the grading work on this pile during that time would have significant negative health impacts on all of us who live downwind of the CKD pile.

As you know, that fine particulate matter is unhealthy, and that CKD dust does have some hazardous materials in it as well. For both of those reasons, the timing of the grading of the CKT pile is the number one management issue of this project.

Fall and Winter are the best times to do this work. Oct - Feb are the absolutely best months to do this work from this perspective.

I believe that the county might have been avoiding those months due to avoidance of impact on red legged frogs.

I understand and respect that, but while red legged frog habitat is important (though questionable on the highly industrial use land of the cement plant) - it should not take precedence over the physical health and well being of the people of the town of Davenport.

Your current plan puts this work being done during the windiest time of the year - spring through summer.

That is simply unacceptable for those of us who live downwind from the CKD pile.

If you insist on doing this work during those months (which I do not agree with) then the timing of the work should be adjusted so that it is ONLY done at night (when there is no wind). If the work was done from 8pm through the night and wrapping up by 6 am then it could possibly be done during the Spring/summer - if and only if the entire graded area was deeply watered down each morning to keep dust from impacting the town during the high winds which start each day around 10 am and last until dusk.

It appears that the planning process, as currently outlined, is primarily concerned with/focused on water quality. While important, water quality is not the biggest impact of this project on the residents of Davenport - rather, air quality is. The county needs to re-do this plan with air quality being front and center in the planning process. Fugitive dust has the potential to be a significant air quality health issue for the residents of Davenport. This plan needs to be re-made with every attempt to manage the project for the least air quality impact on those of us who live, work and go to school here.

As the plan currently stands - dust generating activities are upwind of much of Davenport. All activities will be during the dry (windy) season.

This is likely due to the fact that the consultants did not use the best available science for background wind data. The data they cite are from 1998 (a strong La Nina year which has been associated with lower wind velocities in our area) and from non-overlapping window of months of the proposed activity: 6/13-11/20/1998 vs 4/1-10/31 (see attached from Appendix 5 Table 2-1 and Figure 2-6). These data are old and appear to be cherry picked (only 4 DAYS with winds over 15mphs during the entire time) - suggesting little potential impact on the Town of Davenport. We are all familiar with predominant of very strong NW daytime wind direction especially during the spring April 1 - Oct 31. I think the consultant should reference representative wind data.

In addition, the consultants do not mention dust and control of dust from the degraded plastic sheeting that is disintegrating atop the CKD pile. Which becomes air born and rains down on the town of Davenport.

We have an elementary school downwind of these operations. The health of school students, teachers, and residents would be best protected with an adaptive management operations protocol where work occurs outside of high wind events with appropriate onsite dust mitigation (water hoses) not just on roads but on active operations where soil is scraped, dumped and transported.

When CEMEX removed the Ball Mill there was lots of fugitive dust that impacted the town of Davenport. They worked during some of the windiest days of that season. The structures that were removed contained significant amounts of dust and contained signage that said "Caution - Respirator Required for Entry". The contractor did not use hoses to water down the site to control dust. The trucks leaving the site were not tarped and billowed dust from Davenport all the way to the recycler's yard in South County. There were no monitoring stations. I could visually see the dust in the air, in our home, and feel it in my mouth and lungs.

The County must adapt this CKD project planning to avoid such air quality impacts going forward.

I have reviewed the Dust Monitoring Plan - Appendix 5 and they are using some poor data and questionable assumptions about wind speed that I believe need to be addressed. In particular, they use a wind speed study that was conducted at the "schoolhouse" (Presumably Pacific School) that was conducted June to November 1998. There are two obvious problems. First, Pacific school is protected from the prevailing winds from the eucalyptus forest to the North. Anyone with direct experience here knows wind speeds are much lower at the school than in open area such as the CKD pile. Second, Spring is the windiest time of year here, but the study was conducted during summer and fall and therefore does not represent actual conditions. The fact that best highlights that the wind study is not representative is that the study found only 4 days with wind speeds above 15 mph during 6 months of monitoring! Any quick glance at weather data shows this is very far from actual conditions.

I'm also concerned about the report's assumptions about the size of materials that are present at the site. This is not my area of expertise, but it appears that no field measurements were taken to establish the size of the materials, especially the CKD dust. Instead the study appears to assume a midpoint particle size based on previous studies conducted elsewhere. Smaller particles are blown more easily - are the particles that will be exposed during this project large or small?

Incorrect information about the wind and no information about the size of local materials raises a red flag about the validity of this mitigation plan. At a minimum these issues need to be addressed and the plan modified to accommodate the findings. In addition I recommend the county address the need to change the timing of the work (both time of year and time of day) as well as add significant planning to keep any portion of the disturbed CKD pile watered down multipal times a day. I also suggest that the plan be adapted so that portions of the CKT pile which are disturbed are capped or covered as by section as the work progresses - in order to keep those graded portions from releasing fugitive dust and creating unhealthy air quality for the residents of Davenport for the duration of the work.

Please keep us posted on how our concerns are being addressed and how the consultants and county will be changing the project plan to address the negative impacts outlined here.

Thank you so much, losto Saleri Puddu

101 San Vicente St, Davenport CA

\_\_

Josto Saleri Puddu UCSC Dining Business Systems Analyst Cell (831)212-5003 Office (831)459-5236

From: David Carlson

Sent: Tuesday, December 22, 2020 2:49 PM

**To:** David Carlson

**Subject:** FW: Davenport CKD Closure proposal -Public Comments

## Begin forwarded message:

From: kasha forgette < kashaforgettelac@gmail.com > Date: December 17, 2020 at 11:09:28 PM PST

To: Kathy Molloy < <a href="mailto:Kathy.Molloy@santacruzcounty.us">Kathy.Molloy@santacruzcounty.us</a> Subject: Davenport CKD Closure proposal -Public Comments

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

#### Kathy,

Hi this is Kasha Forgette And I have been a Davenport residence for many years. I would like to leave my public comment about the CKD closure proposal 2020 in Davenport.

I read through the report and am extremely concerned about 4 things. I believe for the health and safety of our community and children That these 4 things need to be addressed and that the proposal needs to include ways to mitigate these hazards to public health before this proposal moves forward.

1. When the CKD pile is grated It needs to be wetted down constantly to prevent dust and small particles of hazardous waste from reaching the elementary school 1/4 mile away. The school and community of Davenport is directly down wind from the CKD pile.

There needs to also be an over site group making sure the wetting down gets done and that the contractors are Fallowing all safety protocols.

2. A level of acceptable wind knots for grating needs to be decided. For the safety and well being of the children at the school and the residents of Davenport. If the wind reaches over The safety threshold in knots the grating has to be postponed until wind levels come down. There needs to be an over site group to make sure This is being fallowed.

The wind data in the report was majorly flawed and not consistent with the Actual conditions on the north coast of Santa Cruz. The proposed time of year for the project is our windiest time of year. The north coast of santa Cruz has Extreme wind and can last dawn to dusk for days on end. The elementary school and town Of Davenport are directly down wind from the proposed CKD Project and if it is a windy day like we get up here most days the proposed grating of the CKD pile will cause major health risks to our children and community. These include A huge exposure to dust from the grating, exposure to hazardous materials in the CKD pile ( listed as a hazardous materials site in 2019 for Santa Cruz county), both dust and hazardous materials in our water supply.

3. Our drinking water supply comes mostly from San Vicente creek which is downwind from the Proposed grating of the CKD Pile.

4. Particle size of material from the proposed CKD pile grating that will become airborne was not properly established or addressed in the report.

As residents of Davenport we would all like the CKD pile to be dealt with in the best way possible. However This proposal does not use Accurate data That is applicable When addressing the effect the grating of the CKD pile will have on the down wind community of Davenport, And the health and safety of the elementary school children 1/4 mile away.

The data does not truly represent the wind conditions here in Davenport, the amount of dust and hazardous materials that will blow down wind to the residents and Elementary school children, or into our drinking water supply. Nor does it address accurately the size of the dust and waste particles generated from the grating.

I strongly disagree with the statements on pages 94, 96, and 98 and feel that this project is a significant risk to the health and safety of the public and children of our community, and drinking water supply.

I think that the data in appendix 5 and 10 is not accurate and should be reconsidered.

If Safety measures Like spraying down the CKD pile with water while grating and only grating if wind is under certain knots in strength were implemented this project could pose less risk to the public health and safety in Davenport.

I ultimately think that the wind levels, particle size of the CKD pile material and impacts on drinking water and Risks of inhalation of this dust for adults and elementary school children Be further studied before this report or plan gets approved or moves forward.

Thank you for your time,

Kasha

--

Warmly,

Kasha Forgette, LAC

(831) 239-1948 kashaforgettelac@gmail.com

This email and any attachments thereto may contain private, confidential, and privileged material for the sole use of the intended recipient. Any review, copying, or distribution of this email (or any attachments thereto) by others is strictly prohibited. If you are not the intended recipient, please contact the sender immediately and permanently delete the original and any copies of this email and any attachments thereto.

From: Kathy Molloy

Sent: Saturday, December 19, 2020 12:22 AM

**To:** David Carlson

**Subject:** Fwd: CKD Pile in Davenport

#### Begin forwarded message:

From: Maria Fernandez <bodyworkbymariaf@gmail.com>

Date: December 18, 2020 at 9:57:50 PM PST

To: Kathy Molloy < Kathy. Molloy@santacruzcounty.us>

**Subject: CKD Pile in Davenport** 

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

# Hi Kathy,

I am a resident of New Town in Davenport. It is very exciting to hear about plans to take care of the CKD pile. However there is some concern about the proposal and key missing information.

I strongly agree with their points as noted below on the Plant Mitigation Study done by the DNCA and Noel.

- 1. There has been insufficient notification of the local residents to allow careful study and timely comments. DNCA strongly urges an extension of the comment period to allow sufficient public input. I am requesting an extension of at least 30 days to allow our community to assess the impact of this activity likely to affect us.
- 2. There has been insufficient assessment of material to be cleaned up. I have lived here for 5 years and seen plenty of tarp, plastic and other debris flying away in the 30+ knots of breeze we see here in Davenport.
- 3. As stated in section 2, our winds can be unruly here and based on what time of day and what time of year, wind models could be inaccurate. There is a reason we are known as the windsurfing capital of the world. I would like to suggest a cap of 10 knots of wind in order to contain the debris that floats down on Davenport. I was not a resident when the Cement plant was in operation but I have heard horror stories of cars being covered in cement dust and would hate to see something like that happen again especially considering the legal battle that ensued causing Cemex to compensate residents and provide car covers. It would be unfortunate to see history repeat itself.
- 5. Dust mitigation plan. We have an elementary school and the heart of the town downwind of these operations. The health of residents would be best protected with proper watering prior to removal of the debris.

We would love to see this project in action along with addressing our concerns for the health and wellness of our community and environment.

Thank you so much,

Maria Fernandez 9 1st Ave Davenport

From: Kathy Molloy

Sent: Saturday, December 19, 2020 12:21 AM

To: David Carlson

**Subject:** Fwd: Davenport CKD pile cleanup

#### Begin forwarded message:

From: Melissa Sullivan <scboardrider@gmail.com>
Date: December 18, 2020 at 9:17:47 PM PST
To: Kathy Molloy <Kathy.Molloy@santacruzcounty.us>

Subject: Davenport CKD pile cleanup

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email. \*\*\*\*

#### Hello Kathy,

My name is Melissa Sullivan and I am a resident of New Town, Davenport. It has come to my attention that there is a severe lack of information associated with the proposed cleanup of the CKD pile on the Cemex property. I can literally see it out of my kitchen window so as thrilled as I am that it is going to be cleaned up, I am concerned with the process being dangerous for our residents.

I have read over the comments on the Plant Mitigation Study done by the DNCA and Noel and strongly agree with their points as noted below.

- 1. There has been insufficient notification of the local residents to allow careful study and timely comments. DNCA strongly urges an extension of the comment period to allow sufficient public input. I am requesting an extension of at least 30 days to allow our community to assess the impact of this activity likely to affect us.
- 2. There has been insufficient assessment of material to be cleaned up. I have lived here for 5 years and seen plenty of tarp, plastic and other debris flying away in the 30+ knots of breeze we see here in Davenport.
- 3. As stated in section 2, our winds can be unruly here and based on what time of day and what time of year, wind models could be inaccurate. There is a reason we are known as the windsurfing capital of the world. I would like to suggest a cap of 10 knots of wind in order to contain the debris that floats down on Davenport. I was not a resident when the Cement plant was in operation but I have heard horror stories of cars being covered in cement dust and would hate to see something like that happen again especially considering the legal battle that ensued causing Cemex to compensate residents and provide car covers. It would be unfortunate to see history repeat itself.
- 5. Dust mitigation plan. We have an elementary school and the heart of the town downwind of these operations. The health of residents would be best protected with proper watering prior to removal of the debris.

I know how hard it is to make everyone happy in matters like these but we're a small town of very loyal and caring residents and we've already dealt with a lot this year from Covid to the fires and potentially mudslides this winter. It would be nice to see things go smoothly in this

1

operation with a little careful planning and we would all be eternally grateful for your kindness. This is our home and we would greatly appreciate it if you could remember that when considering how to go forward with this proposal.

Thank you for your consideration, Melissa Sullivan Resident at 6 3rd Ave., Davenport, CA, 95017 831-251-2526

--

×

ReplyForward

From: David Carlson

Sent: Tuesday, December 22, 2020 3:07 PM

**To:** David Carlson

**Subject:** FW: Davenport North Cement Kiln Dust Closure Project #28372

From: Noel Bock < ngbock@icloud.com > Sent: Thursday, December 3, 2020 12:02 PM

To: Kathy Molloy < Kathy. Molloy@santacruzcounty.us >

Subject: Davenport North Cement Kiln Dust Closure Project #28372

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

Planning Director Kathy Molloy,

We were surprised to hear about the Cement Plant CKD Closure Plan Public Comment Period ending tomorrow. We request the community of Davenport, NewTown and Pacific Elementary School be notified of updates on the planning for this mitigation operation. We have not seen any notification except by searching the Planning Department website.

After Supervisor Ryan Coonerty held the CKD Q&A meeting in February 2017 for the Davenport community, the Regional Water Board stated:

- ... If allowed to remain in place, it is expected that the North CKD Area will be regraded to mimic the adjacent sloping hilly terrain to make it easier to construct an engineered final cover. Although to a lesser extent, this work will also result in potential fugitive dust and greenhouse gas emissions that will need to be mitigated via oversight by other agencies.
- ...The Final Closure Plan is also required to include an assessment of the Retention Pond and associated drainages, including characterization of the sediments, and a corrective action plan as needed to mitigate any water quality threats.
  - We request the Davenport North Coast Association (DNCA) be notified what agency(s) will be monitoring
    fugitive dust, gas emissions, and water quality during and after this mitigation.
  - We request the DNCA be notified of the mitigation timeline.
  - Since we were not told about the Cement Plant CKD Closure Plan Public Comment Period, would it be possible to extend the deadline beyond tomorrow 12/4?

Thank you,
Noel Garin Bock
Davenport North Coast Association
ngbock@icloud.com
831-332-0646 cell

From: Noel Bock <ngbock@icloud.com>
Sent: Thursday, December 3, 2020 2:58 PM

To: Kathy Molloy

**Cc:** David Carlson; Rachel Dann; Brian McElroy

**Subject:** Re: Davenport North Cement Kiln Dust Closure Project #28372

\*\*\*\*CAUTION:This is an EXTERNAL email. Exercise caution. DO NOT open attachments or click links from unknown senders or unexpected email.\*\*\*\*

Kathy,

Thank you for you quick response and for extending the deadline.

Board member, Brian McElroy, would like to take advantage of the opportunity to meet with David Carlson to better understand the affects especially on NewTown. He will be in touch with you.

None-the-less, I would like to forward you the comments made by a board member for your consideration.

DNCA Draft Comments on Cement Plant Mitigation Study/Plan

The DNCA and local community only became aware of this plan on 12/3 – the day before comments were due. This late notification precludes any sort of careful analysis or input. However, DNCA distributed the plan to a limited number of residents living adjacent to the mitigation site (Old Town and New Town Davenport) as well as the Pacific Elementary School Superintendent and some School Board Members. A summary of our rapidly-accumulated comments from this group of local stakeholders include:

- 1. There has been insufficient notification of the local stakeholders (residents, businesses, local school) to allow careful study and timely comments. DNCA strongly urges an extension of the comment period to allow sufficient public input.
- 2. There has been insufficient assessment of the characteristics of the material to be mitigated. The CKD pile has been covered for years with a combination of petroleum-based plastic tarping and used tires. What is the potential for this material to become suspended during operations, what are the potential health effects, and will they be properly mitigated? The consultants do not mention dust and control of dust from the degraded plastic sheeting that is disintegrating atop the CKD pile. Which becomes air born and rains down on the town of Davenport.
- 3. There has not been a direct analysis of the CKD material. It appears instead that an analysis of similar material from another location has formed the basis of the prediction of the physical quality of the material likely forming dust during operations. This is inadequate as particle sizes and composition is likely different at the RMC site in Davenport compared to the material presented in the analysis.
- 4. The data on wind are severely outdated (climate models are showing intensification of NW winds in the Central California coastal region), based upon a location that does not represent what will be present at the mitigation site (the wind-protected "schoolhouse" site rather than the actual mitigation site), seasonally incorrect (Summer/Fall rather than Spring) and taken from an anomalous year (La Nina 1998). It is well established that the strongest and most consistent winds occur in the area in the Spring between March and June. However, the wind data used in the analysis was from the LEAST windy period in the region (June-November Summer/Fall). We understand the mitigation effort will occur during the Spring season (April-October). Specifically, the consultants do not use the best available science for background wind data. The data they cite are from 1998 (a strong La Nina year which has been associated with lower

wind velocities in our area) and from non-overlapping window of months of the proposed activity: 6/13-11/20/1998 vs 4/1-10/31 (see attached from Appendix 5 Table 2-1 and Figure 2-6). Indeed, these old data appear to be cherry picked (only 4 DAYS with winds over 15mphs during the entire time) - suggesting little potential impact on the Town of Davenport. We are all familiar with predominant NW daytime wind direction especially during the spring April 1 - Oct 31. More representative wind data should be used.

- 5. Dust mitigation plan. We have an elementary school downwind of these operations. The health of school students, teachers, and residents would be best protected with an adaptive management operations protocol where work occurs outside of high wind events with appropriate onsite dust mitigation (water hoses) not just on roads but on active operations where soil is scraped, dumped and transported. Our experience when CEMEX removed the Ball Mill was that there was significant fugitive dust that impacted the town of Davenport. Indeed, the work was conducted during some of the windiest days of that season. The structures that were removed contained significant amounts of dust and contained signage that said "Caution Respirator Required for Entry". The contractor did not use hoses to water down the site to control dust. The trucks leaving the site were not tarped and billowed dust from Davenport all the way to the recycler's yard in South County. There were no monitoring stations. I could visually see the dust in the air, in our home, and feel it in my mouth and lungs. We are fearful of a similar scenario developing under this plan with inadequately defined timing and dust mitigation procedures.
- 6. Our understanding based upon our read of the process and requirements is that properties considered "contiguous" we should be notified of the process and plan with opportunity for comment. None of the Davenport residents contacted by the DNCA had received nonfiction of the plan. This seems to violate the regulatory requirements of the process.

As mentioned above, these comments have been developed with the most cursory review of the proposal due to the inadequate prior nonfiction. We respectfully request an extension of 30 days to allow our community to more fully assess this important and impactful activity likely to affect the quality and health of our community, school, and businesses

Thank you for your time, Noel Garin Bock Davenport North Coast Association ngbock@icloud.com 831-332-0646 cell